



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L043 - T02 CHOTA RAGHUNATHPUR TO KARIMULLAPUR DAKSHIN (VR43) DIVERSION 1 ST CUT

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 125	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	0.125	KM
TOTAL COST OF F.D.R. PART - A	Rs. 16.043	Lacs
ADD G.S.T @ 12%	Rs. 1.925	Lacs
ADD Labour Cess @ 1%	Rs. 0.160	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.460	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 18.588	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन


पथ का नाम	:- L043-T02 Chota Raghunathpur To Karimullahpur Dakshin (VR43) Diversion 1 st Cut
पथ की लम्बाई	:- 0.125 KM
प्राक्कलित राशि	:- 18.588 Lac
वित्तीय वर्ष	:- 2021-22 / FDR-2021
प्रखंड	:- Amdabad


प्रस्तुत प्राक्कलन मो0 18.588 लाख (अठारह लाख अठावन हजार आठ सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के L043-T02 Chota Raghunathpur To Karimullahpur Dakshin (VR43) Diversion 1st Cut पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन के डायवर्सन में एक तरफ बम्बू पाईलिंग और Sand Bag के पश्चात मिट्टी कार्य करने के उपरान्त ब्रीक बैट डाल कर डायवर्सन को चालू किया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Manihari

2. Name of Block/Road Amdabad / L880-TO 2 chota Paganathpur
To Karimullahpur Dakshin (VR 43) Division 1st Cut

A for Road

1. Damage location : 0.675 km

2. Damage Length : 0.125 km

3. Nature of Damage : Diversion

4. Details of Restoration :

i. Material being used in Restoration Bamboo, E/w, bricks bats, Sand bag

ii. Equipment/Tools being used in Restoration Works : JCB, Tractor

iii. Procedure taken up in Restoration works: Manual

iv. Restored Length 0.125 km

B. for Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i. Material being used in Restoration :

ii. Equipment/Tools being used in Restoration Works :

iii. Procedure taken up in Restoration works:

iv. Restored Length

Signature of JE/AE/EE

Executive Engineer
Rural Works Department
Manihari

Signature
(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L043 - T02 CHOTA RAGHUNATHPUR TO KARIMULLAPUR DAKSHIN
(VR43) DIVERSION 1 ST CUT

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 0.125


Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	9.169
2	HUME PIPE	0.000
3	BRICK BAT	4.975
4	SAND BAGS	0.942
5	G.S.B.	0.000
5	BAMBOO WORK	0.957
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		16.043
Add G.S.T. @ 12%		1.925
Add Labour Cess @ 1%		0.160
Add Seigniorage Fee @ 10%		0.460
Total Cost of Restoration Work =		18.588


J.E.
RWD


A.E.
RWD


E.E.
RWD

Technically Sanction for Rs. 18.588 Lac (Rs.
Crore. Eighteen Lac. Fifty eight
Thousand. Eight Hundred. Paise)


Superintendent Engineer
Rural Works Department
Works Circle, Purnea