

## SUMMARY OF COST ESTIMATE FOR THE PROJECT


**NAME OF ROAD** :- Hariharpur Chauk To R.E.O. Road Nimrauli  
**DISTRICT** :- Darbhanga  
**BLOCK** :- Singhwara  
**Actual Length of Road** :- 3.600 Km  
**Flood Affected Length of Road** :- 0.233 Km


|                                              |                                                                           | Lead in Km | 3 | + | 1                                          |
|----------------------------------------------|---------------------------------------------------------------------------|------------|---|---|--------------------------------------------|
| Sr. No.                                      | Description                                                               |            |   |   | Amount (In Rs.)                            |
| 1                                            | Brick bats<br>Total Qty. = <del>144,583</del> <sup>72.14</sup> @ 1,874.91 |            |   |   | <del>2,71,081.00</del> <sup>135256</sup>   |
| 2                                            | Add GST @ 12%=                                                            |            |   |   | <del>32,530.00</del> <sup>16231</sup>      |
| 3                                            | Add Labour Cess @ 1%=                                                     |            |   |   | <del>2,711.00</del> <sup>1353</sup>        |
| 4                                            | S.F. @10% on material(Brick Bats)=                                        |            |   |   | <del>14,921.00</del> <sup>7445</sup>       |
| TOTAL RESTORATION COST OF THE PROJECT IN Rs. |                                                                           |            |   |   | <del>3,21,243.00</del> <sup>1,60,285</sup> |

कार्यपालक अभियन्ता, ग्रामीण कार्य विभाग, कार्य प्रमोडाल-मधुबनी का पत्रांक-59534  
 दि०-12-03-2022 के द्वारा समर्पित ज्ञात-प्रतिवेदन के आधार पर।  
 - Post-facto T/A for Rs. 1,60,285/- (Rs. One lac sixty thousand  
 + two hundred eighty-five only)

  
 Superintending Engineer  
 RWD (W) Circle Darbhanga

  
 Junior Engineer  
 RWD (W) Division, Darbhanga-2

  
 Assistant Engineer  
 RWD (W) Division, Darbhanga-2

  
 Executive Engineer  
 RWD (W) Division, Darbhanga-2

**कार्यपालक अभियंता का कार्यालय**  
**ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधुबनी।**

पत्रांक:- 595 अनु०

दिनांक:- 12/03/2022

प्रेषक,

कार्यपालक अभियंता  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल, मधुबनी।

सेवामें,

कार्यपालक अभियंता  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल, दरभंगा-2

विषय:-

एफ०डी०आर० योजनान्तर्गत अस्थायी पूर्णस्थापन कार्य (Motorable Work) का प्राक्कलन समर्पित करने के संबंध में।

महाशय,

उपर्युक्त विषयक सूचित करना है कि अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, दरभंगा के द्वारा आपके प्रमंडल अंतर्गत एफ०डी०आर० योजनान्तर्गत अस्थायी पूर्णस्थापन कार्य (Motorable Work) के पथों एवं प्राक्कलन की जाँच हेतु निदेश दिया गया था। जिसके आलोक में जाँचापरांत पथ का प्राक्कलन समर्पित की जाती है। विवरणी निम्न प्रकार से है:-

| RWD(W) Sub Division Singhwara              |                                     |                            |                       |
|--------------------------------------------|-------------------------------------|----------------------------|-----------------------|
| Flood affected Road Lists for Year-2021-22 |                                     |                            |                       |
| Sr. No.                                    | List of Eligible Roads              | Flood affected length(mtr) | Restored quantity(m3) |
| 1                                          | L023-L022 to Dharampur (VR23)       | 1.550                      | 1.550                 |
| 2                                          | T02 to Chamnpur                     | 9.000                      | 5.400                 |
| 3                                          | PMGSY Katasa to Gaurinath Barhmpura | 233.700                    | 91.230                |
| 4                                          | MMGSY to Jha ji Tola                | 113.260                    | 30.680                |
| 5                                          | T02 - AGYASPUR                      | 54.200                     | 16.100                |



|    |                                                                                      |         |              |
|----|--------------------------------------------------------------------------------------|---------|--------------|
| 6  | T01 - BIRDIPUR                                                                       | 15.500  | 34.410       |
| 7  | N.H -57 sastri chowk sa P.W.D path                                                   | 16.000  | 32.690       |
| 8  | Govindpur PMGSY to Birdepur EDGHAH                                                   | 65.500  | 28.750       |
| 9  | P.W.D. Pak Tola to Sanhpur Via Chakauti                                              | 107.000 | 33.250       |
| 10 | PMGSY to Kushamari Tola                                                              | 122.700 | 15.400       |
| 11 | Rasulpur PWD Rd to Saraiya                                                           | 70.500  | 79.040       |
| 12 | Darbhanga Sima to L065 Biribala Tinkonama                                            | 43.000  | 19.770       |
| 13 | PWD Road to Ghop Tola.                                                               | 30.000  | 11.880       |
| 14 | NH 57 to Bhawara Tol                                                                 | 33.500  | 8.880        |
| 15 | REO Gandhi Chauk to Birdipur Dih Tola                                                | 18.000  | 14.550       |
| 16 | Moen Nadi Pull Rahi Toal to Damodri Pokhar                                           | 95.000  | 19.080       |
| 17 | Reo to Karti Pokhar                                                                  | 76.000  | 49.700       |
| 18 | PWD Sagir Chowk to Sahani tol sima tak                                               | 93.000  | 19.080       |
| 19 | Pmgsy Bramhapura to Mmgsy Raghua                                                     | 310.000 | 44.64,788.64 |
| 20 | ConstrucToin of Road Bauka Chowk To asthuuaa kaligow sima Via Bhajaura Radhiya kutti | 18.600  | 3.910        |
| 21 | L033-T02 to Raghua (VR33)                                                            | 88.000  | 14.950       |
| 22 | Kora to Radhawa                                                                      | 109.900 | 27.450       |
| 23 | Kalwara Road To Korapaswan Tola                                                      | 55.000  | 8.750        |
| 24 | T01 NH 57 to L029 Shekh Toli Manihas                                                 | 104.000 | 58.240       |

|    |                                          |         |         |
|----|------------------------------------------|---------|---------|
| 25 | L049-T02 to Shankarpur (VR49)            | 35.500  | 7.990   |
| 26 | PMGSY to Mushari Tol                     | 292.000 | 108.950 |
| 27 | REO Road to Kusumpatti via Kanuar        | 254.100 | 87.890  |
| 28 | PWD Sadhwara to Sahani Tola.             | 28.000  | 16.400  |
| 29 | Hariharpur Chauk to R.E.O. Road Nimrauli | 168.700 | 72.140  |
| 30 | Simri Sighwara Road                      | 175.000 | 42.420  |
| 31 | Dahsil to Neem Tola                      | 50.000  | 90.000  |
| 32 | P.W.D Path to Hariharpur                 | 150.600 | 26.930  |
| 33 | Mushari Tola to L037 Bhabanipur Lorika   | 16.000  | 19.472  |
| 34 | Phulthua PCC Road to Kheraj Sima         | 12.200  | 18.550  |
| 35 | Katasa se Sobhan                         | 477.500 | 118.470 |
| 36 | L068-PMGSY to Nikasi (VR68)              | 80.000  | 17.775  |
| 37 | Bhajoura PMGsy to Nista Cham Toli        | 104.200 | 29.930  |

अनु०:-यथोक्त ।

विश्वासभाजन

*[Signature]*  
12/03/22

कार्यपालक अभियंता

ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधुबनी ।



(29)

## Inspection Report for Flood Damage Work

Date:- 15.12.2021

Name of PIUs:- Doodhnaagee-02

Name of Block/Road:- Singraon / Hoshorpur check to Red Road nirpore

(A) For Road:-

1 Damage Location/Chainage:- ch. 0.200 to 6.83 km.

2 Damage Length:- 168.70 m.

3 Nature of Damage:- Major put holes in Road.

4 Details of Restoration Works:-

(i) Material being used in Restoration Works:-

Brick Ball (72.14 m<sup>3</sup>)

(ii) Equipment's/Tools being used in Restoration works:- Tractor, JCB

(iii) Procedure taken up in Restoration Works:- Brick Ball filling.

(iv) Restored Length:- 168.70 m.

(B) For Bridge:-

1 Damage Location/Chainage:-

2 Damage Length:-

3 Nature of Damage:-

4 Details of Restoration Works:-

(i) Material being used in Restoration Works:-

(ii) Equipment's/Tools being used in Restoration works:-

(iii) Procedure taken up in Restoration Works:-

(iv) Restored Length:-

work found satisfactory

Signature of JE/AE/EE

18/12/22  
J.E.

18/12/22  
AE

Signature  
(Name of Inspect)

18/12/22