



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

S045 TO TEGIA LAKHANPUR

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 600	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	0.600	KM
TOTAL COST OF F.D.R. PART - A	Rs. 6.524	Lacs
ADD G.S.T @ 12%	Rs. 0.783	Lacs
ADD Labour Cess @ 1%	Rs. 0.065	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.123	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 7.494	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari


प्रतिवेदन


पथ का नाम	:— S045 To Tegia Lakhanpur
पथ की लम्बाई	:— 0.600 KM
प्राक्कलित राशि	:— 7.494 Lac
वित्तीय वर्ष	:— 2021-22 / FDR-2021
प्रखंड	:— Amdabad


प्रस्तुत प्राक्कलन मो0 7.494 लाख (सात लाख उन्चास हजार चार सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के S045 To Tegia Lakhanpur पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक— मु0अ0-4 (मु0) विविध (कार्य)— 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में पथ के गहरे कटाव स्थान पर मिट्टी भरने के पश्चात ईट का टुकड़ा डाला गया है। फलैंक में पानी से कटाव स्थान पर बम्बू पाईलिंग और चचरी के पश्चात Sand Bag का प्रयोग किया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Manihari
2. Name of Block/Road Amdeabad / SO45 TO Jega Lakhanpur

A for Road

1. Damage location : 0.0 - 0.35, 0.6 ,
2. Damage Length : 0.363 km
3. Nature of Damage : Cross Cut
4. Details of Restoration :
 - i. Material being used in Restoration Bamboo, Sand bag, Brick bat.
 - ii. Equipment/Tools being used in Restoration Works : Tractor.
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.363 km.

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EB

[Signature]
26/11/21
Executive Engineer
Rural Works Department
Manihari

[Signature]
Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : S045 TO TEGIA LAKHANPUR

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 0.600

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	2.360
2	HUME PIPE	0.000
3	BRICK BAT	0.967
4	SAND BAGS	0.406
5	G.S.B.	0.000
5	BAMBOO WORK	2.791
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		6.524
Add G.S.T. @ 12%		0.783
Add Labour Cess @ 1%		0.065
Add Seigniorage Fee @ 10%		0.123
Total Cost of Restoration Work =		7.494

[Signature]
J.E.
RWD

[Signature]
A.E.
RWD

[Signature]
J.E.
RWD

Technically Sanction for Rs. 7.494 Lac (Rs.
Crore. Seven Lac. Forty nine ...
Thousand. Four Hundred. 100 ...)

[Signature]
Superintendent Engineer
Rural Works Department
Works Circle, Purnea