



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

PWD ROAD BAKHRIPUR TO KATIHAR MANIHARI RCD ROAD AT KAJRA (RRP-II)
BRIDGE DIVERSION

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH

0 TO 66

DISTRICT

KATIHAR

BLOCK

MANSAHI

DIVISION

MANIHARI

TOTAL LENGTH OF ROAD

0.066

KM

TOTAL COST OF F.D.R. PART - A

Rs. 17.603

Lacs

ADD G.S.T @ 12%

Rs. 2.112

Lacs

ADD Labour Cess @ 1%

Rs. 0.176

Lacs

ADD Seigniorage Fee @ 10%

Rs. 0.886

Lacs

TOTAL COST OF RESTORATION WORK In
Rs.

Rs. 20.777

Lacs


SUBMITTED BY
The Executive Engineer,
Works Division, Manihari


प्रतिवेदन


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल ...अन्तर्गत ... प्रखंड के पथ ... जो विभागीय Or line Morititring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण याता गत न्यायक Moterale हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterale) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterale कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक ... का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।


कनीय अमियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, ...


सहायक अमियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, ...


कनीय अमियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, ...

Inspection Report for Flood damage work

Date:

1. Name of PIUs-

E.E.R.N.D. Yamitani

2. Name of Block/Road-

Yamitani

A. For Road

PWD Road Bakhsipur To Yamitani RCD Road AT Kajra
(OPP-1)

1. Damage Location/Chainage :

At -

2. Damage Length :

80 M.

3. Nature of Damage :

4. Details of Restoration :

Road cuts due to flood.

i Material being used in Restoration

: Brick Ball, Bamboo,

ii Equipment/Tools being used in Restoration works:

Tractor, JCB, Roller.

iii Procedure taken up in Restoration works

: Manual

iv Restored Length

: 80 M.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

25/11/21

Signature of JE/AE/EE

25.11.21

Signature of Inspector

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : PWD ROAD BAKHRIPUR TO KATIHAR MANIHARI RCD ROAD AT KAJRA
(RRP-II) BRIDGE DIVERSION

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK MANSAHI

LENGTH OF ROAD (IN KM) 0.066

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.727
3	BRIKCK BAT	16.270
4	SAND BAGS	0.000
5	BAMBOO WORK	0.606
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		17.603
Add G.S.T. @ 12%		2.112
Add Labour Cess @ 1%		0.176
Add Seigniorage Fee @ 10%		0.886
Total Cost of Restoration Work =		20.777

J.E.
RWD

A.E.
RWD

E.E.
RWD

Technically Sanction for Rs. 20.777 Lac (Rs.)

Cr. Twenty Lac. Seventy Seven

Thousand. Seven Hundred.

.....

Superintendent Engineer
Rural Works Department
Works Circle, Purnea