

ग्रामीण कार्य विभाग, कार्य प्रमंडल-रोसाडा अंतर्गत FDR के तहत मरम्मत / Motorable कराए गये
पथों की जीव की सूची।

not in act
MIS


प्रखंड	पथ का नाम	कराए गए कार्य	मरम्मत कराए जाने हेतु पथ की लम्बाई किलोमीटर	मरम्मत कराए जाने हेतु पथ की राशि	अभियुक्ती
Singhia	MDR-Bhararia	Brick Bat Filling	0.400	9.47	पूर्ण
Singhia	PWD Path To Gadua	Brick Bat Filling	0.150	2.43	पूर्ण
Singhia	L070-T02 Bhairson To Bisaharia	Brick Bat Filling	0.900	6.95	पूर्ण
Singhia	Singhia To Kalali Chowk Path	Brick Bat Filling	0.2	3.82	पूर्ण
Singhia	L045-T01 To Behat(VR45)	Brick Bat Filling	0.3	8.73	पूर्ण
Singhia	T02 (Sonsa) To Parhat	Brick Bat Filling	0.4	4.91	पूर्ण
Singhia		Brick Bat Filling	0.3	16.40	पूर्ण
Singhia	Improvement of road From Bharhar to Kanjara (Mhadalit Tola) To Pansalla mian road via Bangthaiya	Brick Bat Filling	3	13.93	पूर्ण
Singhia	Singhia Mahe Road To Petfora	Brick Bat Filling	2.275	3.15	पूर्ण
Singhia	L045-T02 Sonsa Chowk To Basua	Brick Bat Filling	2.5	6.60	पूर्ण
Singhia	Bara Chowk to Sonmani Via Laxminia	Brick Bat Filling	0.9	6.99	पूर्ण
Singhia	SH56 to Bharihar Tola	Brick Bat Filling	0.15	6.04	पूर्ण
Singhia	MMS(Bharahar Pansalla) Path To Laxminia	Brick Bat Filling	0.25	5.83	पूर्ण
Singhia	Quotahar (T02) Mungelia	Brick Bat Filling	0.4	6.31	पूर्ण
Singhia	Improvement of Road from Bachhuliya to Akopur-Harpur-pabra- lind Phase	Brick Bat Filling	0.35	3.80	पूर्ण
Singhia	L073-T02 Navtoliya	Brick Bat Filling	0.4	5.21	पूर्ण
Singhia	T03 (lilhaul) to Kichaka Musahari Tola ward no. 01	Brick Bat Filling	0.7	5.49	पूर्ण
Singhia	L081-T01 to Dhakjari (VR81)	Brick Bat Filling	0.2	2.75	पूर्ण
Singhia	T01 Manu - Bela	Brick Bat Filling	0.3	19.79	पूर्ण
Singhia	L056-T02 To Jibudihuli (VR56)	Brick Bat Filling	0.3	5.85	पूर्ण
Singhia	Bharhar to Bhairson	Brick Bat Filling	0.8	6.31	पूर्ण
Singhia	Salehpur Path to Musaur	Brick Bat Filling	0.375	4.43	पूर्ण
Singhia	T02 Diha To Murli Ward No 06	Brick Bat Filling	0.25	6.76	पूर्ण
Singhia	X Salepur - Tenua Road	Brick Bat Filling	0.3	4.87	पूर्ण
Singhia	T02 Basopatti	Brick Bat Filling	0.45	7.95	पूर्ण
Singhia	T01 - Aurahi Bhair	Brick Bat Filling	0.25	4.97	पूर्ण
Singhia	Diha (Tenua) To Bhairson (Bharhar)	Brick Bat Filling	0.3	3.49	पूर्ण
Singhia	Haripur Bela Path	Brick Bat Filling	0.6	5.46	पूर्ण
Singhia	L030-L025 to Rampura (VR30)	Brick Bat Filling	0.9	6.24	पूर्ण

[Signature]
3/12/24

कार्यपालक अभियंता
ग्रामीण कार्य विभाग, कार्य प्रमंडल-मशील-बरखली

Road name not
matched MIS
[In MIS Name is -
SH-56 to mushepur]

77



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

GOVT. OF BIHAR

FDR

YEAR 2021-22

Detailed Project Report

Division : Rosera

District :

Samastipur

Block :

Singhia

Name of
Road :

Salehpur Path to Musepur

SUBMITTED BY
THE EXECUTIVE ENGINEER
WORKS DIVISION, ROSERA

FDR

Detailed Estimate for

Salehpur Path to Musepur

Block : Singhia
District : Samastipur

ABSTRACT OF COST FOR ROAD

No	Item of Work	Amount (In Rs)	
		As per Estimate	
	Total Cost for Pavement Works		365213.24
	Total Cost of Project :	Rs -	365213.24
	Total Cost Including (GST + L.Cess) 13% :	Rs -	474777.72
	Total :	Rs -	412690.97
	Say (Lakh) :	Rs -	4.13

[Signature]
27/10/21

Junior Engineer
RWD (W) Section, Singhia

[Signature]
28/10/21

Asstt. Engineer
RWD (W) S. Div. Singhia

[Signature]
28/10/21

Executive Engineer
RWD (W) Div, Rosera

Sanctioned for Rs 4.13 Lakh say four Lakh Three thousand only. including O.H. charge.

[Signature]
10/12/21

प्रमाणित किया गया
आवधिक कार्य विभा.
आवधिक कार्य विभाग, प्रमाणित

[Signature]
10/12/21
T. A

[Signature]
10/12/21

FDR

Salehpur Path to Musepur

District : Samastipur
Block : Singhia

Total Length (Km): 0.375

SI No	Refference To Mord Spec.	Brief Description of Item	No	Measurements			Unit	Quantity	Rate (Rs)	Amount (Rs)
				L (m)	B (m)	D (m)				
1	401	Supply filling brick bat compacted manually	2	35.00	1.70	0.35	cum	41.65		
			1	20.00	1.70	0.30	cum	10.20		
			1	10.00	1.90	0.25	cum	4.75		
			2	5.00	1.80	0.20	cum	3.60		
			8	15.00	3.00	0.20	cum	72.00		
			10	8.00	2.60	0.20	cum	41.60		
			3	11.00	3.10	0.25	cum	25.58		
			3	5.50	3.30	0.15	cum	8.17		
			2	2.75	3.10	0.25	cum	4.26		
		Total Quantity :					cum	211.81	1724.29	365213.24
		Total Cost of Pavement in Rs :								3.65

Junior Engineer
RWD (W) Section, Singhia

Asstt. Engineer
RWD (W) S. Div. Singhia

Executive Engineer
RWD (W) Div, Rosera

[Signature]
22/10/21

[Signature]
22/10/21

[Signature]
22/10/21