

33.00	Providing and laying RCC pipe NP3 (600 mm dia) Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets clauses 1106	15.00	M	1468.05	1468.05	Rupees One Thousand Four Hundred Sixty Eight And Paise Five Only	22020.76
34.00	Plastering with CM 1:4 Plastering with CM 1:4 15mm thick on brickwork in substructures per technical specification clause 613.4 & 1204	28.04	sqm	147.60	147.60	Rupees One Hundred Forty Seven And Paise Sixty Only	4138.73
35.00	Maintainance for 1st year	1.00	Year	61321.71	61321.71	Rupees Sixty One Thousand Three Hundred Twenty One And Paise Seventy One Only	61321.71
36.00	Maintainance for 2nd year	1.00	Year	81005.88	81005.88	Rupees Eighty One Thousand Five And Paise Eighty Eight Only	81005.88
37.00	Maintainance for 3rd year	1.00	Year	95570.27	95570.27	Rupees Ninety Five Thousand Five Hundred Seventy And Paise Twenty Seven Only	95570.27
38.00	Maintainance for 4th year	1.00	Year	115254.43	115254.43	Rupees One Lakh(s) Fifteen Thousand Two Hundred Fifty Four And Paise Forty Three Only	115254.43
39.00	Maintainance for 5th year	1.00	Year	129818.82	129818.82	Rupees One Lakh(s) Twenty Nine Thousand Eight Hundred Eighteen And Paise Eighty Two Only	129818.82
Total Estimated Cost in Figures							
Quoted Amount							
Quoted Rate in Words							

Cons'tn Cost - 11074163.50
5 year maintainance - 482971.00
Total 11557134.50

13.00 approved for Rs. 11557134.50 only

Superintending Engineer
A.W.D. (W) Circle
Chapra

Executive Engineer
Rural Work Department
Work Division, Marhaura

AE

18.02.14

EE

2107242014

JE