


Tender Inviting Authority: Engg-In Chief RWD Patna						
Name of Work: Construction of Road & CD Works Under (Deviganj) Pathraha PMGSY Road near House of Dharmdas Gupta To Singh						
Contract No: Civil Works/						
Bidder Name:						
Excess ( + ) %						
<div style="text-align: right;"> <input checked="" type="checkbox"/> VALIDATE  <input type="checkbox"/> PRINT  <input type="checkbox"/> HELP         </div>						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
107.00	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8	61.24	Cum	4519.53	Rupees Four Thousand Five Hundred & Nineteen and Paise Fifty Three Only	276776.02
108.00	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 (II) RCC Grade M-25	15.40	Cum	8855.69	Rupees Eight Thousand Eight Hundred & Fifty Five and Paise Sixty Nine Only	136377.63
109.00	Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202	1.53	MT	56762.96	Rupees Fifty Six Thousand Seven Hundred & Sixty Two and Paise Ninety Six Only	86847.33
110.00	Providing and fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing and technical specifications	0.00	RM	305.07	Rupees Three Hundred & Five and Paise Seven Only	0.00
111.00	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 (II) Sandy Material	94.77	Cum	587.30	Rupees Five Hundred & Eighty Seven and Paise Thirty Only	55658.42
112.00	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7	48.00	No.	124.03	Rupees One Hundred & Twenty Four and Paise Three Only	5953.44
113.00	Drainage spouts complete as per drawing and technical specifications Clause 1209	4.00	No.	528.61	Rupees Five Hundred & Twenty Eight and Paise Sixty One Only	2114.44
121.00	Maintenance cost of Project road for the 1st year=	1.94	Km	108317.04	Rupees One Lakh Eight Thousand Three Hundred &	108317.04
122.00	Maintenance cost of Project road for the 2nd year=	1.94	Km	127888.19	Rupees One Lakh Twenty Seven Thousand Eight	127888.19
123.00	Maintenance cost of Project road for the 3rd year=	1.94	Km	249575.60	Rupees Two Lakh Forty Nine Thousand Five Hundred &	249575.60
124.00	Maintenance cost of Project road for the 4th year=	1.94	Km	302765.15	Rupees Three Lakh Two Thousand Seven Hundred &	302765.15
125.00	Maintenance cost of Project road for the 5th year=	1.94	Km	357863.19	Rupees Three Lakh Fifty Seven Thousand Eight	357863.19
Total Estimated Cost in Figures				Rupees only		16891275.94
Quoted Amount				16891275.94		16891276.00
Quoted Rate in Words				Rupees One Crore Sixty Eight Lakh Ninety One Thousand Two Hundred & Seventy Six Only		

  
 17/7/2016

Signature of Tenderer with seal

P.T.O.

19/7/16

APPROVED  
  
 SUPERINTENDING ENGINEER  
 R.W.D. WORKS CIRCLE, KISHANGARH