

NEW MAINTENANCE POLICY 2018 (Head - 3054)

Name of Road :- Basahi pul Shophipur Singh ke Ghar Se Madhya
Via Michalta / Purabhatampur to Shobhitpur
To & To Karnpura

Length :-

Name of Block :- Lahladpur / Ekma

Name of Sub-Division :- Lahladpur / Ekma

Agreement No. & Date :-

Name & Address of Agency :- Satgendra Upadhyay
Vill + Post - Muhammadpur
P.S. - Manthi Dist - Saren

A.A. Amount & Date :-

BOQ Value :-

Rate Quoted by Contractor :-

Construction Cost :-

Maintenance Cost :-

Total Agreement Value :-

Performance Security :-

Add. Performance Security :-

Time Required for Work :-

Date of Start :- 10.10.2022

Date of Completion :- 9.10.2023

Total No. of Item :-

Executive Engineer,
Executive Engineer
Roads & Works Department,
R.W.D. Works Division
Chhapra, Chapra-2



बिहार BIHAR



AS 028781

मुकेश कुमार वर्मा

मुद्रांक विज्ञापन एकादश

नम्र नं-170/93

AGREEMENT

Agg. No. :-

Rate :- % Below

Date of Start :- 10.10.2022

Date of Completion :- 09.10.2023

Time Allowed - Month

This agreement made the between RURAL WORKS DEPARTMENT (Govt. of Bihar) Authorized address at 5th floor, Vishweshwariya Bhawan, Jawaharal Nehru Marg, Patna- 800013, Executive Engineer, R.W.D., Works Division, Chapra - 2 (herein after called "the Employer") of the one part and Satyendra Upadhyay, Village + P.O. - Muhammadpur, P.S. - Manjhi, Dist. - Saran (Chapra) (herein after called "the Contractor" of the one part.)

PAN No. :- AAXPU3146N

GST No. :- 10AAXPU3146N1Z3

Whereas the Employer is desirous that the Contractor execute Output and Performance based Rural Road contract for the Repair & Maint. of Road (Package No. - MR-N/22-23/Chapra-2/03)

Tender ID - 110672, BID ID - 471153

Sl. No.	Block	Package No.	Name of Road	Main Work Amount	Maintenance Amount	Grand Total
1	Lahladpur	MR-N/22-23 Chapra-2/03	Dasahi Pal Shobhipur singh Ke Ghar Se Madhya Via Mirhata.	7545306.00	4064657.00	11609963.00
2	Lahladpur		Purushottampur Shobhipur to	5356396.00	2266923.00	7623319.00
3	Ekma		Tot to Karpura	8963069.00	4484131.00	13447200.00
Total Rs.				21864771.00	10815711.00	32680482.00

(hereinafter called "the Works") and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein **11.57% Below**, at a Cost. of Main work Rs. 21864771.00 + Maintenance work Rs. 10815711.00 Grand Total Rs. 32680482.00 (Three Crore Twenty Six Lakh Eighty Thousand Four Hundred Eighty Two only) (Including Labour Cess 1%, GST 12% And Seigniorage Fee)

Executive Engineer
R.W.D. Works Division
Chapra

आयकर विभाग

INCOME TAX DEPARTMENT

SATYENDRA UPADHYAY

BAIJNATH UPADHYAY


05/01/1974

Permanent Account Number

AAXPU3146N

Satyendra Upadhyay

Signature



भारत सरकार
GOVT. OF INDIA



21032013

Executive Engineer
P.W. Works Division
Chennai

Tender Inviting Authority: Engg-in Chief RWD Patna			
Name of Work :-		Basahi Pool Sobhipur Singh Ke Ghar Se Madhya Via. Mirhatta	
Name Of Block :-		Lahladpur	Name Of DISTRICT :- Chapra
Contract No: Civil Works/			
Bidder Name:		Excess (+)	%

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removal of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.68	ha	57007.10	Rupees Fifty Seven Thousand Seven And Paise Ten Only	38764.83
2.00	Construction of subgrade and earthen shoulders :-Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 300.1.	1428.00	Cum	244.02	Rupees Two Hundred Forty Four And Paise Two Only	348460.58
3.00	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	55.90	Cum	2573.81	Rupees Two Thousand Five Hundred Seventy Three And Paise Sixty One Only	143064.80
4.00	WBM Grading 2 (By Mechanical Means) :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	80.70	Cum	4723.17	Rupees Four Thousand Seven Hundred Twenty Three And Paise Seventeen Only	381159.82

Executive Engineer
R.W.D. Works Division
Chapra

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
23.00	Plastering with cement mortar (1:4):- Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	101.20	Sqm	103.29	Rupees One Hundred Sixty Three And Paise Twenty Nine Only	26335.41
24.00	Painting Two Coats on New Concrete Surfaces :- Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	468.48	Sqm	107.83	Rupees One Hundred Seven And Paise Sixty Three Only	50422.50
	Total cost Of Construction					75,17,033.03
	1% Labour Construction					75,170.33
	12% GST Construction					9,02,043.96
	TOTAL SEIGNIORAGE FEE Construction					38,271.26
25.00	Maintenance for 1st year	20.00	Per 3 month	202900.10	Rupees Two Lakh(s) Two Thousand Nine Hundred And Paise Ten Only	40,58,002.00
	1% Labour Maintenance					40,580.02
	12% GST Maintenance					4,86,960.24
	TOTAL SEIGNIORAGE FEE Maintenance					10,925.97
	Total Estimated Cost in Figures					1,31,28,986.81
	Quoted Amount				1,31,28,986.81	1,31,28,987.00
	Quoted Rate in Words				Rupees One Crore Thirty One Lakh(s) Twenty Eight Thousand Nine Hundred Eighty Seven Only	

W. S. S. S.

Executive Engineer
R.W.D. Works Division
Chapra-2

B.O.Q. approved for Rs 1,31,28,987 = 00
(Rupees one crore thirty one lac twenty eight
thousand nine hundred eighty seven) only
from item no. (1) to (25).

Certified Cpy.



Superintending Engineer
Rural (Works) Deptt.
Works Circle, Chupra

sd/—

Executive Engineer
R.W.D. Works Division
Chupra

Tender Inviting Authority: Engg-In Chief RWD Patna			
Name of Work: =		Pursattampur To Shehltipur	
Name Of Block: =		Lehaladpur	Name Of DISTRICT :- Chapra
Contract No: Civil Works/			
Bidder Name:		Excess (+)	%

SCHEDULE OF WORKS						
Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	Clearing and Grubbing Road Land (By manual means) including uprooting all vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removal of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a land of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E&I	0.40	ha	67007.10	Rupees Fifty Seven Thousand Seven And Paise Ten Only	26802.84
2.00	Construction of subgrade and earthen shoulders :-Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 300.1.	840.00	Cum	244.02	Rupees Two Hundred Forty Four And Paise Two Only	204976.80
3.00	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	67.40	Cum	2563.63	Rupees Two Thousand Five Hundred Sixty Three And Paise Eighty Three Only	172802.14
4.00	W&M Grading 2 (By Mechanical Means) :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	53.10	Cum	4702.44	Rupees Four Thousand Seven Hundred Two And Paise Forty Four Only	249699.56

Executive Engineer
R.W.D. Works Division
C'

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
22.00	Road Marking with Hot Applied Thermoplastic :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.	400.00	Sqm	771.66	Rupees Seven Hundred Seventy One And Paise Sixty Six Only	308664.00
23.00	Providing and Fixing 'Logo' of Maintenance Project :- Providing and fixing of typical MMSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG steel tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	2.00	nos	10349.98	Rupees Ten Thousand Three Hundred Forty Nine And Paise Ninety Six Only	20699.92
24.00	Brick Masonry in C.M.(1:3) in parapet :- Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	20.16	Cum	5644.26	Rupees Five Thousand Six Hundred Forty Four And Paise Twenty Five Only	113788.00
25.00	Plastering with cement mortar (1:4):- Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	141.12	Sqm	163.12	Rupees One Hundred Sixty Three And Paise Twelve Only	23019.49
26.00	Painting Two Coats on New Concrete Surfaces :- Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	409.92	Sqm	107.83	Rupees One Hundred Seven And Paise Sixty Three Only	44119.63
	Total cost Of Construction					53,33,665.28
	1% Labour Construction					53,336.65
	12% GST Construction					6,40,039.83
	TOTAL SEIGNIORAGE FEE Construction					30,174.15
27.00	Maintenance for 1st year	20.00	Per 3 month	113107.14	Rupees One Lakh(s) Thirteen Thousand One Hundred Sixty Seven And Paise Fourteen Only	22,63,342.80

SL No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
	1% Labour Maintenance					22,633.43
	12% GST Maintenance					2,71,601.14
	TOTAL SEIGNORAGE FEE Maintenance					5,945.02
	Total Estimated Cost in Figures					86,20,738.30
	Quoted Amount				86,20,738.30	86,20,738.00
	Quoted Rate in Words	Rupees Eighty Six Lakh(s) Twenty Thousand Seven Hundred Thirty Eight Only				

Handwritten signature/initials

B.O.A. approved for Rs eighty six lacs twenty thousand seven hundred thirty eight (Rs 86,20,738.30) only. from item no ① to ②⑦

Certified copy

Handwritten signature/initials

Handwritten signature/initials
04/06/21
E.O.

Handwritten signature
Superintending Eng. cum
Rural (Works) Deptt.
Works Circle, Chapra

Tender Inviting Authority: Engg-In Chief RWD Patna			
Name of Work: =		T04 To Karanpura	
Name Of Block =		Ekma	Name Of DISTRICT :- Chapra
Contract No: Civil Works/			
Bidder Name:		Excess (+)	%

SCHEDULE OF WORKS						
Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.80	ha	57007.10	Rupees Fifty Seven Thousand Seven And Paise Ten Only	45605.68
2.00	Construction of subgrade and earthen shoulders :-Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	1680.00	Cum	244.02	Rupees Two Hundred Forty Four And Paise Two Only	409953.60
3.00	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator or DMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	73.60	Cum	2544.26	Rupees Two Thousand Five Hundred Forty Four And Paise Twenty Eight Only	186750.15
4.00	WDM Grading 2 (By Mechanical Means) :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, wetting and compacting to the required density Grading 2 as per Technical Specification Clause 405.	57.90	Cum	4660.95	Rupees Four Thousand Six Hundred Sixty And Paise Ninety Five Only	269869.01

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
22.00	Read Marking with Hot Applied Thermoplastic :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.	800.00	Sqm	771.08	Rupees Seven Hundred Seventy One And Paise Sixty Six Only	617328.00
23.00	Providing and Fixing 'Logo' of Maintenance Project :- Providing and fixing of typical MMGSY Informalory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	2.00	nos	10340.00	Rupees Ten Thousand Three Hundred Forty Only	20680.00
24.00	Brick Masonry in C.M.(1:3) in parapet :- Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	17.28	Cum	5644.25	Rupees Five Thousand Six Hundred Forty Four And Paise Twenty Five Only	97532.64
25.00	Plastering with cement mortar (1:4):- Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	120.96	Sqm	162.33	Rupees One Hundred Sixty Two And Paise Thirty Three Only	19635.44
26.00	Painting Two Coats on New Concrete Surfaces :- Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	351.38	Sqm	107.63	Rupees One Hundred Seven And Paise Sixty Three Only	37816.89
	Total cost Of Construction					89,39,472.52
	1% Labour Construction					89,394.73
	12% GST Construction					10,72,736.70
	TOTAL SEIGNIORAGE FEE Construction					34,175.45
27.00	Maintenance for 1st year	20.00	Per 3 month	223032.50	Rupees Two Lakh(s) Twenty Three Thousand Eight Hundred Thirty Two And Paise Fifty Only	44,76,650.00

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
	1% Labour Maintenance					44,768.50
	12% GST Maintenance					5,37,198.00
	TOTAL SEIGNIORAGE FEE Maintenance					12,211.37
	Total Estimated Cost in Figures					1,52,06,605.27
	Quoted Amount					1,52,06,605.00
	Quoted Rate in Words				1,52,06,605.27	1,52,06,605.00
				Rupees One Crore Fifty Two Lakh(s) Six Thousand Six Hundred Five Only		

[Handwritten signature]

B.O.A. approved for Rs 1,52,06,605.00
 (Rupees one crore fifty two lakh six thousand six hundred five) Only from item no ① to ②
Certified by S/L

[Handwritten signature]
 04/06/21
 Superintending Engineer
 Rural (Works) Deptt.
 Works Circle, Cimpura

मुख्य अभियंता-3, पटना का कार्यालय,
ग्रामीण कार्य विभाग, बिहार, पटना।

पत्रांक- मु0अ0-3 प0पु0 1-284/22
प्रेषक,

26683/30

/पटना, दिनांक-29-9-22

मुख्य अभियंता-3,
ग्रामीण कार्य विभाग,
बिहार, पटना।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, छपरा-2

विषय: शीर्ष 3054 MR योजना (नई अनुरक्षण नीति 2018 योजना) अन्तर्गत कार्य प्रमंडल, छपरा-2 के अधीन MR-N/22-23 Chapra-2/03 पथ गरम्पति (TenderID-110672) कार्य के निविदा निष्पादन के संबंध में।

प्रसंग:-अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना का पत्रांक-मु0अ0-4(मु0)-निविदा-04-29 पार्ट-II/2022 - 1843 पटना दिनांक-28.09.2022

महोदय,

शीर्ष 3054 MR योजना (नई अनुरक्षण नीति 2018 योजना) अन्तर्गत कार्य प्रमंडल, छपरा-2 के अधीन MR-N/22-23 Chapra-2/03 पथ गरम्पति (TenderID-110672) कार्य निविदा के वित्तीय बीड में सफल निविदाकार Satyendra Upadhyay (471153) द्वारा उद्धृत दर जो कि परिमाण विपत्र की दर से 11.57 प्रतिशत कम है, अर्थात् कुल राशि 3,26,80,482.00 (तीन करोड़ छब्बीस लाख अस्सी हजार चार सौ बेशासी) रु0 मात्र पर कार्यरित एवं आपकी अनुमति के आलोक में यह कार्य आवंटित किया जाता है। इस निविदा के निष्पादन पर विभागीय निविदा समिति की सहमति प्राप्त है।

2. निविदा की स्वीकृति सिर्फ इसी कार्य के लिए है, जो भविष्य में पूर्वाधार नहीं होगा।

3. कार्यपालक अभियंता, कार्य प्रमंडल, छपरा-2 संवेदक के द्वारा एकरारनामा के लिए जमा की गई राशि एवं निविदा के साथ अग्रधन के रूप में जमा किये गये संबंधित एन0एस0सी0/पासबुक/फिक्स डिपोजिट/बैंक गारन्टी आदि का सत्यापन कराकर प्रमंडलीय कार्यालय में अभिलेखित करेंगे एवं कार्यादेश निर्गत करने के पूर्व अग्रधन की राशि के सत्यापन से संबंधित कागजात अधोहस्ताक्षरी को उपलब्ध कराया जाना सुनिश्चित करेंगे।

4. एकरारनामा के पूर्व Bid Validity की अवधि विस्तार की जाँच के उपरान्त ही एकरारनामा सुनिश्चित किया जाय।

5. एकरारनामा के पूर्व निविदा सूचना के अनुसार सभी वांछित कागजातों की अद्यतन स्पष्ट एवं सत्यापित प्रति निश्चित रूप से प्राप्त कर लिया जाय एवं साथ में इसकी भी जाँच कर ली जाय कि संवेदक डीबार सूची से मुक्त है।

5. अधीक्षण अभियंता एवं कार्यपालक अभियंता अग्रोत्तर कार्यवाई से पूर्व भली भाँति आवश्यक हो लेंगे कि पथ का हस्तांतरण हेतु विभाग द्वारा अनुरूप प्रमाण पत्र निर्गत नहीं किया गया है।

6. कार्य में व्यवहृत सामग्रियों का दर प्राक्कलन में स्वीकृत लीड के आधार पर दिया गया है, कार्य करते समय अगर इसमें कमी पाई जाती है तो उसके दर में सापेक्ष कमी कर दी जायेगी।

7. इस कार्य के संबंध में ग्रामीण कार्य विभाग, बिहार सरकार द्वारा निर्गत प्रशासनिक स्वीकृति एवं प्रावैधिक स्वीकृति तथा निविदा आमंत्रण सूचना में उल्लिखित शर्त एकरारनामा का भाग होगा, जिसे विशेष शर्त में जोड़कर संवेदक के साथ एकरारनामा किया जायेगा।

8. अनुमोदित किये गये तुलनात्मक विवरणी के प्रत्येक बिन्दु की जाँच अपने स्तर से स्वयं कर लेंगे एवं त्रुटि पाये जाने की स्थिति में वस्तुस्थिति से तत्क्षण अधोहस्ताक्षरी को अवगत करायेंगे। त्रुटि के सुधारोपरान्त एकरारनामा की कार्यवाई की जायेगी।

9. एकरारनामा के समय प्रत्येक मद के भाग की शुद्धता की जाँच कार्यपालक अभियंता स्वयं कर लेंगे एवं यह सुनिश्चित करेंगे कि इसमें कोई त्रुटि न हो।

10. कार्यारम्भ के पूर्व कार्यपालक अभियंता कार्य स्थल के निरीक्षणोपरान्त स्थल की स्थिति एवं प्राक्कलन में किये गये उपबंध से पूरी तरह आश्चरित हो लेंगे एवं प्रशासनिक स्वीकृति तथा प्रावैधिक स्वीकृति के अग्रसारण प्रारूप में दिये गये निर्देश का अनुपालन सुनिश्चित करायेंगे।

11. कार्यादेश निर्गत करने से पहले संबंधित संवेदक से एकरारित अवधि के अन्दर कार्य समाप्त करने हेतु विस्तृत मदवार कार्य प्रोग्राम प्राप्त कर ही एकरारनामा किया जाय।

12. अधीक्षण अभियंता एवं कार्यपालक अभियंता विशेष रूप से ध्यान देंगे कि कार्य मानक विनियमों के अनुरूप निर्धारित कार्य अवधि के अंदर पूरा की जाय।

13. कार्य समाप्ति की अवधि परिमाण विपत्र के अनुसार होगी।

**दिनांक-29.04.2022 को सम्पन्न तकनीकी बीड सामात का
बैठक की कार्यवाही (पुनर्विचार)**

निविदा आमंत्रण सूचना संख्या-MR-3054-03/2021-22 के तहत योजना शीर्ष 3054 के अंतर्गत कार्य प्रमंडल, छपरा-2 के अधीन Package No.- MR-N/20-21/Chapra-2/03 (Tender ID-110672) के अंतर्गत पथ की गरम्पति एवं पंचवर्षीय रख-रखाय हेतु दिनांक-23.05.2021 को प्रकाशित निविदा एवं दिनांक-08.07.2021 को प्राप्त निविदा में भाग लेने वाले निविदाकारों के तकनीकी बीड संबंधी कागजात की समीक्षा की गयी। इस कार्य के लिए अनुमोदित परिमाण विपत्र की राशि 369.56330 लाख मात्र है। इस कार्य की निविदा में 07 निविदाकारों द्वारा निविदा डाली गयी है। समयक विचारोपरांत क्षेत्रीय कार्यालय से प्राप्त चेकलिस्ट एवं निविदा कागजात के आधार पर समिति द्वारा दिनांक 05.11.2021 को निर्णय लिया गया जिसमें 04 निविदाकारों के तकनीकी बीड को योग्य घोषित किया गया जबकि 03 निविदाकारों के तकनीकी बीड को अयोग्य घोषित किया गया।

वर्तमान में निविदाकार Santoshi Singh, HMK Infratech Pvt. Ltd., Rajeev Kumar Singh एवं Satyendra Upadhyay का परिवाद पत्र प्राप्त हुआ है जिसके आलोक में कार्यपालक अभियंता का जाँच प्रतिवेदन उपलब्ध कराया गया है जो निम्नवत् है:-

क्रम सं०	परिवाद/अभ्यावेदन	कार्यपालक अभियंता, कार्य प्रमंडल छपरा-2 का जाँच प्रतिवेदन (पत्रांक 728 अनु० दिनांक- 06.04.2022)
1	निविदाकार Santoshi Singh, HMK Infratech Pvt. Ltd. के अभ्यावेदन के अनुसार पैकेज सं०-MR-N/20-21/Chapra-2/03 (Tender ID-110672) में भाग लिये सभी संवेदकों के शपथ पत्र, बैंक सर्टिफिकेट जाँच करते हुए निविदा प्रक्रिया पूर्ण की जाय।	कार्यपालक अभियंता, कार्य प्रमंडल छपरा-2 के जाँच प्रतिवेदन के अनुसार परिवादी संवेदक HMK Infratech Pvt. Ltd. के द्वारा सभी 07 निविदाकारों के लगभग सभी कागजातों में जाँच की मांग करना निविदा प्रक्रिया को बाधित करना है। पूर्व में C/S तैयार करते समय सभी निविदाकारों के कागजातों की जाँच प्रमंडल स्तर पर की गई जो सही प्रतीत होता है।