



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

010

DETAILED PROJECT REPORT FOR FDR

बिहार



DISTRICT : VAISHALI

BLOCK : MAHUA

ROAD NAME : MAHUA PREMRAJ TO NARANGI SARSIKAN

FLOOD DAMAGED ROAD

5

TOTAL LENGTH

: 3.400 KM

TOTAL PROJECT COST

: 6.77 7.28 LAKH

SUBMITTED BY
EXECUTIVE ENGINEER
RURAL WORKS DEPTT.
WORKS DIVISION
MAHUA

GENERAL ABSTRACT OF COST

Name of Road-Mahua Premraj To Narangi Sarsikan

District-Vaishali

Block-Mahua

Length(in KM)-3.40

Sl No.	Item Of Work	Amount(in Rs)
1	Earthwork	0.00
2	Brick Bats	727856.50 677365.91
3	Sand Filling	0.00
	Sub Total	727856.50 677365.91
	Grand Total (In Lacs)	6.77 7.28

[Signature]
22/11/21
JE

[Signature]
22/11/21
A.E.

[Signature]
22.11.21

As Per S.E. RWD (W) Circle Muz
Letter No 1179 Dated 01/10/2021
Estimate has been verified by inspecting
F. E. RWD. (W) Division *Nagibpur*

Technically Sanctioned for Rs. 7.28 lacs (Rs. Seven lacs twenty eight thousand) only (provisionally)

[Signature]
30.12.21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

[Signature]
30.12.21

Inspection Report for Flood Damage Work

Date:-

1 Name of PIU's :-

2 Name of Block/Road :-

3 For Road: mahua Premraj to Narraungi Sarai, km

Damage Location/Chainage :- 50-80, 400-420, 1000-1080, 2200-2290, 2500-2520

4 Damage Length :- 250 mtr

5 Nature of Damage :- Flood

6 Details of Restoration Works :-

Material being used in Restoration works:- Brick bats (352.54 cum)

Equipment's/Tools being used in Restoration works:- Back hoe loader, Tractor

Procedure taken up in Restoration works:- Immediate restor for drainage

Restored Length :- 0.25 km

work found satisfactory

7 For Bridge:

1 Damage Location/Chainage :-

2 Damage Length :-

3 Nature of Damage :-

4 Details of Restoration Works :-

5 Material being used in Restoration works:-

6 Equipment's/Tools being used in Restoration works:-

7 Procedure taken up in Restoration works:-

8 Restored Length :-

A/A/

Signature of JE/AE/EE
4/12/24

Signature
4/12/24

(Name of Inspection)


प्रतिवेदन


कार्य का नाम- महुआ प्रेमराज के जहाँगी अरिक्कन
पथ में अप्रत्याशित बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ में
सुधार करने हेतु आपातकालीन मरम्मत कार्य।

महुआ
दिनांक - 2021-22
प्रकल्प - 7-28/10/21

प्रकल्प प्रकल्प जिसकी प्राक्कलित राशि 7-28/10/21 है, महुआ प्रेमराज के जहाँगी अरिक्कन प्रकल्प- महुआ में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक-458/ दिनांक 13/11-21 द्वारा दिए गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू करने का प्रबन्धन किया गया है। प्राक्कलन वर्तमान धल अनुसूचित दर पर तैयार किया गया है। इसकी प्रत्येक सीढ़ी अपेक्षित है। 1055 के सविधि की गई (जमा राशि अंकित)


अभियंता


सहायक अभियंता


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल:-

SI No	SOR Sl.No	MORD Ref No.	Description	Unit	Quantity	Rate	Amount
1			Providing and Laying Brick Bats Providing laying spreading and compacting Brick Bats including spreading in uniform thickness hand packing (manual means)				
			As per Appendix I	Cum	352.548	2064.56	727856.50
				Total	352.548	1921.34	677365.91
2		11.2	Sand Filling Filling in Foundation trenches as per drawing and technical specification clause 305.3.9				
				Cum	0		
				Total	0		
					Total		677365.91

677365.91
727856.50

22/11/24
21

AGL
22/11/24
AG

22/11/24
AG