

ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR

बिहार



DISTRICT :	VAISHALI	BLOCK :	PATEPUR
------------	----------	---------	---------

ROAD NAME :	MANDAIDIH P.A . GARDANIYA CHAUK TO CHAKFAJIL PASWAN TOLA
-------------	--

		FLOOD DAMAGED ROAD			5
--	--	--------------------	--	--	---

TOTAL LENGTH	:	3.525	KM
TOTAL PROJECT COST	:	14.74 13.97	LAKH

14.737

SUBMITTED BY
EXECUTIVE ENGINEER
RURAL WORKS DEPTT.
WORKS DIVISION
MAHUA

GENERAL ABSTRACT OF COST

NAME OF ROAD - MANDAIDIH P.A . GARDANIYA CHAUK TO CHAKFAJIL PASWAN
TOLA

TRIC- VAISHALI
DCK-PATEPUR
LGTH(in KM)-3.525

No.	Item Of Work	Amount(in Rs)
	Earthwork	0.00
	Brick Bats	1418357.67 1319967.80 1418352.72
	Sand Filling	55319.75 76800.71 55320.32
	Sub Total	1473677.42 1396768.51 1473673.04
	Grand Total (In Lacs)	13.97 14.74

14.737 lacs

A 06/12/21
JE


06.12.21

As Per S.E. RWD (W) Circle Muz.
Letter No 1170 Dated 01/08/2021
Estimate has been verified by inspecting
E. E. RWD. (W) Division

Technically Sanctioned for Rs. 14.737 lacs
(Rs. Forteen lacs seventy three thousand seven
hundred) only (provisionally)


30.12.21
Superintending Engineer
Rural Works Department
Work Circle-Muzaffarpur
30.12.21

Inspection Report for Flood Damage Work

Date:-

1 Name of PIUs :-

2 Name of Block/Road :- mandouli P.A hardamniya chaur to
charkhewi paswan tola.

(A) For Road:


1. Damage Location/Chainage :- 20-450, 2120-2160, 2600-2700
2. Damage Length :- 0.560 mtr
3. Nature of Damage :- flood
4. Details of Restoration Works :-

- (i) Material being used in Restoration works:- Brck bat (687.00 cu) sand local (92.06 cu)
- (ii) Equipment's/Tools being used in Restoration works:- Tractor, roller, loader
- (iii) Procedure taken up in Restoration works:- Immediate restoration for traffic
- (iv) Restored Length :- 0.56 km
work found satisfactory.

(B) For Bridge:

1. Damage Location/Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works :-
- (i) Material being used in Restoration works:-
- (ii) Equipment's/Tools being used in Restoration works:-
- (iii) Procedure taken up in Restoration works:-
- (iv) Restored Length :-

N/A


Signature of JE/AE/EE


06-12-21


Signature

(Name of Inspection)

E. E.
Hazipur


प्रतिवेदन


कार्य का नाम:- मंडईडीह पंचायत बर्तनीया चौक से चकईज
पश्चिम टीला पथ में अप्रत्याशित बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ में
चालू करने हेतु आपातकालीन मरम्मत कार्य।


स्थान:- पातेपुर
वित्त वर्ष - 2021-22
प्राक्कलित राशि - Rs. 14.74 लाख

प्रस्तावित प्राक्कलन जिसकी प्राक्कलित राशि 14.74
13.97 लाख है, प्रखंड-पातेपुर में यातायात बहाली हेतु आपातकालीन मरम्मत के
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक-4587 दिनांक 13-11-21 द्वारा
दिए गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चालू अनुसूचित दर पर तैयार किया गया है। इसकी
प्रत्येक स्वीकृति अपेक्षित है। (MS में प्रविष्टि की गई है (चक्रवात प्रति संलग्न))


06/12/21
सहायक अभियंता


06-12-21
सहायक अभियंता


06-12-21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल:-