

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000

INDIA

बिहार BIHAR

AB 380311

AGREEMENT FORM

Supplementary

Agreement No :- 16/S.B.D./NABARD)-2018-19

This Agreement, made the 06th day July 2018 between The Executive Engineer, Rural Works Department, Works Division Jadishpur (Bhojpur) and PRASHANT KUMAR, Maharaja Hata, Katira, Ara, Distt-Bhojpur.

Whereas the Employer is desirous that the Contractor execute Construction of Road From Kusma Nahar Pul to Baraon Dalit Basti (Tender ID-56783) and maintenance for five years under NABARD for 2018-19 and the Employer has accepted the Bid by Contractor for the execution and completion of such works and the remedying of any defects therein at a cost of Rupees 15,77,180.00 (Rupees Fifteen Lac Seventy Seven Thousand One Hundred Eighty Only.)

Amount of Agreement Rs

:- 15,77,180.00

Approved Rate of which Payment

:- Below 10 % From Schedule rate.

PRASHANT KUMAR SINGH

Executive Engineer

6/8/18

(Ministry of Rural Works Department, Govt. of Bihar)
Nabard

Bill of Quantities For Extra Items

Road Nam Kushma Nahar Pul to Barson Dalit Basti

BLOCK :- Jagdishpur

DISTRICT :- BHUPUR

Length of Road (KM) ~2.100KM

S.No.	DESCRIPTION OF ITEMS	QUANTITY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
1	Proving and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with primer and cleaned with hydriloc broom as per technical specification clause 503.	7,684.380	Sqm	15.59	119799.00
2	Proving and laying and rolling of close-graded premix surfacing material of 20mm thickness composed of 11.2mm to 0.9mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 (in place)	7,684.380	Sqm	212.46	1632623.00
Grand Total (A)					1752422.00

Sqm 17.524 Lach

Bill of Quantity approved for Rs 17.524 Lach
IN SEVENTEEN LACH KITY
THIRY THOUSAND FOUR HUNDRED

Superintending Engineer
Rural Works Department
Jagdishpur

Superintending Engineer
Rural Works Department
Jagdishpur

Prashant Kumar Singh

6/10/18
6-10-18