



SUBMITTED BY
EXECUTIVE ENGINEER
RURAL WORKS DEPTT.
WORKS DIVISION
MAHUA

GENERAL ABSTRACT OF COST

Name of Road-Kankatta chauk to satrudhan singh ke ghar tak

District-Vaishali

Block-Mahua

Length(in KM)-1.00 KM

Sl No.	Item Of Work	Amount(in Rs)
1	Earthwork	0
2	Brick Bats	464990.53 ✓
3	Sand Filling	5745.20 5749.4715
	Sub Total	470735.73 470740.00
	Grand Total (In Lacs)	4.71 ✓

12/01/22
JB

AB
A.C.

D
17-01-22
E.E

Technically Sanctioned for Rs. 4.71 lacs (Rs. Four
lacs seventy one thousand) only (provisionally)

10-2-22

Superintending Engineer
Rural Works Department
Work Circle-Muzaffarpur

Inspection Report for Flood Damage Work

Date

1. Name of PIUs - EE, RWD, mahua

2. Name of Block/Road - mahua (naural)

A. For Road Kankata Chaula to Satrudham Singh ke ghairtak,

1. Damage Location/Chainage : 400-410, 600-620

2. Damage Length : 30 mtr

3. Nature of Damage : Flood

4. Details of Restoration Works :

i. Material being used in Restoration works : Brick ball (225.00 cum), Sand (10.00 cum)

ii. Equipments/Tools being used in Restoration works : Tractor, Road roller

iii. Procedure taken up in Restoration works : Immediate for restore traffic

iv. Restored Length : 0.03 km

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration Works :

i. Material being used in Restoration works :

ii. Equipments/Tools being used in Restoration works :

iii. Procedure taken up in Restoration works :

iv. Restored Length :

N/A

17/01/22
Signature
S. J. E/AE/EE

17.01.22
Signature
N.A.M.

17/1/22
Signature
(Name of Inspector)

प्रतिवेदन

कार्य का नाम:-

कनकड़ा चौक से बाधुन सिंह के घर तक

पथ में अप्रत्याशित बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- महुआ (बरोल पूर्व ई)

वित्तीय वर्ष - 2021-22

प्राक्कलित राशि - Rs. 4.71 लाख

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 4.71 लाख है, कनकड़ा चौक से बाधुन सिंह के घर तक, प्रखण्ड- महुआ में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 489 दिनांक 25/11/21 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी घटनोत्तर स्वीकृति अपेक्षित है।

17/01/22
कनीय अभियंता

17.01.22
सहायक अभियंता

17.01.22
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल -

SI No	SOR Sl.No	MORD Ref No.	Description	Unit	Quantity	Rate	Amount
1			Providing and Laying Brick Bats Providing laying spreading and compacting Brick Bats including spreading in uniform thickness hand packing (manual means)				
			As per Appendix I	Cum	225.225		
				Total	225.225	2064.56	464990.53
2		11.2	Sand Filling Filling in Foundation trenches as per drawing and technical specification clause 305.3.9				
				Cum	10.0875		5745.20
				Total	10.0875	569.96	5749.4715
				Total			470740.00

470 735.73

17.01.22

for

for