



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR

बिहार



DISTRICT : VAISHALI

BLOCK : PATEPUR

ROAD NAME : SUKKI P.A. TRANSFORMER CHAUK PWD ROAD SE SARAIYA GHAT TAK

FLOOD DAMAGED ROAD

5

TOTAL LENGTH

: 1.230 KM

TOTAL PROJECT COST

: 13.98 LAKH

SUBMITTED BY
EXECUTIVE ENGINEER
RURAL WORKS DEPTT.
WORKS DIVISION
MAHUA

GENERAL ABSTRACT OF COST

Name of Road - SUKKI P.A. TRANSFORMER CHAUK PWD ROAD SE SARAIYA GHAT
TAK

District-Vaishali

Block-Patepur

Length(in KM)-1.230

Sl No.	Item Of Work	Amount(in Rs)
1	Earthwork	0
2	Brick Bats	1295470.11
3	Sand Filling	31286.53
4	Sand Bags	71653.40
	Sub Total	1398410.04
	Grand Total (In Lacs)	13.98


28/12/21
88



28.12.21

कार्यपालक अधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल, महाराष्ट्र

Technically Sanctioned for Rs. 13.98 lacs
(Rs. Thirteen lacs ninety eight thousand) only
(Provisionally)


14.2.22
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

Inspection Report for Flood Damage Work

Date:

1. Name of PIUs - EE, RWD, mahua

2. Name of Block/Road - Patepur

A. For Road Sukki P.A Transformer chowk pWD Road se
sauraiya ghaut detk;

1. Damage Location/Chainage : 400-500, 550 to 750, 800-950

2. Damage Length : 450 meter

3. Nature of Damage : flood

4. Details of Restoration Works :

i. Material being used in Restoration works :

ii. Equipments/Tools being used in Restoration works:

iii. Procedure taken up in Restoration works : Immediate restore for traffic

iv. Restored Length : 450 meter

(Roll back 267
622.48 cum)
Sena - 31.89 cum
Boys - 1820.10 cum

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration Works :

i. Material being used in Restoration works :

ii. Equipments/Tools being used in Restoration works:

iii. Procedure taken up in Restoration works :

iv. Restored Length :

N/A

Signature of JE/AE/EE

28.12.21

EE

Signature

(Name of Inspector)

कार्यपालक अभियंता
प्राथमिक कार्य निदेशन
कार्य प्रमंडल, महंगा

प्रतिवेदन


कार्य का नाम:- इसकी ५० ३० टास्कमार्क चौक पीकलडी ० रुड से
इसका धारा तक पथ में अप्रत्याशित बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ में


यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।


प्रखण्ड-
वित्तीय वर्ष -
प्राक्कलित राशि - Rs.

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 13.98 लाख है,
प्रखंड-पटिपुर् में यातायात बहाली हेतु आपातकालीन मरम्मत के
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक दिनांक 22-08-2021 द्वारा
दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand मरकर पथ को चालू
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी
घटनोत्तर स्वीकृति अपेक्षित है।


28/12/21
कनीय अभियंता


28-12-21
सहायक अभियंता


28-12-21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल:-

Block-Patepur

SI No	SOR SI.No	MORD Ref No.	Description	Unit	Quantity	Rate	Amount
1			Providing and Laying Brick Bats Providing laying spreading and compacting Brick Bats including spreading in uniform thickness hand packing (manual means)				
			As per Appendix I	Cum	627.48		
				Total	627.48	2064.56	1295470.11
2		11.2	Sand Filling Filling in Foundation trenches as per drawing and technical specification clause 305.3.9				
				Cum	54.89		
				Total	54.89	569.96	31286.53
3		11.2	Sand Bags Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E in Charge				
				Nos	1820.00		
				Total	1820.00	39.37	71653.40

Total

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, महुआ

28.12.21