

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, पीरो (भोजपुर)

पत्रांक—278 / पीरो दिनांक—22/2/22

प्रेषक,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, पीरो (भोजपुर)।


सेवा में,

नोडल पदाधिकारी **MIS**
ग्रामीण कार्य विभाग
बिहार, पटना ।

विषय:— एकरारनामा की राशि सुधार करने के संबंध में ।
महाशय,

उपर्युक्त विषय के संबंध में कहना है कि MMGSY NDB BRICS योजनान्तर्गत Reo Road to T02 Tetariya जिसका Project Id-1040180190027 है। जिसका कन्सट्रक्शन एकरारनामा राशि 1,24,59,488.69 मरम्मति राशि प्रथम वर्ष—57,540.00, द्वितिय वर्ष—72,124.00 तृतीय वर्ष—3,30,961.00, चतुर्थ वर्ष—1,26,984.00 एवं पंचम वर्ष—3,72,862.00 है। जो कि भूल वश कन्सट्रक्शन एकरारनामा राशि 3,54,81,878.00 मरम्मति राशि प्रथम वर्ष—72,709.00, द्वितिय वर्ष—88,490.00 तृतीय वर्ष—3,48,702.00, चतुर्थ वर्ष—1,45,981.00 एवं पंचम वर्ष—3,93,116.00 प्रविष्ट हो चुका है।

अतः निवेदन है जिसका कन्सट्रक्शन एकरारनामा राशि 1,24,59,488.69 मरम्मति राशि प्रथम वर्ष—57,540.00, द्वितिय वर्ष—72,124.00 तृतीय वर्ष—3,30,961.00, चतुर्थ वर्ष—1,26,984.00 एवं पंचम वर्ष—3,72,862.00 प्रविष्ट करने की कृपा की जाये।


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, पीरो



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

Contractor Details

1	Agreement No.	30/S.B.D./MMGSY (NDB BRICS) -2020-21
2	Tender ID	96073
3	Name of Road	Construction of Road From Construction of Road From 1. 5025 To Udayamanpur, 2. REO Road To Tetariya, 3. T02 To Jaganpura, 4. Construction Of HL Bridge At REO Path To T02 Tetariya (MMGSY NDB BRICS) Package No-MMGSY-NDB-BRRP-229, Piro, Tender Id-96073.
4	Company Name	Sri Rohit Kumar Singh,
5	Contractor Name:-	Sri Rohit Kumar Singh,
6	Registration No.	1180002
7	Registration Class :-	I
8	Registration Validity :-	11.01.2023
9	Contractor Address :-	At-Siaruan Sadan, Near Mahuli Kothi, K.G. Road Nawada, Ara, Dist-Bhojpur.
10	District :-	Bhojpur
11	Pan No :-	BSGPS2912C
12	EPF Number :-	BRPAT1488141
13	GST NUMBER :-	10BSGPS2912C2ZA
14	Bank A/C No :-	
15	Bank Name :-	
16	IFSC Code :-	
17	Mobile No :-	9934695896
18	E-mail ID :-	rks5179@rediffmail.com

Rohit Kumar Singh

Rohit Kumar Singh
K.G. Road
Ara, Buxar.

(Signature)
EXECUTIVE ENGINEER,
RURAL WORKS DEPARTMENT,
WORKS DIVISION, PIRO

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000

बिहार BIHAR

30 DEC 2020

AGREEMENT FORM

Agreement No :- 30/SBD/MMGSY(NDB BRICS) -2020-21

This Agreement, made the 08th day February, 2021 between The Executive Engineer, Rural Works Department, Works Division Piro (Bhojpur) and Sri Rohit Kumar Singh, At-Siaruan Sadan, Near Mahuli Kothi, K.G. Road Nawada, Ara, Dsit-Bhojpur.

Whereas the Employer is desirous that the Contractor execute Construction of Road From 1. S025 To Udayamanpur, 2. REO Road To Tetariya, 3. T02 To Jaganpura, 4. Construction Of HL Bridge At REO Path To T02 Tetariya (MMGSY NDB BRICS) Package No-MMGSY-NDB-BRRP-229-Piro, Tender Id-96073 and maintenance for five years under MMGSY NDB BRICS for 2020-21 and the Employer has accepted the Bid by Contractor for the execution and completion of such works and the remedying of any defects therein at a cost Rupees 6,26,27,958.00 (Rupees Six Crore Twenty Six Lacs Twenty Seven Thousand Nine Hundred Fifty Eight Only.)

Amount Of Estimated Cost	:-	Rs. 6,26,27,957.62
Amount of Agreement Rs	:-	Rs. 6,26,27,958.00
Construction Value	:-	Rs. <u>589,73,421.00</u>
Maintenance Amount:-		Rs. <u>36,54,537.00</u>
Date of Written order to Commence	:-	<u>08.02.2021</u>
Time of Completion	:-	<u>07.02.2022</u>
Approved Rate of which Payment	:-	Below 0.00 % From Schedule rate will be made.

Rohit Kumar Singh

Executive Engineer
Rural Works Department
Works Division, Piro

Name of Works :- 1. S025 To Udayamanpur, 2. REO Road To Tetariya, 3. T02 To Jaganpura, 4. Construction Of HL Bridge At REO Path To T02 Tetariya (MMGSY NDB BRICS) Package No- MMGSY-NDB-BRRP-229-Piro, Tender Id-96073

Agency:

**Sri Rohit Kumar Singh,
At-Siaruan Sadan, Near Mahuli Kothi,
K.G. Road Nawada, Ara, Dsit-Bhojpur.**

Performance Security

1.	Earnest Money	F.D.	12,54,000 = 00	Date 09.07.2020
2.	Initial Security			Date
	Total	12,54,000 = 00		

- | | | |
|----|--|---|
| 1. | Estimated Cost:- | Rs. 6,26,27,957.62 |
| 2. | Agreement Value:- | Rs. 6,26,27,958.00 |
| 3. | Construction Value:- | Rs. 5,89,73,421.00 |
| 4. | Maintenance Amount:- | Rs. 36,54,537.00 |
| 5. | Performance Security:- | Rs. 12,54,000.00 |
| 6. | Date of Written order to Commence:- | 08-02-2021 |
| 7. | Time of Completion:- 12 Months i.e. | 07-02-2022 |
| 8. | Rate:- | 0.00 % Below from Schedule Rate. |

Rohit Kumar Singh


Executive Engineer
Rural Works Department
Works Division Piro (Bhojpur)

96073

MUKHYA MANTRI GRAM SAMPRAK YOJANA (MMGSY)					
BILL OF QUANTITIES (BOQ) CONSTRUCTION					
Road Name :	Reo Road To T02 Tetariya				
Block :	Charpokhari	District :	Bhojpur		
Length :	1.490 km				
Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Providing & Fixing of Working benchmark/Reference Pillars 01 nos. per km & 04 Nos. of reference pillars required for 1 Km as per drawings given and direction of E/I				
	Benchmark Pillars 01 nos. per km	No	2.00	4453.42	8906.84
	Reference Pillars 04 nos. per km	No	5.00	2034.28	10171.40
2	Clearing and Grubbing Road Land Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation , grass ,bushes ,shrubs , saplings and trees of girth upto 300mm , removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification - clause 201.1 and direction of E/I (By Manual Means) In area of non-thorny jungle				
		Hect	1.04	52966.72	55085.39
3	Road Cutting :- Excavation for roadway in soil using manual means for carrying of cut earth to embankment site with a lift upto 1.5 m and lead upto 50 m as per Technical Specification Clause 302.3				
		Cum	40.50	75.57	3060.59
4	Construction of Embankment with Material Obtained from Roadway Cutting Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5				
		Cum	24.30	26.54	644.92
5	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 100 m as per Technical Specification Clause 301.5				
		Cum	1962.74	143.06	280789.50
6	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5				
		Cum	1048.77	190.07	199339.71
7	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m & 100 m as per Technical Specification Clause 303.1. (Including Royalty & Labour Less).				
		Cum	2660.22	191.76	510123.79

APPROVED AS COLLECTOR.

S.E. RWE
Works Division
22/6/2021

Rohit Kumar Singh

Executive Engineer
Rural Works Division
Bhojpur
22/6/2021

Name: Reo Road To T02 Tetariya					
Block:	Charpokhari	District:	Bhojpur		
Length:	1.498 km				
No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
30	Providing and laying of a reinforced cement concrete pipe duct, 300 mm dia. across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC: 981997, bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC: 98 - 1997 and approved drawings.	RM	22.50	881.83	19841.18
	Estimate For Dismantling				
31	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 m as per Technical Specification Clause 202.	APPROVED AS CONTRACTOR S.E. RWC Works Division A 22/6			
1	Cement Concrete	Cum	3.24	497.81	1612.90
32	Dismantling of existing structures like culverts, bridges, retaining walls and other structures comprising of brick masonry, including disposal of unserviceable material and stacking the serviceable material with all lift and lead of 1000 m as per Technical Specification Clause 202.				
1	Cement mortar	Cum	122.76	235.20	28873.15
33	Removing all types of Hume pipes and stacking including Earthwork and Dismantling of Masonry Works as per Technical Specification Clause 202.				
1	Above 600 mm to 900 mm dia Hume pipe	RM	20.00	244.92	4898.40
Total Construction Cost :-					10898425.10
GST @ 12% :-					1307811.01
LC @ 1% :-					108984.25
Solignorage Fee @ 10% :-					144268.33
Total Construction (A) :-					12459488.69
34	1st Year Maintenance Cost	Year	1.00	57540.00	57540.0
35	2nd Year Maintenance Cost	Year	1.00	72124.00	72124.0

ROLA Kumar S

(B) 12/2
20/06/2020
Executive Engineer
Rural Works Department
Works Division, Piro

Road Name	Res Road To T02 Tetariya				
Block	Charpokhari	District	Bhojpur		
Length :	1.490 km				
Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
36	3rd Year Maintenance Cost	Year	1.00	330961.00	330961.0 ✓
37	4th Year Maintenance Cost	Year	1.00	126984.00	126984.0 ✓
38	5th Year Maintenance Cost	Year	1.00	372862.00	372862.0 ✓
	Total Maintenance Cost :-				960471.00 ✓
	GST 12 @ % :-				115256.52 ✓
	LC @ 1% :-				9604.71 ✓
	Seigniorage Fee @ 10% :-				48310.53 ✓
	Total Maintenance (B) :-				1133642.76 ✓
	Grand Total Cost (A+B) :-				13,593,131.45 ✓

Qty, R 135,931 lakh only,
 (R) 135
 20/06/2020

Bill of Quantity approved for Rs. 135.931 lakh
 (Rupees one crore thirty five lakh ninety -
 three thousand and one hundred only)

Superintending Engineer,
 Rural Works Department,
 Works Circle, ARA
 22/6/20

Rajiv Kumar Singh

(R) 135
 08/02/21
 Executive Engineer
 Rural Works Department
 Works Division, Piro
 08/02/21