

योजना का नाम - RCC BRIDGE OVER GANGA DHAR IN BETWEEN BAHORANPUR AND
DAMODARPUR का पहुँच पथ का मोटरेबुल कार्य का प्राक्कलन वर्ष 2021- 22

मद - FDR प्रखण्ड - शाहपुर

प्राक्कलित राशी - 4.202 लाख

प्रतिवेदन

प्रस्तुत प्राक्कलन जिसकी अनुमानित लागत मात्र 4.202 लाख है, उपरोक्त कार्य हेतु तैयार किया गया है!

यह पथ बहोरनपुर से दामोदरपुर तक पथ PMGSY से निर्मित है इसके 7वें कि०मी० दूरी दामोदरपुर गाँव के निकट पुल अवस्थित है ! अतिवृष्टि एवं बाढ़ के कारण पहुँच पथ क्षतिग्रस्त हो गया था! आवागमन को सुचारु रूप से चालू करने के लिए पहुँच पथ को मोटरेबुल कराया गया है !

प्राक्कलन में प्रयुक्त दर वर्तमान अनुसूचित दर के अनुकूल है! कार्य हित में प्रशासनिक एवं तकनीकी स्वीकृति अपेक्षित है!

→ ।

कनीय अभियंता

शाहपुर

सहायक अभियंता

कार्य अभि० शाहपुर


कार्यपालक अभियंता

कार्य प्रमण्डल जगदीशपुर

निरीक्षण प्रतिवेदन

अधीक्षण अभियंता, ग्रामीण कार्य विभाग , कार्य अंचल, आरा का पत्रांक -923 दिनांक - 14.11.2021 के द्वारा दिये गए निर्देश के अनुपालन में कार्य प्रमण्डल, जगदीशपुर के अंतर्गत वर्ष 2021 के बाढ़ एवं अतिवृष्टि से क्षतिग्रस्त निम्नलिखित पथों के Temporary Restoration वाले कार्य स्थलों का निरीक्षण किया गया एवं उन पथों को प्राक्कल के अनुसार कार्य कराया गया एवं कार्य संतोषप्रद पाया गया !

SL No.	Name Of Road	Length (In K.M)	Damage Length (In K.M)	Block
1.	Pwd Road Ishwarpura To Lalu KaDera	5.300	1.079 K.M	Shahpur
2.	Kadam Ka Dera Se Kariman Ka Dera	2.670	0.412 K.M	Shahpur
3.	Approach Of Rcc Bridge Over Ganaga Dhar In Between Bahoranpur And Damodarpur		0..182 K.M	Shahpur


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, डुमराव


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, जगदीशपुर

FDR 2021-21

GENERAL ABSTRACT OF COST

Block :- SAHPUR

District :- BHOJPUR

Name of Road :- APPROACH OF RCC BRIDGE OVER GANGA DHAR IN BETWEEN BAHORANPUR
AND DAMODARPUR VILLAGE

SL. No.	Item of Work	Amount
A	TOTAL COST OF CONSTRUCTION :	4.202 3.863
	TOTAL :	4.202 3.863 / see

Junior Engineer

Asstt. Engineer

Executive Engineer

CS
Gopal.
24/11/2021
EE RWD Derran

Sanctioned 3.863 lacs (Rupees)
Post fact technical, approved for Rs.
Three lacs Eighty Six Thousand
Three Hundred only.
RWD

Superintending Engineer,
Rural Works Department
Work Circle ABP

GENERAL ABSTRACT OF COST

NAME OF ROAD : APPROACH OF RCC BRIDGE OVER GANGA DHAR IN BETWEEN BAHORANPUR AND DAMODARPUR VILLAGE

DISTRICT : BHOJPUR

DIVISION : SAHPUR

DIVISION : JAGDISHPUR

SL. No.	DESCRIPTION	AMOUNT (LAKHS)
PART -A	INITIAL RECTIFICATION INCLUDING SURFAC RENEWAL	
1	BRICKS BATS	3.419 3.719
	ADD 12% GST ON RECTIFICATION COST	0.410 0.445
	ADD 1 % LABOUR CESS ON RECTIFICATION COST	0.034 0.037
	TOTAL COST OF CONST. IN LACS	3.863 4.202
	TOTAL COST OF PROJECT IN LACS	3.863 4.202

JE
RWD

18/11/2021
AE
RWD

20/11/21
EE
RWD

Name of the road:-		APPOACH OF RCC BRIDGEOVER GANGA DHAR BETWEEN BAHORANPUR AND DAMODARPUR VILLAGE			BLOCK	SAHPUR					
					DISTRICT	BHOJPUR					
SL. No.	SDB SL. NO.	MORD Ref. No.	Description	Unit	Nos	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1.	6.1	604	Brick Bats								
			Providing and laying of Brick bat obtained from chimney with machanical means with all spreading,grading to required slope and compacted at OMC to achieve required density with all comlete as per the direction of engineer in charge .								
			Net Qty. Required	Cum					198.2	1735.11	341917.2
										1876.3	374900
										9	371900
											TOTAL COST OF PAVEMENT IN RS. = 371900

JE
RWD

RWD

RWD

POT MEASUREMENT

CH	NO.	L	B	T	Area	Remarks
NORTH SIDE						
	1	7	7.5	$(0.80+0.50)/2$	34.12	
Shoulder	1	40	$(1.25+1.25)/2$	$(0.80+0.50)/2$	29.25	
Shoulder	1	40	$(1.25+1)/2$	$(0.80+0.50)/2$	29.25	
Shoulder	1	7	1.25	0.50	4.37	
Shoulder	1	7	1	0.50	3.5	
Shoulder	1	7.50	$(1.25+1)/2$	0.50	4.21	
	1	3	7	0.50	10.5	
Shoulder	1	7	3	0.50	10.5	
	1	5	4	$(0.60+0.30)/2$	9	
SOUTH SIDE						
Shoulder	1	11.5	2	0.50	11.5	
Shoulder	1	7	2	0.50	7	
	1	40	$(1+1.5)/2$	$(1+0.80)/2$	45	

total = 182

Total Area of Brick Bats

198.2

Boyle
20/11/2021
AE

112
20/11/21

C/S
Boyle
24/11/2021
LEE Road, Derrymore