



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar



BIHAR RURAL ROADS PROJECT

Bihar Rural Road Development Agency (BRRDA)

Govt. of Bihar

EMERGENT REPAIR OF ROAD FROM NH-30A TAMAULIYAPUL TO KORARI VIA BAGHATILA BANDICHAK UNDER FDR



Name of the Road :-

EMERGENT REPAIR OF ROAD FROM NH-30A TAMAULIYAPUL TO KORARI VIA BAGHATILA
BANDICHAK UNDER FDR

DISTRICT	:	Patna	
DIVISION	:	Barh	
BLOCK	:	Belchi	
Total Damaged length of Road	:	75.00 m	
TOTAL COST OF CONSTRUCTION	:	11.119	Lacs
TOTAL COST OF PROJECT	:	11.119	Lacs

Executive Engineer
Rural Works Division,
BARH

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :		EMERGENT REPAIR OF ROAD FROM NH-30A TAMAULIYAPUL TO KORARI VIA BAGHATILA BANDICHAK UNDER FDR
DISTRICT		PATNA
BLOCK		BELCHI
DIVISION		BARH
Total Damaged length of Road		15.00 m
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	COST OF ITEM	953112.75 ₹ 1,111,911.20
TOTAL COST IN LACS =		11.119 9.501

Bhamesh
28/10/21
JE
RWD

28/10/21
AE
RWD

28/10/21
EE
RWD

Technically sanctioned for Rs. 9.501 lac (Rupees Nine
lakh Fifty Three thousand one hundred
only)
~~including five year Maintenance Cost~~

sd
तकनीकी सलाहकार *sd* Superintending Engineer
ग्रामीण कार्य विभाग R.W.D. WORKS CIRCLE, PATNA
कार्य अंचल, पटना

Amur
16/12/2021
Superintending Engineer
R.W.D. WORKS CIRCLE, PATNA

प्रतिवेदन

पथ का नाम	:- एम0एच0-30ए तमौलिया पुल से कोरासी भाग बाघाटीला बंदीचक तक पथ की आपातकालीन मरम्मत। (3054 एम0आर0)
पथ की लम्बाई	:- 5.445 कि0मी0
प्राक्कलित राशि	:- 11.119 लाख रुपये
प्रखण्ड	:- बेलछी
मद	:- एफ0डी0आर0

प्रस्तुत प्राक्कलन बेलछी प्रखण्ड अंतर्गत तमौलिया पुल से कोरासी भाग बाघाटीला बंदीचक तक पथ की आपातकालीन मरम्मत हेतु तैयार किया गया है। इस वित्तीय वर्ष में बाढ़ एवं अतिवृष्टि के कारण पथ के एक स्थान पर चार आउट हो गया एवं विभिन्न स्थानों पर बड़े-बड़े गड़ढ़े बन गये हैं। विभागीय निर्देशानुसार पथ को यातायात योग्य बनाना है। यह पथ एम0आर0-3054 अन्तर्गत स्वीकृत जो तृतीय वर्ष के अनुसंधान के अन्तर्गत है। पथ के क्षतिग्रस्त पथांश में ग्रीक्स पैट भर दिया गया है। वर्तमान में आवागमन चालू है। अतः कार्यहिन में प्राक्कलन की स्वीकृति अति आवश्यक है।

BK...
28/10/21
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा बेलछी

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल बेलछी

...
28/10/21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल बाढ़

युनस-वः काम की जोन भवन द्वारा निर्धारित
कर्म प्रमंडल द्वारा करा ली गई है।
जोन प्रमंडल द्वारा

ड
19
में
को
में

प्रतिवेदन

कार्य का नाम :

एन०एच०-30 A तमोलिया पुल से ~~बिहटा सस्मेरा एक्स्प्रेस-रोड~~
कैरारी बाघटीला तक पथ की आपातकालीन मरम्मति ।

स्वीकृत पथ :-


पथ की लम्बाई : 5.445 ~~2.000~~ कि०मी०

प्राक्कलित राशि : रू० 11.119 लाख

मद : एफ० डी० आर०

प्रस्तुत प्राक्कलन बेलछी प्रखण्ड अंतर्गत तमोलिया पुल से बिहटा सस्मेरा एक्स्प्रेस-रोड
कैरारी बाघटीला तक पथ की आपातकालीन मरम्मति हेतु एक्स्प्रेसनामित कर रू० 11.119
लाख (ग्यारह लाख ग्यारह हजार नौ सौ रूपये) मात्र का तैयार किया गया है। विगत पिछले माह में
बाढ़ एवं अतिवृष्टि के कारण पथ के एक स्थान पर Washout हो गया एवं विभिन्न स्थानों पर
यातायात योग्य बनाना है, जिसके लिए पहले से ही संवेदक चयनित है। पथ के क्षतिग्रस्त पथांश में
ब्रीक्स वैट भर दिया गया है। वर्तमान में आवागमन चालू है। अतः कार्यहित में प्राक्कलन की
स्वीकृति अति आवश्यक है।

Bhumer
28/11/21
कनीय अभियंता
बेलछी


28/11/21
सहायक अभियंता
बेलछी

कार्यपालक अभियंता
(ग्रामीण कार्य विभाग)
कार्य प्रमंडल, बाढ़

NAME OF ROAD	BANDICHAQ UNDER FDR
EMERGENT REPAIR OF ROAD FROM NH-30A TAMAULIYAPUL TO KORARI VIA BAGHATILA	

02-29-56
SL-4-5918

95314
SF. 711555

EE (RWD)
WORK DIVISION
PATNA

AE(RWD):

Sl. No	Name of Block	Name of Road	Damage Location and Size	Status of Restoration			Traffic Status	Remarks
				Work Completed	Work in Progress	Work Yet To Be Started		
30	Pandarak	Goriyari Pull Road Darba Bhadaur to Goriyari	0.00 km To 0.100 Km, 0.500 Km To 0.520 Km, 0.950 Km To 0.965 Km, 1.200 Km To 1.225 Km and 1.800 Km To 1.840 Km (200 M)	Work Completed			Traffic is smooth	200 M E/W Partially Damage and 100 M Length Bolder Pitching Require, due to flow of River parallel to road.
31	Mokama	NH-31 To Shahbegpur	1.200 Km To 1.220 Km and 1.800 Km To 1.860 Km (80 M)	Work Completed			Traffic is smooth	No any damage. Traffic is smooth.
32	Belchhi	Fatehpur Masathlu Ekdianga Sikandra Path	0.00 Km To 1.500 Km (1500 M)	Work Completed			Traffic is smooth	No any damage. Traffic is smooth.
33	Ghoswari	NH-82 To Karra Path	1.000 Km To 3.000 Km (2000 M)	Work Completed			Traffic is smooth	2000 M flank damage. 150 M PCC Crack
34	Ghoswari	Ghoswari Karra Path To Prahadpur Karra Path	0.00 Km To 0.400 Km (400 M)	Work Completed			Traffic is smooth	No any damage. Traffic is smooth.
35	Belchhi	Bandi Chak Mandir or School to Bandi Chak	0.00 Km To 1.200 Km (1200 M)			Work Yet To Be Started	Traffic is not smooth	1200 M Flood Water Overtopped.
36	Belchhi	NH 31 Tamoliya korari via Bagha tila bandichak	2.400 Km To 3.000 Km, 3.700 Km To 4.500 Km (1400 M)			Work Yet To Be Started	Traffic is not smooth	1400 M Flood Water Overtopped. 40 M Road Wash Out.
37	Pandarak	Construction of Road From Bara Samera Road To Nirpur Mahato Tola	0.015 Km To 0.075 Km (60 M)			Work Yet To Be Started	Traffic is not smooth	60 M Flood Water Overtopped.

Executive Engineer,
RWD, Works Division, Barh

Sl. No	Division	Block	Road/Bridge Name	Scheme	Status	Is Maintenance (Y/N)	Len Gth (in Km)	Damage Part Length During Flood	Restoration Amount (in Lakh)	Remarks	Start Point		Intermediate Point	
											Latitude	Longitude	Latitude	Longitude
					(Comp./OnGoing)						Type	FDR Fin Year		
1	Barn	Athmalgola	Jalprakash Neta to Barhiya Village	MMG SY WB	Completed	Yes	2.85	0.2	8	400 Meter Flood Water Overtopped. GSB, Gr-II, Gr-III and BT Surface is damaged.	Road	2021-22	25.444256	85.59128
2	Barn	Athmalgola	Chandradip Rai Primary School to Sataba Bada Kucha	MMG SY WB	Completed	Yes	1.74	1.738	10	Water Logged in 1738 M Length.	Road	2021-22	25.462551	85.601855
3	Barn	Athmalgola	NH-31 to Ganjpur Gram Hote	NAB ARD	Completed	Yes	0.69	0.615	8	Water Logged in 615 M Length.	Road	2021-22	25.462269	85.592233
4	Barn	Athmalgola	Ramnagar Diyara Faguli Ram	MMG SY WB	Completed	Yes	0.63	0.6	8	Water Logged in 600 M Length.	Road	2021-22	25.478424	85.569273
5	Barn	Barn	Nadwan - Pratechur	PMG SY	Completed	No	4.7	0.15	8	Water Logged in 150 M Length.	Road	2021-22	25.412223	85.707838
6	Barn	Barn	Construction of Road from Barhiya to Sataba Road	MMG SY WB	Completed	No	4	1.8	10	1800 Meter Flood Water Overtopped.	Road	2021-22	25.293704	85.852711
7	Barn	Barn	Khumun Khanda Kona Par To Chandania Village	GTS NY	Completed	Yes	2	0.35	10	350 Meter Flood Water Overtopped. PCC Crack and Paint damage.	Road	2021-22	25.393775	85.737725
8	Barn	Belchhi	LDSP-Korai to Paighambarpur	PMG SY	Completed	Yes	0.88	0.01	2	HYP Culvert has been damaged.	Road	2021-22	25.321614	85.657065
9	Barn	Belchhi	Fatehpur Masatthu Eldanga	MR	Completed	No	8	1.5	10	1500 Meter Flood Water Overtopped.	Road	2021-22	25.392124	85.698528
10	Barn	Belchhi	Gram Pura to Gram Manikaura Via Gram Naya Bigha Tak	MR	Completed	Yes	4.5	0.65	5	200 Meter Flood Water Overtopped.	Road	2021-22	25.432233	85.648009
11	Barn	Belchhi	NH-30A (Salbona Barn Road) to Brahmi Ashan	NAB ARD	Completed	Yes	0.5	0.15	15	Flood/Rain Water Log. Require RCC Culvert (1 X 6 X 4 M)	Road	2021-22	25.404661	85.707023
12	Barn	Belchhi	NH-30A to Chibanya Path	MR	Completed	Yes	1.88	0.07	5	Water Logged in 70 M Length.	Road	2021-22	25.360475	85.682171
13	Barn	Belchhi	LDSP-NH-30A to Chibanya Path to Bina - Sarmara SM Road via Korai Baghalla (SR-26P2R-01)	PMG SY WB	On Going	No	7.25	0.2	4	Flood Water Overtopped in 200 M Length.	Road	2021-22	25.357044	85.647769
14	Barn	Chitwan	Construction of Road from Ghoswari Karra Path to Mahadipur Karra Path in Ghoswari block under Patna	NAB ARD	On Going	No	0.73	0.4	8	400 Meter Flood Water Overtopped.	Road	2021-22	25.369971	85.8575
													25.366952	85.859208
													25.367957	85.859208

अधीक्षण अभियंता का कार्यालय,
ग्रामीण कार्य विभाग, कार्य अंचल, पटना।

पत्रांक-
प्रेषक,

851 (अ-30)

/पटना, दिनांक-21/06/2021

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, पटना

सेवामें,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बाढ़।

विषय:- Very Short Notice No. RWD/FDR/Patna /01(2021-22) के तहत आनत्रित कोटेशन
अंतर्गत कार्य प्रमंडल, बाढ़ में न्यूनतम दर दाता के साथ एकरारनामा करने के संबंध में।

महाराज,

उपर्युक्त विषय के संबंध में कहना है कि कोटेशन के माध्यम से प्राप्त आनत्रित निविदा में तकनीकी विवरणी एवं वित्तीय विवरणी में सफल एवं न्यूनतम दर दाता M/S Sundar Nirman घोषित किए गए हैं। इनके द्वारा उद्धृत न्यूनतम दर इस पत्र के साथ संलग्न कर भेजी जा रही है। यदि दरों में कोई त्रुटि दृष्टिगोचर हो तो अविलंब उसका निराकरण करा लिया जाये।

अतः आपको निदेश दिया जाता है कि उक्त संवेदक से 03 (तीन) दिनों के अंदर एकरारनामा करते हुए उसकी सूचना अधोहस्ताक्षरी के कार्यालय में समर्पित करना सुनिश्चित करें साथ ही साथ अन्य संवेदक अगर इसी न्यूनतम दर पर कार्य करने हेतु ईच्छुक हो तो उन्हें भी सूचीबद्ध कर ली जाये, ताकि भविष्य में आवश्यकता पड़ने पर उनसे काम लिया जा सके।

संबंधित संवेदक का प्राप्त अग्रघन की राशि पत्र के साथ संलग्न की जा रही है।

अनु0-यथोक्त।

विरवात्तनाजन

21/06/21

अधीक्षण अभियंता

ग्रामीण कार्य विभाग, कार्य अंचल, पटना

21-06-21

21-06-21

Sl. No.	Material	Specifications	Unit	Lowest M/S Sundar Nirman Bidder Rate	Amount in Word
1	Empty Cement Bags	Empty Cement Bags, Synthetic should be old but in good condition of 1.20 cft. Capacity.	Each	8.71	Eight Rupees & Seventy One Paise
2	Bamboos	Bamboos should be 100mm dia 6 to 8m long.	Each	170.00	One Hundred & Seventy Rupees
3	Brickbats		M3	1741.00	One Thousand Seven Hundred & Forty One Rupees
4	Local Sand		M3	337.00	Three Hundred & Thirty Seven Rupees
5	Kiln Rubbish		M3	1068.00	One Thousand & Sixty Eight Rupees
6	Hume Pipe (NP3) 600mm Dia		M	1044.50	One Thousand Forty Four & Fifty Paise
7	Hume Pipe (NP3) 1000mm Dia		M	3362.80	Three Thousand Three Hundred Sixty Two & Eighty Paise
8	Boulders	Minimum Size 300mm	M3	1861.35	One Thousand Eight Hundred Sixty One & Thirty Five Paise
9	Granular Sub base Material Grading-II		M3	1814.00	One Thousand Nine Hundred & Ninety Rupees
10	Stone Metal Aggregates Gr-II		M3	1857.00	One Thousand Eight Hundred & Fifty Seven Rupees
11	Stone Metal Aggregates Gr-III		M3	1810.26	One Thousand Eight Hundred Ten & Twenty Six Paise
12	Screening Material Type-B		M3	2712.58	Two Thousand Seven Hundred Twelve & Fifty Eight
13	Nylone Crate	Nylone crate of size 1m3(1mx1mx1m) with 20mm mesh of specification 12603/4/2X ie having 24 threads of weight 165 1/2-gm.	Each	45.00	Forty Five Rupees

Estimator
R.W.D.

पाकटोन पदाधिकारी
आम्रकोट

तकनीकी सलाहकार
प्राचीन कारी विभाग

Supervising Engineer

Sl. No.	Rate	Quantity	Unit	Lowest Bidder's Bidder Rate	Amount in Word
1	Unskilled Labour	110 cft. Soft Earth.	Each	329.00	Three Hundred & Twenty Nine Rupees
2	Semi Skilled Labour		Each	343.00	Three Hundred & Forty Three Rupees
3	Skilled labour		Each	418.00	Four Hundred & Eighteen Rupees
4	Mason		Each	396.00	Three Hundred & Ninety Six Rupees
5	Head mason		Each	445.00	Four Hundred & Forty Five Rupees
6	Bhisti		Each	329.00	Three Hundred & Twenty Nine Rupees
7	Carpenter		Each	396.00	Three Hundred & Ninety Six Rupees
8	Head Carpenter		Each	445.00	Four Hundred & Forty Five Rupees
9	Night Guard		Each	343.00	Three Hundred & Forty Three Rupees
10	Electrician		Each	421.00	Four Hundred & Twenty One Rupees

21/10/21

Estimator

R.W.D

Works Circle, Patna

प्राक्कलन पदाधिकारी

आजीन कार्य विभाग

कार्य अंचल पटना

21/10/21

तकनीकी सलाहकार

आजीन कार्य विभाग

कार्य अंचल, पटना

21/10/21

Superintending Engineer

R.W.D. WORKS CIRCLE, PATNA

Sl.	Description of Machine	Activity	Output of Machine	Output	Unit	Lowest M/S Sundar Nirman Bidder Rate	Amount in Word
1.	Front End Loader 1.0 cum bucket capacity (JCB)	Soil Loading/Aggregate Loading	Cum/hour	60/25	Per Hour	1585.00	One Thousand Five Hundred & Eighty Five Rupees
2.	8-10 Ton Smooth Wheeled Roller	Compaction/ Consolidation	Cum/hour	70/25	Per Hour	907.00	Nine Hundred & Seven Rupees
3.	Tractor with Trolley	Transportation of Material	25 HP Capacity	3 to 5 Ton	Ton/ Trip	647.00	Six Hundred & Forty Seven Rupees
4.	Tipper	Transportation of Material	Cum	5.50	Ton/ Trip	41.50	Forty One & Fifty Paise
5.	Tractor with Tipper	Transportation of Material	25 HP Capacity	3 to 5 Ton	Ton/ Trip	667.50	Six Hundred Sixty Seven & Fifty Paise
6.	Generator Set	Generation of Electrical energy	KVA	5	Per Hour	4183.00	Four Thousand One Hundred & Eighty Three Rupees

[Signature]
21/06/21

Estimator

R.W.D.

Works Circle, Patna

[Signature]
21/06/21

प्रमुख पदाधिकारी

आजीन कार्य विभाग

कार्य अंचल, पटना

[Signature]
21/06/21

तकनीकी सलाहकार

ग्रामीण कार्य विभाग

कार्य अंचल, पटना

[Signature]
21/06/21

Superintending Engineer

R.W.D. WORKS CIRCLE, PATNA

अधीक्षण अभियंता का कार्यालय,
ग्रामीण कार्य विभाग, कार्य अंचल, पटना।

पत्रांक- 851 (अनु०)
प्रेषक,

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, पटना

संबन्धित,
कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बाढ़।


विषय:- Very Short Notice No. RWD/FDR/Patna /01(2021-22) के तहत कार्यगत कोटेशन
अंतर्गत कार्य प्रमंडल, बाढ़ में न्यूनतम दर दाता के साथ एकत्रित करने के संबंध में।

महाराय,
उपरोक्त विषय के संबंध में कहना है कि कोटेशन के माध्यम से प्राप्त आवेदन पत्रों में
तकनीकी विवरणी एवं वित्तीय विवरणी में सफल एवं न्यूनतम दर दाता M/S Sunder Mirman केवल
किए गए हैं। इनके द्वारा उद्धृत न्यूनतम दर इस पत्र के साथ संलग्न कर भेजी जा रही है। यदि दलों में
कोई त्रुटि दृष्टिगोचर हो तो अविलंब उसका निराकरण करा लिया जाये।

अतः आपको निर्देश दिया जाता है कि उक्त संवेदक से 03 (तीन) दिनों के अंदर एकत्रित
करते हुए उसकी सूचना अधोहस्ताक्षरी के कार्यालय में समर्पित करना सुनिश्चित करें साथ ही साथ उक्त
संवेदक अगर इसी न्यूनतम दर पर कार्य करने हेतु ईच्छुक हो तो उन्हें भी सूचीबद्ध कर दी जाये, ताकि
भविष्य में आवश्यकता पड़ने पर उनसे काम लिया जा सके।

संबन्धित संवेदक का प्राप्त अध्वन की राशि पत्र के साथ संलग्न की जा रही है।
अनु०-यथोक्त।

विरदासनजन


अधीक्षण अभियंता
ग्रामीण कार्य विभाग, कार्य अंचल, पटना

pin\2021\FDR\DR Work Order.Docx


Executive Engineer
R. G. S. D. Work Order Scanner
BARH 26/06/21

Lowest Bidder Rate
Works Division : Barh

Sl. No.	Material	Specifications	Unit	Lowest M/S Sunder Nirman Bidder Rate	Amount in Word
1	Empty Cement Bags	Empty Cement Bags, Synthetic should be old but in good condition of 1.20 cft. Capacity.	Each	8.71	Eight Rupees & Seventy One Paise
2	Bamboos	Bamboos should be 100mm dia 6 to 8m long.	Each	170.00	One Hundred & Seventy Rupees
3	Brickbats		M3	1741.00	One Thousand Seven Hundred & Forty One Rupees
4	Local Sand		M3	337.00	Three Hundred & Thirty Seven Rupees
5	Kiln Rubbish		M3	1068.00	One Thousand & Sixty Eight Rupees
6	Hume Pipe (NP3) 600mm Dia		M	1044.50	One Thousand Forty Four & Fifty Paise
7	Hume Pipe (NP3) 1000mm Dia		M	3362.80	Three Thousand Three Hundred Sixty Two & Eighty Paise
8	Boulders	Minimum Size 300mm	M3	1861.35	One Thousand Eight Hundred Sixty One & Thirty Five Paise
9	Granular Sub base Material Grading-II		M3	1814.00	One Thousand Nine Hundred & Ninety Rupees
10	Stone Metal Aggregates Gr-II		M3	1857.00	One Thousand Eight Hundred & Fifty Seven Rupees
11	Stone Metal Aggregates Gr-III		M3	1810.26	One Thousand Eight Hundred Ten & Twenty Six Paise
12	Screening Material Type-B		M3	271.58	Two Thousand Seven Hundred Twelve & Fifty Eight Paise
13	Nylon Crute	Nylon crute of size 1m3(1mx1mx1m) with 20cm mesh of specification 12603/4/2 to having 24no of threads of weight 165 +/5gm.	Each	45.00	Forty Five Rupees

Estimator

[Signature]
21/6/21

Superintendent

[Signature]
21/6/2021

[Signature]

Executive Engineer
R.W.D. Works Division
BARH
21/6/21

II. LABOUR
Works Division : Barh

	Type	Output	Unit	Lowest M/S Sundar Nirman Bidder Rate	Amount in Word
1	Unskilled Labour	110 cft. Soft Earth.	Each	329.00	Three Hundred & Twenty Nine Rupees
2	Semi Skilled Labour		Each	343.00	Three Hundred & Forty Three Rupees
3	Skilled labour		Each	418.00	Four Hundred & Eighteen Rupees
4	Mason		Each	396.00	Three Hundred & Ninety Six Rupees
5	Head mason		Each	445.00	Four Hundred & Forty Five Rupees
6	Bhisti		Each	329.00	Three Hundred & Twenty Nine Rupees
7	Carpenter		Each	396.00	Three Hundred & Ninety Six Rupees
8	Head Carpenter		Each	445.00	Four Hundred & Forty Five Rupees
9	Night Guard		Each	343.00	Three Hundred & Forty Three Rupees
10	Electrician		Each	421.00	Four Hundred & Twenty One Rupees

Estimator
R.W.D.

पावरफुल पदाधिकारी
जनार्दन झाद बिभाग
कार्य अंचल पटना

सहायकी सलाहकार
ग्रामीण कार्य विभाग
कार्य अंचल, पटना

Superintending Engineer
R.W.D. WORKS CIRCLE, PATNA

Executive Engineer
Works Division
BARH
28/06/21

III. TOOLS PLANTS & MACHINERIES WITH DRIVER & FUEL Works Division : Barh

Description of Machine	Activity	Output of Machine	Output	Unit	Lowest M/S Sundar Birman Bidder Rate	Amount in Word
Front End Loader 1.0 cum bucket capacity (JCB)	Soil Loading/Aggregate Loading	Cum/hour	60/25	Per Hour	1525.00	One Thousand Five Hundred & Eighty Five Rupees
8-10 Ton Smooth Wheeled Roller	Compaction/Consolidation	Cum/hour	70/25	Per Hour	907.00	Nine Hundred & Seven Rupees
Tractor with Trolley	Transportation of Material	25 HP Capacity	3 to 5 Ton	Ton/ Trip	647.00	Six Hundred & Forty Seven Rupees
Tipper	Transportation of Material	Cum	5.50	Ton/ Trip	41.50	Forty One & Fifty Paise
Tractor with Tipper	Transportation of Material	25 HP Capacity	3 to 5 Ton	Ton/ Trip	667.50	Six Hundred Sixty Seven & Fifty Paise
Generator Set	Generation of Electrical energy	KVA	5	Per Hour	4183.00	Four Thousand One Hundred & Eighty Three Rupees

[Signature]
Estimator
R.W.D.
Works Circle, Patna

[Signature]
प्रमुख कार्यकारी
आजीव कार्य विभाग
कार्य अंचल पटना

[Signature]
समय-समय सेलियर
आजीव कार्य विभाग
कार्य अंचल, पटना

[Signature]
Supersintending Engineer
R.W.D. WORKS CIRCLE, PATHA

[Handwritten Signature]

[Signature] 28/06/21
Examined by Engineer
R.W.D. Works Division
BARH 28/06/21

कार्यपालक अभियन्ता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, बाढ़

पत्रांक 784 / बाढ़ / दिनांक 28/06/21

प्रेषक,
कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल बाढ़।

सेवा में,
मेसर्स सुन्दर निर्माण,
सहजानन्द नगर, वार्ड नं०-01, बाढ़, पटना।

विषय :- बाढ़/अतिवृष्टि से क्षतिग्रस्त पथों के परिचालन हेतु सामग्रियों की आपूर्ति
हेतु कार्यादेश के सम्बन्ध में।

प्रसंग :- एकरारनामा संख्या 02/एफ02/2021-22

महोदय,

उपर्युक्त विषय के सम्बन्ध में कहना है कि अधीक्षण अभियन्ता ग्रामीण कार्य
विभाग, कार्य अंचल पटना के पत्रांक 851/अनु० दिनांक 21.06.2021 के आलोक में
विषयगत कार्य हेतु आपका एकरारनामा कर लिया गया है। जिसका एकरारनामा
संख्या 02/एफ02/2021-22 दिनांक 28.06.2021 है। उक्त एकरारनामा वित्तिय वर्ष
2021-22 के लिए मान्य होगा।
सूचनार्थ प्रेषित।

विश्वासभाजन

[Signature] 28/06/21
कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बाढ़
28/06/21

कार्यपालक अभियन्ता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, बाढ़

पत्रांक 784 / बाढ़ / दिनांक 28/06/21
प्रेषक,

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल बाढ़।

सेवा में,

मेसर्स सुन्दर निर्माण,
सहजानन्द नगर, वार्ड नं०-01, बाढ़, पटना।

विषय :- बाढ़/अतिवृष्टि से क्षतिग्रस्त पथों के परिचालन हेतु सामग्रियों की आपूर्ति
हेतु कार्यादेश के सम्बन्ध में।

प्रसंग :- एकरारनामा संख्या 02/एफ02/2021-22

महाशय,

उपर्युक्त विषय के सम्बन्ध में कहना है कि अधीक्षण अभियन्ता ग्रामीण कार्य
विभाग, कार्य अंचल पटना के पत्रांक 851 अनु० दिनांक 21.06.2021 के आलोक में
विषयगत कार्य हेतु आपका एकरारनामा कर लिया गया है। जिसका एकरारनामा
संख्या 02/एफ02/2021-22 दिनांक 28.06.2021 है। उक्त एकरारनामा वित्तिय वर्ष
2021-22 के लिए मान्य होगा।

सूचनार्थ प्रेषित।

विश्वासमाजन

28/06/21
कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बाढ़।

ज्ञापांक / बाढ़ / दिनांक
प्रतिलिपि :- अधीक्षण अभियन्ता, ग्रामीण कार्य विभाग, कार्य अंचल पटना को सूचनार्थ
समर्पित।

28/06/21
कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बाढ़।

ज्ञापांक / बाढ़ / दिनांक
प्रतिलिपि :- सभी कनीय अभियन्ता/सहायक अभियन्ता ग्रामीण कार्य विभाग कार्य
प्रमंडल बाढ़ को सूचनार्थ एवं आवश्यक कारवाई हेतु समर्पित।

28/06/21
कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बाढ़।
28-6-21

Inspection Report for Flood Damage Work

Date :- 24.11.21

1. Name of PIUs :- Executive Engineer, RWD, works(D) Barh
2. Name of Block / Road :- Belchi / NH30A Tamauliya to Bihta Samara
SH Road via Kauri Baghatila
- A. For Road
 1. Damage Location / Chainage :- Between ch. 2.700 to 2.750 Km
 2. Damage Length :- 42m
 3. Nature of Damage :- Breach and scour in the road due to flood.
 - i. Material being used in Restoration works :- Bricks bats
 - ii. Equipments / Tools being used in Restoration works : J.C.B., tractor
 - iii. Procedure taken up in Restoration works : Bricks bats spreading & laying
 - iv. Restored Length : 42 m
- B. For Bridge
 1. Damage Location / Chainage :-
 2. Damage Length :-
 3. Nature of Damage :-
 4. Details of Restoration Works :-
 - i. Material being used in Restoration works :-
 - ii. Equipments / Tools being used in Restoration works
 - iii. Procedure taken up in Restoration works :
 - iv. Restored Length :

N/A

Amey
02/12/21
AE


Name of Inspector
Executive Engineer
R.W.D. Works Division, Patna