



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar



BIHAR RURAL ROADS PROJECT

Bihar Rural Road Development Agency (BRRDA)

Govt. of Bihar

EMERGENT REPAIR OF ROAD FROM T01 OLD PANAPUR TO KEDALPURA UNDER FDR



Name of the Road :-

EMERGENT REPAIR OF ROAD FROM T01 OLD PANAPUR TO KEDALPURA UNDER FDR

DISTRICT	:	Patna	
DIVISION	:	Danapur	
BLOCK	:	Danapur	
Total Damaged length of Road		0.540492	km
Total Length of Road		4.920492	Km
TOTAL COST OF CONSTRUCTION	:	2.452	Lacs
TOTAL COST OF PROJECT	:	2.379	Lacs

Executive Engineer

Rural Works Division,

Danapur

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :		EMERGENT REPAIR OF ROAD FROM T01 OLD PANAPUR TO KEDALPURA UNDER FDR	
DISTRICT		PATNA	
BLOCK		DANAPUR	
DIVISION		DANAPUR	
Total Damaged length of Road		4.920 km 0.540Km	
Total Length of Road		4.920Km	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)	
1	COST OF ITEM	2,37,900.00 ₹ 2,45,220.00	
	TOTAL COST IN LACS =	2.452 2.379 ✓	

[Signature]
28/10/21
JE
RWD

[Signature]
28/10/21
AE
RWD

[Signature]
9/11/21
EE
RWD
[Signature]
28/10/21

Technically sanctioned for Rs. 2.379 (Rupees. Two Lacs
Hundred and thirty seven thousand and nine hundred only)

including five year Maintenance Cost

[Signature]
18/11/22
Estimator
R.W.D.
Works Circle, Patna

तकनिकी सलाहकार
ग्रामीण कार्य विभाग
कार्य अंचल, पटना

[Signature]
13/10/2022
Superintending Engineer
R.W.D. WORKS CIRCLE, PATNA

प्रतिवेदन

कार्य का नाम :

टी01 पुराना पानापुर से खेदलपुरा पथ का आपातकालीन मरम्मत ।

क्षतिग्रस्त पथांश की लम्बाई : 0.540 कि० मी०


प्राक्कलित राशि : ^{2.379}रु० 2.452 लाख

मद : ¹एफ० डी० आर०

प्रस्तुत प्राक्कलन दानापुर प्रखण्ड अंतर्गत टी01 पुराना पानापुर से खेदलपुरा पथ का आपातकालीन मरम्मत का पूर्व एकरारनामित दर पर ^{2.379}रु० 2.452 लाख (दो लाख ^{सैंतीस} पाँच हजार ^{नौ} सौ रूपये) मात्र का तैयार किया गया है । इस वर्ष के भीषण बाढ़ से पथ के चैनेज 20 मी० से 220 मी० एवं 220 मी० से 560 मी० पथांश पर Sandy Soil भर गया है । विभागीय निर्देशानुसार पथ को यातायात योग्य बनाना है, जिसके लिए पहले से ही संवेदक चयनित है । पथ पर भरे हुए Sandy Soil को हटाया जाना है । वर्तमान में आवागमन चालू है । अतः कार्यहित में प्राक्कलन की स्वीकृति अपेक्षित है ।


कर्मिय अभियंता
दानापुर


सहायक अभियंता
दानापुर


कार्यपालक अभियंता
(ग्रामीण कार्य विभाग)
कार्य प्रमंडल दानापुर




2/11/15
2/11/15

3. 4 2
12/01/2020
20/01/2020

28/11/22

Division	Block	Name of Road	7	8	9	10	11	12
3	5							
ANAPUR	MANER	NH-30 Khaspur Hanuman Mandir To Chamarol Aanganbas Kendra	AT CH-0.700 Km To 1.30 Km	-	-	Y	Traffic Partially Disturbed	Waterlogged
ANAPUR	DANAPUR	T01- T01 Old Panapur To Kedapura	0.00 Km To 4.920 Km	-	-	Y	Traffic fully disturb	Waterlogged
ANAPUR	DANAPUR	Habasapur PCC Road To Habasapur West Toi Tank	AT CH-0.200 To 0.700 Km	-	-	Y	Traffic Partially Disturbed	Waterlogged
ANAPUR	DANAPUR	Ashpur Lakshmi Bagha Road Near Holy Mission School To Ust Village	AT CH-0.335 To 0.485 Km	-	-	Y	Traffic Partially Disturbed	Waterlogged
ANAPUR	DANAPUR	Panapur PMGSY Road To Old Panapur	AT CH-0.350 Km To 0.600 Km	-	-	Y	Traffic fully disturb	Waterlogged
ANAPUR	DANAPUR	Panapur To Shankapur Via Harish Chak Madhopur	AT CH-0.00 Km To 6.90 Km	-	-	Y	Traffic fully disturb	Waterlogged
ANAPUR	DANAPUR	Panapur To Manas Via Nandiyen	AT CH-0.002 Km To 3.50 Km	-	-	Y	Traffic fully disturb	Waterlogged
ANAPUR	DANAPUR	Link Road of Panapur Shankapur Road To Gangahara Path	AT CH-0.00 Km To 4.50 Km	-	-	Y	Traffic fully disturb	Waterlogged
ANAPUR	DANAPUR	Manas Bera Pul To Manas BasantPati Toia	AT CH-0.00 Km To 4.50 Km	-	-	Y	Traffic fully disturb	Waterlogged
ANAPUR	DANAPUR	Habasapur To Gangahara Naunhya Toia	AT CH-0.00 Km To 2.05 Km	-	-	Y	Traffic fully disturb	Waterlogged
ANAPUR	DANAPUR	Bhuyyan Basawan Shan Jafapur To Madhopur School Jafapur	AT CH-0.00 Km To 0.650 Km	-	-	Y	Traffic fully disturb	Waterlogged
ANAPUR	DANAPUR	Vasnapur To Kalerpur Harishchak Road Via Pani Tanki	AT CH-0.00 Km To 0.975 Km	-	-	Y	Traffic fully disturb	Waterlogged
ANAPUR	DANAPUR	Hemanpur To Pallaipur	AT CH-0.00 Km To 1.320 Km	-	-	Y	Traffic fully disturb	Waterlogged

27/07/23
 R.K.C.
 27/07/23

27/07/23
 A.B.

27/07/23
 A.B.

EMERGENT REPAIR OF ROAD FROM T01 OLD PANAPUR TO KEDALPURA UNDER FDR

S. No.	SDB Sl. NO	MORD Ref.No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1			Supplying Unskilled Labour for Sandy soil disposal from road including labour cess and GST (excluding over head, CP andseignorage fee).							22500	2,27,900/-
				nos.					732.00	-335.00	-2,45,220.00
									TOTAL	Rs	2,27,900/- 2,45,220.00

JE (RWD)

AE(RWD)
28/10/21

EE (RWD)
WORK DIVISION
DANAPUR
Date 9/1/72
28/10/72

NAME OF ROAD	EMERGENT REPAIR OF ROAD FROM T01 OLD PANAPUR TO KEDALPURA UNDER FDR
--------------	---

BLOCK – DANAPUR				DIVISION - DANAPUR				
POT MEASUREMENT								
		NO.		L	W	II	m3	
1)	SANDY SOIL DISPOSAL							
	Ch. 20m to 220m	1	x	200.00	x	5.00	x 0.75 (avg.) =	750.00
	Ch. 220 m to 560 m	1	x	340.00	x	5.00	x 0.90 (avg.) =	1530.00
						TOTAL Qty =	2280.00	m3
						In terms of cft	80506.80	cft
						@ 110 cft / per labour	732.00	

[Signature]
JE
28/10/21

[Signature]
AE
28/10/21

[Signature]
EE
RWD
28/10/21

Inspection Report for Flood Damage Work

Date :- 27-11-2021

1. Name of PIUs :- E.E. R.W.D(W) Division. Masaurhi
2. Name of Block / Road :- Damage / Removal of excess Cray's Sand from Road Crust - To Old Pangpur to K. L. / P. due to Flood.
- A. For Road
 1. Damage Location / Chainage :- In 1st K.M. where work is required.
 2. Damage Length :- 0.540 K.M.
 3. Nature of Damage :- Excess Cray's Sand removal on the Road Crust.
 - i. Material being used in Restoration works :- Sand Removal work.
 - ii. Equipments / Tools being used in Restoration works : JCB, Tractor
 - iii. Procedure taken up in Restoration works : Excess Cray's Sand removal
 - iv. Restored Length : 0.540 K.M.
- B. For Bridge
 1. Damage Location / Chainage :-] NIL
 2. Damage Length :-]
 3. Nature of Damage :-]
 4. Details of Restoration Works :-
 - i. Material being used in Restoration works :- Excess Cray's Sand removal.
 - ii. Equipments / Tools being used in Restoration works : JCB, Tractor.
 - iii. Procedure taken up in Restoration works : Removal of Excess Cray's Sand from Road Crust.
 - iv. Restored Length : 0.570 K.M.

27/11/2021
SR/Manager

27/11/2021
BZ

APAS
Name of Inspector
Executive Engineer
R.W.D. Works Division, Masaurhi

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, मसौदी

पत्राक- 127 (330)

मसौदी/दिनांक- 06-12-2021

प्रेषक- कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मसौदी।

सया में,

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, पटना।

विषय वर्ष-2020 में अतिवृष्टि/बाढ़ से क्षतिग्रस्त पथों को मोटरेबुल करने हेतु किये गए कार्य की
जॉच के संबंध में।

पसंग- विभागीय पत्राक-मु0अ0-4(मु0) विविध(कार्य)-23-291/2019-4589 दिनांक-13.11.2021
एवं भवदीय के पत्राक-1482 दिनांक-25.09.2021

महाशय,

उपर्युक्त विषयक प्रासंगिक पत्र के निर्देश के आलोक में ग्रामीण कार्य विभाग, कार्य प्रमंडल,
दानापुर का निम्नलिखित नौ(09) पथों का दिनांक-24.11.2021 एवं 26.11.2021 को बाढ़ क्षतिग्रस्त
मरम्मत कार्य का जॉच किया गया एवं किया गया संतोषप्रद पाया गया।

सूचनार्थ समर्पित।

क्रमांक	पथ का नाम	पथ की लम्बाई	क्षतिग्रस्त पथ की ल0 (कि0मी0)
1	कंदलपुरा से शंकरपुर भाया हरशामचक	11.40	0.030
2	PMGSY रोड से Old पानापुर	0.600	0.300
3	Old पानापुर से कंदलपुरा	4.920	0.540
4	पानापुर से शंकरपुर भाया हरशाम चक माधोपुर	6.90	0.820
5	आशापुर सुर्य मंदिर से ओमनगर (सुर्य नगर) दीपक जी के घर तक	0.750	0.750
6	चकरदाहा मोड से नवरतनपुर	1.05	0.250
7	रामबाद से सुअरमरवा	2.00	0.470
8	REC रोड से बाजितपुर मोड	3.00	2.10
9	गनर से रामबाद	2.10	2.10

अनु- निरीक्षण प्रतिवेदन प्रपत्र सलग्न।
(दो प्रतियों में)

विश्वारामाजन

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मसौदी।