

बिहार सरकार

## FLOOD DAMAGE REPAIR (FDR)

YEAR 2021-22

FOR T/A

DISTRICT :- BEGUSARAI  
BLOCK :- ~~BHAGWANPUR~~  
Teghra

|                   |    |               |
|-------------------|----|---------------|
| CONSTRUCTION COST | :- | Rs. 4.246 Lac |
| TOTAL COST        | :- | Rs. 4.246 Lac |

PMGSY YOJNA

NAME OF ROAD :- FLOOD DAMAGE REPAIR OF ROAD  
NH-28 TO AYODHA.

|                            |   |           |
|----------------------------|---|-----------|
| TOTAL LENGTH               | : | 2.50 KM   |
| LENGTH DAMAGE DUE TO FLOOD | : | 0.887 KM. |

SUBMITTED BY:

EXECUTIVE ENGINEER

R.W.D. WORKS DIVISION, TEGHRA






Name of Road :- **Flood Damage Repair of Road  
NH-28 To Ayodha.**


Year 2021-22

|          |    |           |
|----------|----|-----------|
| District | :- | Begusarai |
| Block    | :- | Teghra    |

**GENERAL ABSTRACT OF COST**

| Sl No. | Item of Work                                                                                              | Amount (in Rs.)<br>As Per Estimate                                                                          |
|--------|-----------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------|
| 1      | COST OF FDR                                                                                               | 3,69,511.00                                                                                                 |
| 2      | Add L.C. @1%                                                                                              | 3,695.00                                                                                                    |
| 3      | ADD GST @ 12%                                                                                             | 44,341.00                                                                                                   |
|        | Add S.F. @ 10% on Material Rate                                                                           | 7,039.00                                                                                                    |
|        | <b>Total Rs. :-</b>                                                                                       | <b>4,24,586.00</b>                                                                                          |
|        | <b>Say Rs. :-</b>                                                                                         | <b>4,24,600.00</b>                                                                                          |
|        | <br>J.E.<br>RWD. Teghra | <br>A.E.<br>RWD. Teghra  |
|        |                                                                                                           | <br>E.E.<br>RWD. Teghra |

Technically Approved for 4,24,600 = 00 say four lakh  
twenty four thousand and Six Hundred only. in words  
@ H.C and C.P.

  
10.12.21  
बसावत बाधक  
बाधीत बाधे विभाग  
बाधे बाधक, प्रयत्नीक  
10.12.21

| SDB<br>SL.NO | MOR<br>D<br>Ref.N | Description                                                                                                                                                                                                                                                                                                                                                                    | Unit | NOS | LENGTH | WIDTH | HEIGHT | QUANTITY | RATE     | AMOUNT (in Rs.) |
|--------------|-------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-----|--------|-------|--------|----------|----------|-----------------|
| 1.           |                   | Providing brick bats including ,spreading,laying, hand packing with CI hammers in layers has exceeding 75mm thick including cost of light barriers,danger equal,choukidar,taxes,royalty etc all complete job, as per specifications and direction of E/I including cost of bricks,.....all complete job.                                                                       |      |     |        |       |        |          |          |                 |
|              |                   | Qty From Calculation Sheets                                                                                                                                                                                                                                                                                                                                                    | Cum  |     |        |       |        | 66.19    | 1896.75  | 1,25,552.00     |
| 2.           |                   | Construction of road embankment materials obtained from borrow pits .....all complete job as per clouse 300.1,300.2 with lead upto 1000m                                                                                                                                                                                                                                       |      |     |        |       |        |          |          |                 |
|              |                   | Qty From Calculation Sheets                                                                                                                                                                                                                                                                                                                                                    | Nos  | 0   | X      | 0     |        | 0.00     | 173.25   | 0.00            |
| 3.           |                   | Granular Sub - base with well graded materials (table 400.1) Gr II                                                                                                                                                                                                                                                                                                             |      |     |        |       |        |          |          |                 |
|              | 4.1(ii)           | ( A ) By Mix in Place Method Construction of granular sub base by providing well graded materials. Spreading in uniform layers with motar grader on prepared surface, mixing by mix in place method with rotovator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification clause 401 For Grading ii Materials |      |     |        |       |        |          |          |                 |
|              |                   |                                                                                                                                                                                                                                                                                                                                                                                |      |     |        |       |        | 120.578  | 2,023.26 | 2,43,959.00     |
|              |                   |                                                                                                                                                                                                                                                                                                                                                                                |      |     |        |       |        | Total =  |          | 369511.00       |

*J.E.*  
22/11/2024  
J.E.  
RWD. Teghra

*A.E.*  
22/11/24  
A.E.  
RWD. Teghra

*E.E.*  
23/11/24  
E.E.  
RWD. Teghra

कार्यपालक अभियंता का कार्यालय

ग्रामीण कार्य विभाग , कार्य प्रमण्डल, समस्तीपुर

पत्रांक-

Camp, Teghda, 01

दिनांक- 7.12.21

प्रेषक,

कार्यपालक अभियंता

ग्रामीण कार्य विभाग ,

कार्य प्रमण्डल, समस्तीपुर ।

सेवा में,

कार्यपालक अभियंता

ग्रामीण कार्य विभाग ,

कार्य प्रमण्डल, तेघड़ा (बेगूसराय)।

विषय: शीर्ष-FDR अन्तर्गत पथों की जांच प्रतिवेदन समर्पित करने के संबंध में

प्रसंग : कार्यपालक अभियंता, ग्रामीण कार्य विभाग, तेघड़ा (बेगूसराय) के पत्रांक- 1 दिनांक- 24.11.2021

महाशय,

उपर्युक्त विषयक प्रसांगिक पत्र के संबंध में कहना है कि ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेघड़ा (बेगूसराय) के अधीन शीर्ष-FDR अन्तर्गत वर्ष- 2021-22 के पथों की जाँच कर जाँच प्रतिवेदन आवश्यक कारवाई हेतु समर्पित किया जाता है ।

अनु०- पथों की सूची ।

विश्वासभाजन

कार्यपालक अभियंता

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, समस्तीपुर ।

**ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेवड़ा द्वारा कराये गये पथों की जाँच से संबंधित प्रतिवेदन**

| क्र० सं० | पथ का नाम                                                                                                      | क्षतिग्रस्त भाग (मी० में) | कराये गये कार्य                              | कराये गये कार्य की राशि (रु०) | GST @ 12% | L. Cess @ 1% | S.F. @ 10% | Total     | अभियुक्ति     |
|----------|----------------------------------------------------------------------------------------------------------------|---------------------------|----------------------------------------------|-------------------------------|-----------|--------------|------------|-----------|---------------|
| 1        | NH JHAMMATIA GHAT - GOPALPUR                                                                                   | 188.000                   | Bricks bats,sand bags,Bamboo piling          | 700937.00                     | 84112.00  | 7009.00      | 13883.00   | 805941.00 | कार्य पूर्ण । |
| 2        | NH-28 Rani to Bhajos Dih                                                                                       | 711.000                   | Bricks bats                                  | 416574.00                     | 49989.00  | 4166.00      | 24074.00   | 494803.00 | कार्य पूर्ण । |
| 3        | X Road - Chan Barkhut C. Ghat                                                                                  | 174.000                   | Bricks Bats,Sand bags                        | 414436.00                     | 49732.00  | 4144.00      | 9366.00    | 477678.00 | कार्य पूर्ण । |
| 4        | Kadrabad ( PWD Road ) To (Dharampur) Bachhwara                                                                 | 95.000                    | Bricks bats,sand bags,GSB Gr-I               | 218310.00                     | 26197.00  | 2183.00      | 4934.00    | 251624.00 | कार्य पूर्ण । |
| 5        | Railway Gurnti Bachhwara to Siswa Road                                                                         | 120.000                   | Bricks Bhat                                  | 279283.00                     | 33514.00  | 2793.00      | 16141.00   | 331731.00 | कार्य पूर्ण । |
| 6        | Chamtha REO Goptol to Chiralyatok(Rescued work)                                                                | 27.000                    | Bricks Bats, Sand bags                       | 69608.00                      | 8353.00   | 696.00       | 1573.00    | 80230.00  | कार्य पूर्ण । |
| 7        | Chan Barkhoot L06 Chhot khut to Laxman tola Bharat chowk                                                       | 16.000                    | Bricks bats                                  | 69184.00                      | 8302.00   | 692.00       | 1564.00    | 79742.00  | कार्य पूर्ण । |
| 8        | Constriction of bridge of size 4x24.75 m. on Dadopur ghat of Baya river of Bachhawara block in Begusaral Dist. | 39.000                    | Bricks Bats,Sand bags                        | 71333.00                      | 8560.00   | 713.00       | 1612.00    | 82218.00  | कार्य पूर्ण । |
| 9        | PWD RD - MOKARIR                                                                                               | 79.000                    | Bricks bats                                  | 134076.00                     | 16089.00  | 1341.00      | 3030.00    | 154536.00 | कार्य पूर्ण । |
| 10       | L039 - T01 Chabliapur to Barkurwa (VR39)                                                                       | 78.000                    | Bricks bats                                  | 663207.00                     | 79585.00  | 6632.00      | 38326.00   | 787750.00 | कार्य पूर्ण । |
| 11       | Tara Chowk to Rampur                                                                                           | 5.000                     | Sand bags,Bricks bats,HP -600mm dia          | 93011.00                      | 11161.00  | 930.00       | 2102.00    | 107204.00 | कार्य पूर्ण । |
| 12       | PWD ROAD - DAHRATHPUR                                                                                          | 132.000                   | Sand bags                                    | 115900.00                     | 13908.00  | 1159.00      | 2619.00    | 133586.00 | कार्य पूर्ण । |
| 13       | Patni Chowk Rwd Road to Makratol                                                                               | 168.000                   | E/W,Sand bags,Bricks bats,HP NP-3-1000mm dia | 788628.00                     | 94635.00  | 7886.00      | 17823.00   | 908972.00 | कार्य पूर्ण । |
| 14       | L023-NH-28 To Temahun(VR23)Chiwari                                                                             | 6.000                     | Bricks bats                                  | 90680.00                      | 10882.00  | 907.00       | 5243.00    | 107712.00 | कार्य पूर्ण । |
| 15       | S048 Mahadait Tola to Larwapur Bandh Via House of Munna Mahto (Telan)                                          | 507.000                   | Sand bags                                    | 319926.00                     | 38391.00  | 3199.00      | 7230.00    | 368746.00 | कार्य पूर्ण । |
| 16       | Bachhwara to Samasa Road                                                                                       | 341.000                   | Bricks bats                                  | 426284.00                     | 51154.00  | 4263.00      | 24636.00   | 506337.00 | कार्य पूर्ण । |
| 17       | PMGSY Road Dasrathpur house of ganga giri to MMGSY Road Satbhaiya tola                                         | 82.000                    | Sand bags                                    | 87851.00                      | 10542.00  | 879.00       | 1985.00    | 101257.00 | कार्य पूर्ण । |
| 18       | L023 - NH-28 To Temahun (VR23)                                                                                 | 61.000                    | Sand bags                                    | 158317.00                     | 18998.00  | 1583.00      | 3578.00    | 182476.00 | कार्य पूर्ण । |
| 19       | PWD Road to Rajapur Bagho                                                                                      | 21.000                    | Bricks bats                                  | 44129                         | 5295.00   | 441.00       | 997.00     | 50862.00  | कार्य पूर्ण । |

|    |                                      |         |                       |         |           |          |          |            |               |
|----|--------------------------------------|---------|-----------------------|---------|-----------|----------|----------|------------|---------------|
| 20 | L03-Teghra Atarua P Road To Mananpur | 219,000 | Bricks bats           | 235058  | 28207.00  | 2351.00  | 13177.00 | 278793.00  | कार्य पूर्ण । |
| 21 | L032-T02 to Maheshpur                | 19,000  | Bricks bats           | 116536  | 13984.00  | 1165.00  | 6534.00  | 138219.00  | कार्य पूर्ण । |
| 22 | T02 Churamanchak To Gaura Sima       | 135,000 | Bricks bats           | 173613  | 20834.00  | 1736.00  | 9733.00  | 205916.00  | कार्य पूर्ण । |
| 23 | PWD To Din Dhayal Path               | 180     | GSB, WBM Gr-iii       | 303852  | 36462.00  | 3039.00  | 18056.00 | 361409.00  | कार्य पूर्ण । |
| 24 | NH-28 To Ayodha                      | 887     | Bricks bats ,GSB      | 369511  | 44341.00  | 3695.00  | 7039.00  | 424586.00  | कार्य पूर्ण । |
| 25 | L038-Issapur To Samastipur Siwan     | 357     | Bricks bats Sand bags | 1216963 | 146036.00 | 12170.00 | 27503.00 | 1402672.00 | कार्य पूर्ण । |

8825000.00

उपरोक्त सभी पथों की जाँच की गई जो संतोषप्रद है ।

Executive Engineer

RWD (W) Division Samastipur

