

निरीक्षण प्रतिवेदन

अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ के पत्रांक 1381 दिनांक 20.11.2021 में दिये गये निर्देश के आलोक में दिनांक 20.11.2021 से दिनांक तक ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ अन्तर्गत ग्रामीण कार्य विभाग, कार्य प्रमंडल पूर्णियाँ, में कुसवा, जलालगढ़, श्रीमर के नगर एवं पूर्णियाँ पूर्व प्रखंड के वर्ष 2021 की बाढ़ से निम्नलिखित क्षतिग्रस्त पथों के Temporary Restoration कार्य के स्थल का निरीक्षण किया गया एवं इन कार्यों को प्राक्कलन के अनुरूप पाया गया। कार्य की वर्तमान स्थिति संतोषजनक है एवं पथ इस स्थलो पर मोटेरेबल है।


Block - Jalalgarh

Sl. No	Division	Road Name	Road Status	Length (In Km.)	Estimated Cost for Restoration (In Lakh)	Remarks
1	2	3	4	5	6	7
1	Purnea	JALARGARH NH 57 MOTIYARPUR - DIMIHA	Completed	7.050	1.896	RESTORATION WORK COMPLETED
2	Purnea	Dimia To Suraha Tola Dimia	Completed	3.150	5.313	RESTORATION WORK COMPLETED
3	Purnea	Jalalgarh (NH 57) - Bakania Village	Completed	17.600	3.101 6.350	RESTORATION WORK COMPLETED
4	Purnea	Katail - Bhateli (Khata Ghat)	Completed	1.920	5.965	RESTORATION WORK COMPLETED


कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा, कुसवा
जलालगढ़


सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमंडल, कुसवा
जलालगढ़


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल पूर्णियाँ


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल कटिहार



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

KATAIL TO BHATELI (KHATA GHAT)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1920	
DISTRICT	PURNEA	
BLOCK	JALALGARH	
DIVISION	PURNEA	
TOTAL LENGTH OF ROAD	1.920	KM
TOTAL COST OF F.D.R. PART - A	Rs. 5.219	Lacs
ADD G.S.T @ 12%	Rs. 0.626	Lacs
ADD Labour Cess @ 1%	Rs. 0.052	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.068	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 5.965	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Purnea

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : KATAIL TO BHATELI (KHATA GHAT)

DISTRICT PURNEA

DIVISION PURNEA

BLOCK JALALGARH

LENGTH OF ROAD (IN KM) 1.920

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	0.000
4	G.S.B.	5.219
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		5.219
Add G.S.T. @ 12%		0.626
Add Labour Cess @ 1%		0.052
Add Seigniorage Fee @ 10%		0.068
Total Cost of Restoration Work =		5.965

[Signature]
14/11/24
J.E.
RWD

[Signature]
14/11/24
A.E.
RWD

[Signature]
14/11/24
E.E.
RWD

provisional Technical Sanction for Rs 5.965 lacs (Rupees five lacs Ninety six thousand five hundred) only.

[Signature]
10.1.22

KATAIL TO BHATELI (KHATA GHAT)

Sl. No.	SDB SL.NO	MORD Ref.No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1	4.1	401	Granular Sub Base								
			Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.								
			C/O To ANNEXURE "C"						173.80		
				Cum					173.80	3002.67	521864.05
									Total Cost fo Flood Protective work (In Rs.) =		521864.05
									Total Cost fo Flood Protective work (In Lakh) =		5.219

[Signature]
A.E.

[Signature]
A.E.

[Signature]
14/11/21
JE.



KATAIL TO BHATELI (KHATA GHAT)

ANNEXURE "C"

Sl. Chaining No. At (Mtr.)	NO. Length (in mt.)	Top Width (in mt.)	Top Width + Bottom Width) /2	Height (in mt.)	Qty. (in Cum)	Remarks
1	15.00	(4.90+5.10)/2	(4.90+5.10)/2	(0.20+0.250)/2	16.88	
1	10.00	(4.80+5.10)/2	(4.80+5.10)/2	(0.20+0.20)/2	9.90	
1	14.00	(5.0+5.25)/2	(5.0+5.25)/2	(0.20+0.25)/2	16.14	
1	16.00	(4.75+5.25)/2	(4.75+5.25)/2	(0.20+0.20)/2	16.00	
1	18.00	(4.50+4.85)/2	(4.50+4.85)/2	(0.150+0.250)/2	16.83	
1	12.00	(4.65+4.85)/2	(4.65+4.85)/2	(0.150+0.250)/2	11.40	
1	10.00	(5.25+5.05)/2	(5.25+5.05)/2	(0.150+0.20)/2	9.01	
1	19.00	(4.80+5.05)/2	(4.80+5.05)/2	(0.15+0.25)/2	18.72	
1	11.00	(4.80+5.05)/2	(4.80+5.05)/2	(0.15+0.20)/2	9.48	
1	16.00	(5.60+5.30)/2	(5.60+5.30)/2	(0.15+0.25)/2	17.44	
1	14.00	(5.0+5.20)/2	(5.0+5.20)/2	(0.15+0.20)/2	12.50	
2	15.00	(2.50+4.0)/2	(2.50+4.0)/2	(0.25+0.150)/2	19.50	
Total=					173.80	
J.E.						
A.E.						
E.E.						

