



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

BAIMAN CHOWK TO JOKA

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 0		
DISTRICT	PURNEA		
BLOCK	K NAGAR		
DIVISION	PURNEA		
TOTAL LENGTH OF ROAD		0.000	KM
TOTAL COST OF F.D.R. PART - A		Rs. 3.956	Lacs
ADD G.S.T @ 12%		Rs. 0.475	Lacs
ADD Labour Cess @ 1%		Rs. 0.040	Lacs
ADD Seigniorage Fee @ 10%		Rs. 0.210	Lacs
TOTAL COST OF RESTORATION WORK In Rs.		Rs. 4.681	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Purnea

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : BAIMAN CHOWK TO JOKA

DISTRICT PURNEA

DIVISION PURNEA

BLOCK K NAGAR

LENGTH OF ROAD (IN KM) 0.000

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	1.133
2	HUME PIPE	0.486
3	BRIKCK BAT	0.362
4	SAND BAGS	1.627
5	BAMBOO WORK	0.348
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		3.956
Add G.S.T. @ 12%		0.475
Add Labour Cess @ 1%		0.040
Add Seigniorage Fee @ 10%		0.210
Total Cost of Restoration Work =		4.681

[Signature]
14/11/21
J.E.
RWD

[Signature]
14/11/21
A.E.
RWD

[Signature]
14/11/21
E.E.
RWD

*Provisional Technical Sanction for Rs. 4.681 lacs C. hyperus
four lacs sixty eight thousand one hundred only!*

hmt
10.1.22

BAIMAN CHOWK TO JOKA

Sl. No.	SDB SL.NO	MORD Ref.No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1	3.3	301.5	EARTH WORK								
			Construction of Embankment with approved material obtained from borrow pits with a lift upto 1.5 m transporting to site, spreading grading to required slope and compacting to meet requirement of Table 300.1 and 300.2 with a lead of 1000 m as per Technical								
			C/O To ANNEXURE "B"						310.62		
				Cum					310.62	364.81	113317.28
2	9.3	(c)	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design.								
			Providing and laying reinforced cement concrete pipe NP3 For Restoration (1000 mm dia Single Row)								
					6	2.50			15.000		
				RM					15.000	3241.530	48622.95
3	4.5		Brick Bats								
			Providing Brick Bats including, Spreading, Laying Compacting with C.I. Hammer all complete job as per Specification and Direction E/I.								
			C/O To ANNEXURE "A"						18.660		
				Cum					18.660	1941.880	36235.48
4	10.7.40	WRD	Labour for Sand filling in Cement Bag, swing and laying materials.						5950.00		
				Bag					5950.000	27.350	162732.50
5	14.17		Labour for driving 62 MM to 75 MM dia Bamboo Piles Including cutting to in proper size and shoes etc complete job. (Bamboo Piles c/c 0.3 m)								
				m		48.00			48.00		
			Total Length						48.00		
			(Length / 0.3) x 3 +1						481	51.090	24574.29
6	14.18		Supplying fitting and fixing in position split bamboo woven chanchary with 20 SWG G.I etc. Complete job								
				Sqm	36.58	1.20			43.9	233.130	10234.41
										Total Cost fo Flood Protective work (In Rs.) =	395716.91
										Total Cost fo Flood Protective work (In Lakh) =	3.957


12/11/02


12/11/21


~~22/11/2020~~

ANNEXURE "A"

Sl. No.	Chainage At (Mtr.)	NO.	Length (in mt.)	Top Width (in mt.)	Top Width + Bottom Width) / 2	Height (in mt.)	Qty. (in Cum)	Remarks
		1	4.30	1.80	1.80	0.30	2.32	
		1	30.00	(1.60+1.40+1.45)/3	(1.60+1.40+1.45)/3	0.30	13.35	
		1	6.58	(1.50+1.60+1.45)/3	(1.50+1.60+1.45)/3	0.30	2.99	
						Total=	18.66	


 14/11/21
 J.E.


 14/11/21
 A.E.


 14/11/21
 E.E.

ANNEXURE "B"

J.E

A.É.

E.E.

निरीक्षण प्रतिवेदन

अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ के पत्रांक 1361 दिनांक 20.11.2021 में दिये गये निर्देश के आलोक में दिनांक 01.12.2021 से दिनांक तक ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ अन्तर्गत ग्रामीण कार्य विभाग, कार्य प्रमंडल पूर्णियाँ, में ~~कसबा, जलालगढ़, श्रीनगर~~ के नगर एवं पूर्णियाँ पूर्व प्रखंड के वर्ष 2021 की बाढ़ से निम्नलिखित क्षतिग्रस्त पथों के Temporary Restoration कार्य के स्थल का निरीक्षण किया गया एवं इन कार्यों को प्राक्कलन के अनुरूप पाया गया। कार्य की वर्तमान स्थिति संतोषजनक है एवं पथ इस स्थलो पर मोटेरेबल है।

Block - Krityanand Nagar

Sl. No	Division	Road Name	Road Status	Length (In Km.)	Estimated Cost for Restoration (In Lakh)	Remarks
1	2	3	4	5	6	7
1	Purnea	L029-T-01 to Gangeli (VR29)	Completed	1.605	2.918 3.060	RESTORATION WORK COMPLETED
2	Purnea	Kajha Hatia To Tharaha Musherri	Completed	3.985	16.767	RESTORATION WORK COMPLETED
3	Purnea	Baiman Chowk to Joka	On Going	1.510	4.681	RESTORATION WORK COMPLETED

कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा, ~~कसबा~~

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमंडल, ~~कसबा~~

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल पूर्णियाँ

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल कटिहार