

**अधीक्षण अभियंता का कार्यालय,
ग्रामीण कार्य विभाग, कार्य अंचल, मधेपुरा।**
पत्रांक 622 41/ मधेपुरा, दिनांक 21.05.22/

प्रेषक,

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, मधेपुरा।

सेवा में,

मुख्य अभियंता-2,
ग्रामीण कार्य विभाग,
पटना।

विषय : ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधेपुरा के अधीन वर्ष 2021-22 में भारी वर्षा के कारण आयी बाढ़ से क्षतिग्रस्त सड़कों तथा पुलियों का प्रशासनिक स्वीकृति हेतु डी0पी0आर0 समर्पित करने के संबंध में।

प्रसंग : कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधेपुरा का पत्रांक 1675 33/ दिनांक 11.05.22 एवं अभियंता प्रमुख, ग्रामीण कार्य विभाग, विहार, पटना का पत्रांक- मु0अ0-4(मु0)विविध(कार्य)23-291/2019-4849 पटना, दिनांक 07.12.2021

महाशय,

उपर्युक्त विषयक प्रसांगिक पत्र के आलोक में कहना है कि ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधेपुरा के अधीन वर्ष 2021-22 में भारी वर्षा के कारण आयी बाढ़ से क्षतिग्रस्त सड़कों तथा पुलियों का कराये गये कार्य का प्रशासनिक अनुमोदन हेतु माननीय विधायक निरंजन कुमार मेहता, विधान सभा क्षेत्र, विहारीगंज के पत्रांक 75, 78 दिनांक 26.09.2021 एवं जिला पदाधिकारी, मधेपुरा का ज्ञापांक 2908 दिनांक 09.10.2021 के आलोक में प्रशासनिक अनुमोदन हेतु 13 योजनाओं का डी0पी0आर0 तकनीकी स्वीकृति के उपरान्त इस पत्र के साथ संलग्न कर समर्पित की जाती हैं, जो निम्न प्रकार हैं।

क्र0	प्रखंड	प्रखंड	योजना का नाम	क्षतिग्रस्त भाग की लम्बाई (KM)	तकनीकी स्वीकृति की राशि (Lakh)
1.	Murliganj	FDR	Parmanandpur Panchayat Ke Ward No-10 Me PMGSy Road Se Brahmsthan Rahta tola tak.	0.880	22.21221
2.	Murliganj	FDR	Khari Dakshinabri tola MMGSY Road Se Kabir Asram Parmanandpur tak.	0.380	8.99097
3.	Murliganj	FDR	Ratanpatti More Se Manhara PMGSY Nahar.	0.541	11.10203
4.	Murliganj	FDR	Raghunathpur Ward No-06 Me Kameshear Yadav Ke Ghar Se Kailash Yadav Ke Ghar tak.	0.596	17.27885
5.	Murliganj	FDR	Ratanpatti Ward No-02 Mahadalit tola Se S.H.-91 tak.	0.250	14.32069
6.	Murliganj	FDR	Pokhram Me Dularchand Vishwas Ke Ghar Se Bajrangwali Asthan tak.	0.798	20.64189

P.T.O.

क्र०	प्रखंड	प्रखंड	योजना का नाम	क्षतिग्रस्त भाग की लम्बाई (KM)	तकनीकी स्वीकृति की राशि (Lakh)
7.	Murliganj	FDR	Ganganpur Panchyat me PMGSY Sadak Se Kali tola tak.	0.397	12.28615
8.	Murliganj	FDR	Parmanandpur Panchayat Ke Ward No-10 Me PMGSY Road Se Ganesh Gupta Ghar tak.	0.053	1.48789
9.	Murliganj	FDR	Dinapatti Panchayat Ke Ward NO-05 Me Sanjay Yadav Ke Ghar Se Boku Yadav Ke Ghar tak.	0.104	2.92421
10.	Murliganj	FDR	Ganganpur Panchayat. Ke Ward No-11 Ke Upendra Yadav Ke Ghar Se Mahadalit tola tak.	0.244	5.18674
11.	Murliganj	FDR	Raghunathpur Ward No-08 Me Bhumi Das Ke Ghar Se Murho tola tak.	0.910	29.26569
12.	Murliganj	FDR	Raghunathpur Ward No-07 Me PMGSY Road Se Durga Asthan tak.	0.216	15.45514
13.	Murliganj	FDR	Belo Chandadh Se Chatra Kantahi.	0.910	27.52292

अनु०:- प्राक्कलन एक-एक प्रति में।

विश्वासभाजन,

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग, कार्य अंचल,
मधेपुरा।



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Development Agency (BRRDA)

Head :- F.D.R.

YEAR (2021-22)

STATE
DISTRICT
BLOCK
DIVISION

BIHAR
MADHEPURA
MURLIGANJ
MADHEPURA

**DETAILED ESTIMAE FOR TEMPRORY RESTORATION OF
ROAD FROM RATANPATTI WARD NO-02 MAHADALIT
TOLA SE LEKAR SH-91 TAK**

Actual Length of Road	=	1.000 Km
Flood affected Length of Road	=	0.250 Km
TOTAL COST OF PAVEMENT	Rs	14,32,069.18
TOTAL PROJECT COST	Rs	14,32,069.18

Submitted By:
Executive Engineer
RWD (W) Division, Madhepura

Prepared By:
Executive Engineer
RWD (W) Division, Madhepura

Inspection Report for Flood Damage work

Date:-

Name of PIUS :-

Madhepura

Name of Block :-

Murhganj

Name of Road :-

Rasthampatti ward No-2 Madha Maha dalit dalase Jolear
S.H. 91 & k

For Road

1. Damage Location/Chainage :- 0+30m, 30+60m, 60+90m, 90+120m, 120+162m, 162+492m, 492+1000m

2. Damage Length :-

— 0.25 km

3. Nature of damage :-

4. Details of Restoration Works :-

i. Material being used in Restoration works:-

— Bricks bats, H.P

ii. Equipments/Tools being used in Restoration works :-

iii. Procedure taken up in Restoration works :-

iv. Restored Length :-

3. For Bridge

1. Damage Location/Chainage :-

2. Damage Length :-

3. Nature of damage :-

4. Details of Restoration Works :-

i. Material being used in Restoration works:-

ii. Equipments/Tools being used in Restoration works :-

iii. Procedure taken up in Restoration works :-

iv. Restored Length :-

A. Jeyan
JE

Prakash
AE

EE

अभि संतोषजनक पापा गया।

मम 11/11/21

Signature

(Name of inspector)

EE

Privanigay

—तकनीकी प्रतिवेदन—

अंचल का नाम:— मधेपुरा

प्रमण्डल का नाम:— मधेपुरा।

योजना शीर्ष:— 3054 एफ.डी.आर.

पथ का नाम:— Ratanpatti ward no 2 me mahadalit tola se SH 91 tak


पथ की लम्बाई:—1.000 कि.मी.

निर्मित/निर्माणाधीन पथ का शीर्ष:—.....

प्राक्कलित राशि:— रू० 14.320 लाख

प्रस्तुत प्राक्कलन वर्ष 2021 में आई अप्रत्याशित अतिवृष्टि एवं बाढ़ के कारण Ratanpatti ward no 2 me mahadalit tola se SH 91 tak पथ में हुए क्षति यथा कटाव/धसान/जलजमाव की आकस्मिक मरम्मत एवं यातायात पुनर्बहाल करने हेतु शीर्ष 3054 एफ.डी.आर. मद से सचिव, ग्रामीण कार्य विभाग/उच्चाधिकारियों के द्वारा दिये गये निर्देश के अनुपालन में तैयार किया गया है।

प्राक्कलन अन्तर्गत पथ में हुए क्षति की विस्तृत मापी दर्शायी गई है एवं प्राक्कलन वर्तमान अनुसूचित दर पर तैयार किया गया है। माननीय विधायक निरंजन कुमार मेहता का प्रांक-25 दि० 26/09/2021 एवं जिला पदाधिकारी का प्रांक 2908 दि० 9/10/21 के अनुशंसा के आलोक में


01/11/21

कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रषाखा, मुरलीगंज


01/11/21

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमण्डल, मुरलीगंज


01/11/21

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमण्डल, मधेपुरा।

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :- DETAILED ESTIMAE FOR TEMPRORY RESTORATION OF
ROAD FROM RATANPATTI WARD NO-02 MAHADALIT TOLA
SE LEKAR SH-91 TAK

DIVISION :- MADHEPURA

BLOCK :- MURLIGANJ

Actual Length of Road :- 1.000 Km

Flood Affected Length of Road :- 0.250 Km

Sr. No.	Description	Amount (In Rs.)
1	Total Cost of Restoration=	12,13,524.90
2	Add:-Labour Cess @1% amt. =	12,135.25
3	Add:GST@12% on amt. =	1,45,622.99
4	Add:S.F.@ 10% on Material =	60,786.04
TOTAL RESTORATION COST OF THE PROJECT IN LACS		14,32,069.18

Say, 14,32,069/-



Junior Engineer
RWD (W) Division, Madhepura



Assistant Engineer
RWD (W) Division, Madhepura



Executive Engineer
RWD (W) Division, Madhepura

TS no:-26 dated 20/05/2022
पत्रांक- मुं अ-4 (मुं) विविध (कार्य) 23-29/2019.4849
दि 02/12/2024

Technically sanctioned for ₹14,32,069.00/-
Two thousand sixty nine Rupees only.)

प्रेषण

से

Wider
20/05/2022

11/21/05/22

Estimating Officer
Rural Work Department
Work Circle, Madhepura

Superintending Engineer
Rural Works Department
Works Circle, Madhepura

Details of Measurement

कार्य का ब्योरा Deatail of Workl		संख्या No.	Measurement			मात्रा Quantity
			लम्बाई in m.	चाड़ाई In m.	In m.	
DETAILED ESTIMAE FOR TEMPORARY RESTORATION OF ROAD FROM RATANPATTI WARD NO-02 MAHADALIT TOLA SE LEKAR SH-91 TAK						
Item No. 1		Sand filling in Foundation Trenches as per Drawing & Technical Specification				
CH:-in		1	0	2.7	0.075	0.000
CH:-in		1	0	2.7	0.075	0.000
				Total (in Cum)		0.000
Item No. 2		Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.				
CH:-in 0 to 30		1	20.00	3.30	0.250	16.500
CH:-in 30 to 60		1	10.00	3.30	0.450	14.850
CH:-in 60 to 90		1	30.00	3.40	0.300	30.600
CH:-in 90 to 120		1	30.00	3.40	0.250	25.500
CH:-in 120 to 162		1	30.00	3.40	0.200	20.400
		1	30.00	3.96	2.450	291.060
CH:- 162 to 492		1	12.00	3.96	2.600	123.552
CH:-in 492 to 1000		1	30.00	3.40	0.225	22.950
		1	30.00	3.40	0.250	25.500
		1	22.00	3.20	0.300	21.120
		1	6.00	3.20	0.150	2.880
						594.912
Less For Pipe		2	4.00	0.785x(1.23)2x0.622		5.900
				Total (In Cum)		589.012
Item No. 3		Labour for cutting 62mm to 75 mm dia bamboo piles to size and making shoes and driving etc. complete job as per specification and direction of E/I				
CH:-in		1	0.00		2.13	0.000
		1	0.00		2.13	0.000
				Total (In m)		0.000
Item No. 4		Labour for fitting and fixing Split bamboo woven chachari in position with 20 swg G.I wire or 75 mm to 100 mm long nails alternatively including cost of G.I. wire or nails complete job as per specification and direction of E/I				
		Size 6m*2m,	1	0	2	0.00
For Chachary 01 no.(6m) Bamboo=1.413 sqm			1	0	2	0.00
				Total (in sqm)		0.00
				Total (in m)		0.00
Item No. 5		Labour for fitting and fixing 75 mm dia bamboo runners in position at every vertical pole with 150 mm long nails or 38 swg G.I. wire including cost of G.I wire or nails complete job as per specification and direction of E/I				
CH:-in		3	0.00			0.00
CH:-in		3	0			0.00
				Total (in m)		0.00
Item No. 6		Supply of Bamboo at site.				
				Total (In m)		0.00
				Total (In nos.)		0.00
						0.00

No. 7	Labour filling empty cement bags with local sand, stitching the bags and placing including supply of bull and EC bag etc. all complete as per approved design, specification and direction of E/I	
In	1 0.00 2.5 1.250	0.00
	Total (In cum)	0.00
(0.034m ³ =1 no. of EC Bags)		0.00
	Total (In nos.)	0.00
n No. 8	Providing, laying and filling Geo bags of size 1m x 0.7 m (Type A 300 GSM nonwoven) weight of bags 420g volume of filled bag 0.07m ³ . weight of filled Geo bags 128 Kg with local sand including stitching in four lines by approved nylon thread with stitching machine and generator stacking and placing after loading unloading and carriage with help of trolley within 150m lead all complete as per specifications and direction of E/I (Including Carriage of Local sand lead 0.5 km)	
	1 0 0 0	0.00
	(0.07m ³ =1 no. of Geo Bags)	0.00
	Total (In nos.)	0.00
Item No. 9	Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix-in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. (Gr-II Material)	
	1 0 3.75 0.200	0.00
	Total (Cum)	0.00
Item No. 1	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row (1000mm Dia).	
Ch:-	1 8 2.5	20.00
	Total (In m)	20.00

A. I. Arman
01/11/24

OK

Bringsh
01/11/24
A-E

Schedule of Quantity

DETAILED ESTIMAE FOR TEMPRORY RESTORATION OF ROAD
IE OF ROAD :- FROM RATANPATTI WARD NO-02 MAHADALIT TOLA BE LEKAR BLOCK :- MURLIGANJ
SH-91 TAK

	SOR NO	DESCRIPTION OF ITEMS	QTY	UNIT	RATE	AMOUNT
1	301.5	Sand filling in Foundation Trenches as per Drawing & Technical Specification	0.00	Cum	582.71	0.00
2	A/R	Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to achelve required density with all complete as per the direction of engineer in charge.	589.01	Cum	1922.87	1132593.50
3	5.7.7	Labour for cutting 62mm to 75 mm dia bamboo piles to size and making shoes and driving etc. complete job as per specification and direction of E/I	0.00	m	45.88	0.00
4	5.7.8	Labour for fitting and fixing Split bamboo woven chachari in position with 20 swg G.I wire or 75 mm to 100 mm long nails alternatively including cost of G.I. wire or nails complete job as per specification and direction of E/I	0.00	sqm	78.20	0.00
5	5.7.9	Labour for fitting and fixing 75 mm dia bamboo runners in position at every vertical pole with 150 mm long nails or 38 swg G.I. wire including cost of G.I wire or nails complete job as per specification and direction of E/I	0.00	m	5.31	0.00
6		Supply of Bamboo at site.	0.00	nos.	188.39	0.00
7	5.7.40.1	Labour filling empty cement bags with loocal sand, stitching the bags and placing including supply of sutli and EC bag etc. all complete as per approved desing, specification and direction of E/I	0.00	nos.	37.05	0.00
8		Providing, laying and filling Geo bags of size 1m X 0.7 m (Type A 300 GSM nonwoven) weight of bags 420g volume of filled bag 0.07m ³ . weight of filled Geo bags 126 Kg with local sand including stitching in four lines by approved nylon thread with stitching machine and generator stacking and placing after loading unloading and carriage with help of trolley within 150m lead all complete as per specifications and direction of E/I (Including Carriage of Local sand lead 0.5 km)	0.00	Each	172.18	0.00
9	401	Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achleve the desired density, complete as per Technical Specification Clause 401.	0.00	Cum	2091.76	0.00
10	9.3	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Roww(1000mm Dia).	20.00	m	4046.57	80931.40
		Total			Rs.	1213524.90

A. Kumar
JE

Prakash
AE

1/1/21
EE

Calculation of Seigniorage Fees

OF ROAD :- DETAILED ESTIMAE FOR TEMPORARY RESTORATION OF ROAD FROM RATANPATTI WARD NO-
02 MAHADALIT TOLA SE LEKAR SH-91 TAK
BLOCK :- MURLIGANJ

SOR NO	DESCRIPTION OF ITEMS	QTY	UNIT	RATE	AMOUNT
123	Sand filling in Foundation Trenches as per Drawing & Technical Specification				
	E/W	0.00	Cum	141.85	0.00
A/R	Providing & laying Brick Bat....				
	Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.				
	Brick Bats	589.01	Cum	1032.00	607860.38
17	5.7.40.1				
	Labour filling empty cement bags with loocal sand, stitching the bags and placing including supply of sutli and EC bag etc. all complete as per approved desing, specification and direction of E/I				
	Sand	0.00	Cum	141.85	0.00
48	5.7.40.2				
	Providing, laying and filling Geo bags of size 1m X 0.7 m (Type A 300 GSM nonwoven) weight of bags 420g volume of filled bag 0.07m ³ . weight of filled Geo bags 125 Kg with local sand including stitching in four lines by approved nylon thread with stitching machine and generator stacking and placing after loading unloading and carriage with help of trolley within 150m lead all complete as per specifications and direction of E/I (including Carriage of Local sand lead 0.5 km)				
	Sand	0.00	Cum	141.85	0.00
59	401				
	Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.				
	For Grading I Material (with Coarse Sand Screening)				
	Unit = Cum				
	Taking output = 300 cum				
	Coarse graded granular sub-base material as per Table 400.2				
	53 mm to 9.5mm @ 50 percent	180.00	Cum	516.42	92955.60
	9.5 mm to 2.36 mm @ 20 percent	72.00	Cum	411.33	29615.76
	2.36 mm below @ 30 percent (coarse Sand Screening)	108.00	Cum	185.94	20081.52
	Cost for 300 cum = a				142652.88
	Rate psr Cum = (a)/300		Cum		475.51
		0.00	Cum	475.51	0.00
	GSB Gr-I				0.00
				TOTAL	607860.38
	Seigniorage Fees @10% of Basic Amount			Say	60786.04

A. K. Nayak
01/11/14
JE

B. K. Nayak
01/11/14
AE

EE
1/11/14