

Tender Inviting Authority: Engg-in Chief RWD Patna

Name of Work: Construction of Road & CD Works for ~~Amritsar~~ ~~Amritsar~~ Block Under M/R (3054)

KR HIGH School to SOFPA

VALIDATE

PRINT

HELP

Contract No: Civil Works/

Bidder
Name:

Excess (+)

%

SCHEDULE OF WORKS

| Sl. No. | Description of work | No. or Qty. | Unit | Estimated Rate | | AMOUNT Rs. P. |
|---------|---|-------------|-------|----------------|---|------------------|
| | | | | Figure | Words | |
| 1 | Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I | 0.300 | Hect. | 51133.76 | Rupees Fifty One Thousand One Hundred & Thirty Three and Paise Seventy Six Only | 15340.13 |
| 2 | Construction of Subgrade & Earthen Shoulder Construction of subgrade & earthen shoulders with approved material obtained from borrow pits with all lifts and lead, transporting to site, spreading, grading to required slope and compacted to meet requirement of Tables 300.2 with lead upto 1000m as per Technical Specification Clause 301.4.1 | 1396.250 | Cum | 176.86 | Rupees One Hundred & Seventy Six and Paise Eighty Six Only | 246940.78 |
| 3 | Filling in foundation trenches as per drawing and technical Specification clause 305.3.9 | 281.250 | Cum | 478.09 | Rupees Four Hundred & Seventy Eight and Paise Nine Only | 134462.81 |
| 4 | Granular Sub-base with Well Graded Material (Table 400.1) Gr-II Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with three wheel 80-100 kN static roller capacity to achieve the desired density, complete as per Technical Specification Clause 401 | 125.661 | Cum | 2173.23 | Rupees Two Thousand One Hundred & Seventy Three and Paise Twenty Three Only | 273090.26 |
| 5 | WBM Grading 2 Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405. | 33.137 | Cum | 3994.19 | Rupees Three Thousand Nine Hundred & Ninety Four and Paise Nineteen Only | 132355.47 |
| 6 | WBM Grading 3 Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405. | 124.460 | Cum | 3604.29 | Rupees Three Thousand Six Hundred & Four and Paise Twenty Nine Only | 448589.93 |
| 7 | Prime Coat (Low porosity) Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. | 722.020 | Sqm | 44.71 | Rupees Forty Four and Paise Seventy One Only | 32281.51 |

A.

Signature of Tenderer with seal

Inviting Authority: Engg-in Chief RWD Patna

Work: Construction of Road & CD Works for Amathia to Sangrampur in Yogapatti Block Unde M/R (3054)

VALIDATE

Contract No: Civil Works/

PRINT

HELP

Bidder Name:

Excess (+)

%

SCHEDULE OF WORKS

| Sl. No. | Description of work | No. or Qty. | Unit | Estimated Rate | | AMOUNT Rs. P |
|---------|---|-------------|------|----------------|---|-----------------|
| | | | | Figure | Words | |
| 8 | Patch work over WBM using Mix seal surface for bituminous and Existing CC Pavement Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509. | 811.840 | Sqm | 217.41 | Rupees Two Hundred & Seventeen and Paise Forty One Only | 176502.13 |
| 9 | Tack coat Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydriloc broom as per technical specification clause 503. | 5499.335 | Sqm | 15.21 | Rupees Fifteen and Paise Twenty One Only | 83644.89 |
| 10 | Semi-Dense Bituminous Concrete :- Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects. | 117.190 | Cum | 11087.29 | Rupees Eleven Thousand & Eighty Seven and Paise Twenty Nine Only | 1299319.52 |
| 11 | Cement Concrete Pavement :- Construction of unreinforced, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M 30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork, spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specification Clause 1501 | 150.000 | Cum | 7357.55 | Rupees Seven Thousand Three Hundred & Fifty Seven and Paise Fifty Five Only | 1103632.50 |
| 12 | Kilometre Stone Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703 Ordinary Kilometer Stone (Precast) | 2.00 | Each | 2364.20 | Rupees Two Thousand Three Hundred & Sixty Four and Paise Twenty Only | 4728.40 |

A.

Signature of Tenderer with seal

Inviting Authority: Engg-in Chief RWD Patna

Work: Construction of Road & CD Works for Amathia to Sangrampur in Yogapatti Block Under M/R (3054)

VALIDATE

PRINT

HELP

Contract No: Civil Works/

| Sl. No. | Description of work | No. or Qty. | Unit | Estimated Rate | | AMOUNT Rs. p |
|---------|--|-------------|------|----------------|---|--------------|
| | | | | Figure | Words | |
| 13 | Kilometre Stone Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703 200 m stone (precast) | 6.00 | Each | 633.30 | Rupees Six Hundred & Thirty Three and Paise Thirty Only | 3799.80 |
| 14 | Direction and Place Identification signs with size more than 0.9 sqm size board Retro-reflectorised Traffic Signs Providing and erecting direction and place identification retro-reflectorised sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701. | 1.920 | Sqm | 12367.20 | Rupees Twelve Thousand Three Hundred & Sixty Seven and Paise Twenty Only | 23745.02 |
| 15 | Retro-reflectorised Traffic Signs :- Providing and fixing of retro-reflectorised cautionary, mandatory and informative sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 600 mm equilateral & triangle | 31.000 | Nos | 3664.30 | Rupees Three Thousand Six Hundred & Sixty Four and Paise Thirty Only | 113593.30 |
| 16 | Retro-reflectorised Traffic Signs :- Providing and fixing of retro-reflectorised cautionary, mandatory and informative sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 600 mm circular | 5.000 | Nos | 3793.89 | Rupees Three Thousand Seven Hundred & Ninety Three and Paise Eighty Nine Only | 18969.45 |
| 17 | Retro-reflectorised Traffic Signs :- Providing and fixing of retro-reflectorised cautionary, mandatory and informative sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 600 mm x 450 mm rectangular | 12.000 | Nos | 3664.77 | Rupees Three Thousand Six Hundred & Sixty Four and Paise Seventy Seven Only | 43977.24 |
| 18 | Providing and laying Rumble Strip with road studs and Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface Thermoplastic paint | 7.500 | Sqm | 735.44 | Rupees Seven Hundred & Thirty Five and Paise Forty Four Only | 5515.80 |

Signature of Tenderer with seal

(A)

Inviting Authority: Engg-in Chief RWD Patna

Work: Construction of Road & CD Works for Amathia to Sangrampur in Yogapatti Block Unde M/R (3054)

☒ VALIDATE

☐ PRINT

☐ HELP

Contract No: Civil Works/

Bidder Name:

Excess (+)

%

SCHEDULE OF WORKS

| Sl. No. | Description of work | No. or Qty. | Unit | Estimated Rate | | AMOUNT Rs. P |
|---------|---|-------------|--------------------------|----------------|--|-----------------|
| | | | | Figure | Words | |
| 19 | Providing and laying Rumble Strip with road studs and Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface Road strips | 24.000 | Nos | 218.85 | Rupees Two Hundred & Eighteen and Paise Eighty Five Only | 5252.40 |
| 20 | Boundary Pillar/Guard Post Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704 | 40 | Nos | 533.87 | Rupees Five Hundred & Thirty Three and Paise Eighty Seven Only | 21354.80 |
| 21 | Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701 | 88 | per cm height per letter | 0.52 | Rupees and Paise Fifty Two Only | 45.76 |
| 22 | Planting of Trees and their Maintenance for one Year Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year | 43 | Each | 818.84 | Rupees Eight Hundred & Eighteen and Paise Eighty Four Only | 35210.12 |
| 23 | Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes. | 258.00 | Sqm | 735.44 | Rupees Seven Hundred & Thirty Five and Paise Forty Four Only | 189743.52 |
| | Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes. At Edge for Old CC Portion | 50.00 | Sqm | 821.30 | Rupees Eight Hundred & Twenty One and Paise Thirty Only | 41065.00 |

Ax

Inviting Authority: Engg-in Chief RWD Patna

☒ VALIDATE

of Work: Construction of Road & CD Works for Amathia to Sangrampur in Yogapatti Block Unde M/R (3054)

☐ PRINT

Contract No: Civil Works/

☐ HELP

Bidder
Name:

Excess (+)

%

SCHEDULE OF WORKS

| Sl. No. | Description of work | No. or Qty. | Unit | Estimated Rate | | AMOUNT Rs. P |
|--|--|-------------|------|----------------|---|-------------------|
| | | | | Figure | Words | |
| 24 | Providing and fixing of typical informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1 | 2.00 | Sqm | 9725.18 | Rupees Nine Thousand Seven Hundred & Twenty Five and Paise Eighteen Only | 19450.36 |
| 25 | Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4 | 2.880 | m | 5958.21 | Rupees Five Thousand Nine Hundred & Fifty Eight and Paise Twenty One Only | 17159.64 |
| 26 | Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications | 20.160 | Sqm | 193.76 | Rupees One Hundred & Ninety Three and Paise Seventy Six Only | 3906.20 |
| 27 | Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701 | 58.560 | Sqm | 97.19 | Rupees Ninety Seven and Paise Nineteen Only | 5691.45 |
| Cost of Construction :- | | | | | | 4499368.19 |
| Add 1% Labour Cess | | | | | | 44993.68 |
| Add 12% GST | | | | | | 539924.18 |
| Add 10% SEIGNIORAGE FEE (Attached Mining Materials Sheet) | | | | | | 0.00 |
| Total Cost of Construction :- | | | | | | 5084286.06 |

A.

Signature of Tenderer with seal

Contract No: Civil Works/

Bidder
Name:

Excess (+)

%

SCHEDULE OF WORKS

| Sl. No. | Description of work | No. or Qty. | Unit | Estimated Rate | | AMOUNT Rs. p |
|---|---------------------------|--|-------|----------------|--|-----------------|
| | | | | Figure | Words | |
| 28 | Maintainance for 1st year | 1.500 | Km | 71532.00 | Rupees Seventy One Thousand Five Hundred & Thirty Two Only | 107298.00 |
| 29 | Maintainance for 2nd year | 1.500 | Km | 93344.67 | Rupees Ninety Three Thousand Three Hundred & Forty Four and Paise Sixty Seven Only | 140017.00 |
| 30 | Maintainance for 3rd year | 1.500 | Km | 260773.33 | Rupees Two Lakh Sixty Thousand Seven Hundred & Seventy Three and Paise Thirty Three Only | 391160.00 |
| 31 | Maintainance for 4th year | 1.500 | Km | 119236.00 | Rupees One Lakh Nineteen Thousand Two Hundred & Thirty Six Only | 178854.00 |
| 32 | Maintainance for 5th year | 1.500 | Km | 277636.67 | Rupees Two Lakh Seventy Seven Thousand Six Hundred & Thirty Six and Paise Sixty Seven Only | 416455.00 |
| Cost of Maintenance :- | | | | | | 1233784.00 |
| Add 1% Labour Cess | | | | | | 12337.84 |
| Add 12% GST | | | | | | 148054.08 |
| Add 10% SEIGNIORAGE FEE (Attached Mining Materials Sheet) | | | | | | 0.00 |
| Total Cost of Maintenance :- | | | | | | 1394175.92 |
| | Maintainance for 5th year | 20.000 | Qtrly | 69708.80 | Rupees Sixty Nine Thousand Seven Hundred & Eight and Paise Eighty Only | 1394175.92 |
| Total Cost of Project Including Five Year Maintenance :- | | | | | | 6478461.98 |
| Quoted Rate in Words | | Rupees Sixty Four Lakh Seventy Eight Thousand Four Hundred & Sixty One and Paise Ninety Eight Only | | | | |

A.

24/3/22
कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, बेतिया

Signature of Tenderer with seal

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000



बिहार BIHAR

Supplementary Agreement:-

This agreement, made the 20 MB/3054 MR-N/2022 day of April 2022, between श्रीवास्तव Executive Engineer, R.W.D. Works Division, Bettiah ("The I/E") of the one part, Nav Bharati Builders India Pvt. Ltd., At- Khap tola, Nautan, West Champaran ("The Contractor") of the other part.

Whereas the E/I is desirous that the Contractor execute Output and Performance based Rural Road **Supplementary Work Contract** for the Maintenance of Roads **MR-/N/19-20 Bettiah/31 (Tender ID- 88243) Under MR-N** (Hereinafter called "The Works") and E/I has accepted the Bid by the Contractor for the execution of such works and the remedying of any defects therein, at a contract price of **Rs. 64,71,983.00 (Rs. Sixty Four Lac Seventy One Thousand Nine Hundred Eighty Three One).**

| S.N. | Package Number | Road Name | Length (Km) |
|------|--------------------------|------------------------------|-------------|
| 1 | MR-N/19-20 BETTIAH-31 | KR High School to Sofwa tola | 1.500 |

NOW THIS AGREEMENT WITNESSETH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the conditions of contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the E/I to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the E/I to execute and Complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the contract.
3. The E/I hereby covenants to pay the Contractor in consideration of the Execution and completion of the Works and the remedying the defects wherein Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.

श्रीवास्तव

EXECUTIVE ENGINEER

R.W.D. Works Div. Bettiah

12/04/22

12.04.22

Rate _____
Agreement Amount _____
Agreement Number _____
Date of Work Order _____
Time of completion _____
Maintenance _____
PSD/APC _____
Security Deduct From bills _____

Alch.
12/04/22
EXECUTIVE ENGINEER
R.W.D. Works Div. Bettiah

RS
12/04/22
Def
12.04.22

4. The following documents shall be deemed to form and be read and construed as part of this Agreement viz.

- (i) Letter of Acceptance
- (ii) Contractor's Bid;
- (iii) Section VI- General Conditions,
- (iv) Section VII- Particular Conditions,
- (v) Section V- Technical Specifications (General and Supplementary Technical Specifications)
- (vi) Appendix A- Drawings
- (vii) Section IV- Works Schedule
- (viii) Quality Plan For Output and Performance Based Road Contract as per Clause A 14.1 of the Technical Specifications
- (ix) Appendices to the Contract
- (x) Addenda issued during bid period
- (xi) Any other relevant documents listed in the Particular Conditions together with any post bid Correspondence

In witnessed whereof the parties there to have caused this Agreement to be executed the day and year first before written.

The Common Seal of
was hereunto affixed in the presence of:

Signed, Sealed and Delivered by the said
in the presence of:

Binding Signature of E/I

Binding Signature of Contractor

12/04/22
EXECUTIVE ENGINEER

एम. 21 कुमार सिंह

12/04/22
Raj

**OFFICE OF THE EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION, BETTIAH**

Letter no...../Bettiah Date...../

From

Executive Engineer,
Rural Works Division,
Works Division Bettiah.

To

Nav Bharti Builders India Pvt. Ltd.,
At.- Khap tola, Nautan, West Champaran

Sub:- Issue of Notice to proceed with the work .

Dear Sirs,

Pursuant to your furnishing the requisite security as stipulated in GC Clause 53.3 and signing of the Contract execute Output and Performance based Rural Road Contract for the Maintenance of Roads **MR/-N/19-20 Bettiah/31 (Tender ID- 88243) Under MR-N** at a Bid Price Rs. 64,71,983.00 (Rs. Sixty Four Lac Seventy One Thousand Nine Hundred Eighty Three One).

You are hereby instructed to proceed with the execution of the said works in accordance with the contract documents.

Yours faithfully,

(Signature)
12/04/22
Executive Engineer

R.W.D. Works Division Bettiah

(Signature)
12/04/22

(Signature)
12-04-22

(Signature)
वर्मा कुमारी

**OFFICE OF THE EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION, BETTIAH**

Letter no...../Bettiah Date...../

From
Executive Engineer,
Rural Works Division,
Works Division Bettiah.

To
Nav Bharti Builders India Pvt. Ltd.,
At.- Khap tola, Nautan, West Champaran

Sub:- Issue of Notice to proceed with the work .

Dear Sirs,

Pursuant to your furnishing the requisite security as stipulated in GC Clause 53.3 and signing of the Contract execute Output and Performance based Rural Road Contract for the Maintenance of Roads **MR/-N/19-20 Bettiah/31 (Tender ID- 88243) Under MR-N** at a Bid Price **Rs. 64,71,983.00 (Rs. Sixty Four Lac Seventy One Thousand Nine Hundred Eighty Three One).**

You are hereby instructed to proceed with the execution of the said works in accordance with the contract documents.

Yours faithfully,






Executive Engineer
R.W.D. Works Division Bettiah

Memo No.:-.....Bettiah/Date:-...../

Copy Forwarded to Assistant Engineer, R.W.D. Works Sub-division, Nautan for the necessary action.

रामेश कुमार सिंह


12/04/22
Executive Engineer
R.W.D. Works Div. Bettiah

12/04/22

12-04-22

**OFFICE OF THE EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION, BETTIAH**

Letter no...../Bettiah Date.....

From

Executive Engineer,
Rural Works Division,
Works Division Bettiah.

To

Nav Bharti Builders India Pvt. Ltd.,
At.- Khap tola, Nautan, West Champaran

Sub:- Issue of Notice to proceed with the work .

Dear Sirs,

Pursuant to your furnishing the requisite security as stipulated in GC Clause 53.3 and signing of the Contract execute Output and Performance based Rural Road Contract for the Maintenance of Roads **MR/-N/19-20 Bettiah/31 (Tender ID- 88243) Under MR-N at a Bid Price Rs. 64,71,983.00 (Rs. Sixty Four Lac Seventy One Thousand Nine Hundred Eighty Three One).**

You are hereby instructed to proceed with the execution of the said works in accordance with the contract documents.

Yours faithfully,

[Signature]
12/04/22
Executive Engineer
R.W.D. Works Division Bettiah

Memo No.:.....Bettiah/Date:.....
Copy Forwarded to Assistant Engineer, R.W.D. Works Sub-division, Nautan for the necessary action.

[Signature]
12/04/22
Executive Engineer
R.W.D. Works Div. Bettiah

[Signature]
12/04/22