

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs *muz east /*
- 2 Name of Block/Road *Saraya Motipur panchayat Raylunathan*
middle school east - north muz chure
- A For Road
- 1 Damage Location/Chainage *nearby Collection,*
- 2 Damage Length *100m*
- 3 Nature of Damage *Beach line to flood —*
- 4 Details of Restoration Works *Bamboos with local soil,*
EC Bag, Trencher,
- i Material being used in Restoration Works
- ii Equipments/Tools being used in Restoration Works *J.C.B, Trencher,*
- iii Procedure Taken up in Restoration Works *N/A*
- iv Restored Length *N/A* *work found satisfactory,*
- B For Bridge
- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works *HA*
- i Material being used in Restoration Works
- ii Equipments/Tools being used in Restoration Works
- iii Procedure Taken up in Restoration Works
- iv Restored Length

[Signature]
Signature of JE/AE/EE
24.11.17

[Signature]
Signature
(Name of Inspector)
काम प्रमण्डल, महानगर

FDR

YEAR (2021-2022)

GENERAL ABSTRACT OF COST

Restoration of Road from Saraiya Motipur pwd road Raghunathpur Middle school
east north muza chowk in Mushari Block Under F.D.R., RWD Works Division
Muzaffarpur East-1

Block :- ^{Saraiya} Mushari

District :- Muzaffarpur

S.N.

Description

Amount

Road Restoration Cost

61887.00

~~64258.00~~

Total

~~64258.00~~

61887.00

Say

~~64258.00~~ 61887.00

Say 0.619 lac

^{Kanjan}
J.E.

A.E.

^{24.11.21}
Executive Engineer
RWD Works Division
Muzaffarpur East-1

As Per S.E. RWD (M) Circle Muz.
Letter No 1179 Dated 01/10/2021
Estimate has been verified by inspecting
E.E. RWD (M) Division Muzaffarpur

Technically Sanctioned for Rs. 0.619 lac (Rs. Sixty
one thousand nine hundred) only (provisionally)

^{27.12.21}
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

Abstract of Cost & Detailed Estimate For

Restoration of Road from Saraiya Motipur pwd road Raghunathpur Middle school east north
muza chowk in ~~Mushari~~ Block Under F.D.R., RWD Works Division Muzaffarpur East-1
Saraiya

S. N.	SOR	Item of Work	Quantity	Unit	Rate	Amount
1	2	3	4	5	6	7
1		Providing and laying Brick bats, including all taxes etc. all complete job as per specification and direction of E/I.				
		As per MB	0.000	Cum	2161.18	0.00
2		Providing E.C.Bag filled with local sand etc. all complete job as per specification and direction of E/I.			<i>39.37</i>	<i>48819.00</i>
		As per MB	1240.00	Bag	<i>38.25</i>	<i>47430.00</i>
3		Providing Bamboo pile etc. all complete job as per specification and direction of E/I.			<i>53.53</i>	<i>11455.00</i>
		As per MB	214.00	m	<i>64.06</i>	<i>13708.84</i>
4		Providing Bamboo Runners etc. all complete job as per specification and direction of E/I.			<i>16.46</i>	<i>1613.00</i>
		As per MB	98.00	m	<i>31.83</i>	<i>3119.34</i>
5	5.6.2.4	Labour for laying, fitting and fixing NP3 pipe with collars in line level and grade as well providing approved jointing materials and joints properly filled to make them water proof all complete as per specification and direction of E/I (Hume pipe available within a lead of 40 mtr 1000mm dia or 100mm dia NP3 HP.				
		As per MB	0.00	m	3992.28	0.00
					Total Rs.	64258.18
					Say Rs.	64258.00

[Signature]
JE

AE

[Signature]
24.11.24
Executive Engineer
RWD Works Division
Muzaffarpur East-1