

# Inspection Report for Flood Damage Report

Date :

- 1 Name of PIUs : EE, RWD, Woreda Division, Amharu
- 2 Name of Block/ Road : Sereya / Hulle Reja to upland m<sup>2</sup> Udaipur
- A. For Road :
- 1 Damage Location/Chainage : At Ch. 150 m
- 2 Damage Length : 7.5 m
- 3 Nature of Damage : Complete traffic blocked due to breach of lined from flood water
- 4 Details of Restoration Works : (71.25) Police Barracks & Home pipe (1000mm) (7.50 m)
- i. Material being used in Restoration works : Jers, tractor, Road Roller
- ii. Equipments/Tools being used in Restoration works : Immediate Restoration of Home
- iii. Procedure taken up in Restoration works : 7.50 m
- iv. Restored Length : Work found satisfactory
- B For Bridge :
- 1 Damage Location/Chainage :
- 2 Damage Length :
- 3 Nature of Damage :
- 4 Details of Restoration Works : N/A
- i. Material being used in Restoration works :
- ii. Equipments/Tools being used in Restoration works :
- iii. Procedure taken up in Restoration works :
- iv. Restored Length :

Signature of JE / AE / EE

Signature  
(Name of Inspector)  
कार्य प्रमण्डल, म.ना.क

FDR

YEAR (2021-2022)

**GENERAL ABSTRACT OF COST**

Restoration of Road from Hulas Bazar to Ufaraul via Udaipur in  
Saraiya Block under F.D.R., RWD, Works Division, Muzaffarpur  
East-1

Block :- Saraiya

District :- Muzaffarpur

Sl  
No.

Description

Amount

Road Restoration Cost

- Rs.

184743  
184,000.00  
~~179449~~  
160765.00


Total

Say Rs.

184,000.00  
1,84,000.00  
~~184743~~ 179449  
Say Rs. 1.85 lac  
~~1.79 lac~~  
1.608  
lac


  
Junior Engineer  
RWD, Works Section  
Saraiya

Assitant Engineer  
RWD, Works Sub-Div.  
Saraiya

  
Executive Engineer  
RWD, Works Division  
Muzaffarpur East-1

As Per S.E. RWD (W) Circle Muz.  
Letter No 1179 Dated 01/10/2021  
Estimate has been verified by inspecting  
E. E. RWD. (W) Division Mahner

Technically Sanctioned for Rs. 1.608 lac  
(Rs. one lac Sixty thousand eight hundred)  
only (Provisionally)

  
27.12.21  
Superintending Engineer  
Rural Works Department  
Work Circle, Muzaffarpur  
27.12.21


# Abstract of Cost & Detailed Estimate for

## Restoration of Road from Hulas Bazar to Ufaraul via Udaipur in Saraiya Block under F.D.R., RWD, Works Division, Muzaffarpur East-1

Sl. No.	SO R	Item of Work	Quantity	Unit	Rate	Amount
1		2	6	7	8	9
1		Providing and laying Brick bats, including all taxes etc. all complete job as per specification and direction of E/I.	62.20		2064.56	128416.00
		As per M.B	<del>71.25</del>	m <sup>3</sup>	2101.78	<del>147100</del> 153084.00
2	5.6. 2.4	Labour for laying, fitting and fixing NP3 pipe with collors in line level and grade as well providing approved jointing materials and joints properly filled to make them water proof all completeas per specification and direction of E/I. (Hume pipe available within a lead of 40 mtr 1000 mm dia or 100 mm dia NP3 H.P			4313.21 <del>5019.06</del>	323490 <del>27643</del>
		As per M.B	7.50	m	3992.28	29942.00
					Total Rs.	1,83,926.00 <del>1,84,743</del>
					Say Rs.	1,84,000.00 <del>1,84,743</del>

  
24/11/24  
Junior Engineer  
RWD, Works Section  
Saraiya

Assitant Engineer  
RWD, Works Sub-Div.  
Saraiya

  
28-11-24  
Executive Engineer  
RWD, Works Division  
Muzaffarpur East-1

160765.00