



ग्रामीण कार्य विभाग

RURAL WORKS DEPARTMENT, GOVT OF BIHAR

DETAILED PROJECT REPORT FOR FDR 2021-2022



Name of Road :-	NH 104 NARHAR PAKRI SE BHARTHUIYA		
DISTRICT	EAST CHAMPARAN		
DIVISION	CHAKIA		
BLOCK	CHAKIA		
TOTAL LENGTH OF ROAD	1.5	KM	
COST OF RECTIFICATION	0.961 0.868	LAC	

Inspection Report For Flood Damage Work

Date :-

1. Name of PIUs- Executive Engineer RWD, Chakia
2. Name of Block- Chakia
3. Name of Road- NH 104 Narhar Pakur se Barthuiya.

(A) For Road

1. Damage Location/ Chainage:- 250 - 1400 mtr.
2. Damage Length:- ~~1250 mtr~~ 125 m
3. Nature Of Damage:- Surface damaged due to heavy rain.
4. Details Of Restoration works:-
 - (i) Material being used in restoration works:- Brick bat, local Sand,
 - (ii) equipments /Tools being used in Restoration works:- Tractor, JCB, Static Roller,
 - (iii) Procedure taken up in Restoration Works:- Departmental.
 - (iv) Restored length:- 125 mtr

Work found satisfactory


Signature of Inspecting officer,
Executive Engineer
Rural Works Department
Works Division, Raxaul

प्रतिवेदन

कार्य का नाम :- NH104 Narhar Pakui se Bhanthulya

.....पथ में अप्रत्याशित बाढ़ / अतिवृष्टि 2021 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड :- चकिया

वित्तीय वर्ष : 2021-2022

प्रकलित राशि :-

प्रस्तुत प्राक्कलन, जिसकी प्रकलित राशि 0.961 लाख है, प्रखण्ड चकिया में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।


अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 4275 दिनांक 22/10/21 द्वारा दिये गए निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त भाग में brick Bats & Local sand भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चालू अनुसूचित दर पर तैयार किया गया है। इसकी घटनोत्तर स्वीकृति अपेक्षित है।


23/10/21

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा चकिया


23/10/21

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल चकिया


23/10/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल चकिया

GENERAL ABSTRACT OF COST FOR FDR

Name of road NH 104 NARHAR PAKRI SE BHARTHUIYA
District EAST CHAMPARAN
Block CHAKIA
Division CHAKIA
length of road (in Km) 1.5

SL NO	DESCRIPTION	AMOUNT (LAKHS)
1	Excavation in soil using hydraulic excavator	-
2	Brick bats	80751.00 86,878.00
3	Sand filling	6047.00 9,192.00
4	Sand bags	
5	Bamboo piles	
Total		INR 96,070.00

86,798.00
Qty 86,800.00

ABW
23/10/21
Junior Engineer
Rural Works Department
Work Section,
Chakia

ABW
23/10/21
Assistant Engineer
Rural Works Department
Work Sub Division
Chakia

ABW
23/10/21
Executive Engineer
Rural Works Department
Works Division,
Chakia

For factor A.T.S is accorded for Rs. 86,800.00
(~~Eighty Six Eight~~
.....crore.....lacs.....thousand
.....hundred.....) only.

S.E. (R.W.D.)
works Circle
Motihari

Post-facto T.A/T.S is accorded for Rs. 86,800.00
[.....] crore [.....] lac Eighty six thousand
[.....] hundred [.....] only.


S.E. (R.W.D.)
works Circle
Molhari

SL NO.	SBD SL NO.	MORD REF NO.	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT (IN RS.)
1	3.5	302(iii)	Excavation in soil using Hydraulic Excavator excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting only and as per Technical Specification Clause 302.3				
			Appendix -I	cum	0	112.47	0
2			Brick Bats laying Brick Bats in ditches as per direction and specification with all complete job				
			Appendix -II	cum	42.17	2060.40	86878
			Sand Filling				
3			Filling in foundation trenches as per drawing and technical specification clause 305.3.9				
			Appendix -III	cum	19.99	459.91	9192

1914.89

80751.80

302.50

6047.00

Name of Road :- NH 104 NARHAR PAKRI SE BHARTHUIYA

Block :- CHAKIA
Appendix - II

sl no	Chainage	no	Length	Width (M)	Avg. Width (M)	Thickness (M)	Av. Thickness (M)	quantity (Cum)
1		1	20		1.0		0.200	4.00
2		1	17		1.5		0.250	6.38
3		1	3		2.0		0.225	1.35
4		1	17		2.0		0.225	7.65
5		1	4		1.5		0.200	1.20
6		1	2		1.0		0.100	0.20
7		1	2		1.0		0.100	0.20
8		2	3		2.0		0.175	2.10
9		1	2.5		3.8		0.175	1.64
10		1	6		1.0		0.225	1.35
11		1	3		2.0		0.200	1.20
12		2	2		3.0		0.175	2.10
13		1	8		1.0		0.250	2.00
14		1	2		1.0		0.150	0.30
15		1	1		1.0		0.100	0.10
16		1	3		2.0		0.225	1.35
17		1	17		2.0		0.225	7.65
18		1	4		1.5		0.200	1.20
19		1	2		1.0		0.100	0.20

TOTAL 42.17

Abw
23/10/21
Junior Engineer
Rural Works Department
Work Section,
Chakia

W.D.
23/10/21
Assistant Engineer
Rural Works Department
Work Sub Division
Chakia

W.D.
23/10/21
Executive Engineer
Rural Works Department
Works Division,
Chakia

Name of Road :- NH 104 NARHAR PAKRI SE BHARTHUIYA


Block :- CHAKIA

Appendix - III

sl no	Chainage	no	Length	Width (M)	Avg. Width (M)	Thicknes s(M)	Av. Thicknes s (M)	quantity (Cum)
1		1	20		1.0		0.100	2.00
2		1	17		1.5		0.100	2.55
3		1	3		2.0		0.100	0.60
4		1	17		2.0		0.100	3.40
5		1	4		1.5		0.100	0.60
6		1	2		1.0		0.100	0.20
7		1	2		1.0		0.100	0.20
8		2	3		2.0		0.100	1.20
9		1	2.5		3.8		0.100	0.94
10		1	6		1.0		0.100	0.60
11		1	3		2.0		0.100	0.60
12		2	2		3.0		0.100	1.20
13		1	8		1.0		0.100	0.80
14		1	2		1.0		0.100	0.20
15		1	1		1.0		0.100	0.10
16		1	3		2.0		0.100	0.60
17		1	17		2.0		0.100	3.40
18		1	4		1.5		0.100	0.60
19		1	2		1.0		0.100	0.20
TOTAL								19.99


23/10/21
Junior Engineer
Rural Works Department
Work Section,
Chakia


23/10/21
Assistant Engineer
Rural Works Department
Work Sub Division
Chakia


23/10/21
Executive Engineer
Rural Works Department
Works Division,
Chakia