



ग्रामीण कार्य विभाग

RURAL WORKS DEPARTMENT, GOVT OF BIHAR

DETAILED PROJECT REPORT FOR FDR 2021-2022



Name of Road :-	NH 104 Kumhar toli to Ghanshayam Pakri through Siv Mandir		
DISTRICT	EAST CHAMPARAN		
DIVISION	CHAKIA		
BLOCK	CHAKIA		
TOTAL LENGTH OF ROAD	2.3	KM	
COST OF RECTIFICATION	2.621- 2.369	LAC	

Inspection Report For Flood Damage Work

Date :-

1. Name of PIUs- Executive Engineer RWD, Chakia

2. Name of Block- Chakia

3. Name of Road- NH104 kumhar toll to Ghanshyam Pakur through
Shiv mandir

(A) For Road

1. Damage Location/ Chainage:- 0 - 2200

2. Damage Length:- 450 mtr

3. Nature Of Damage:- Road damaged due to heavy rain & water logging.

4. Details Of Restoration works:-

(i) Material being used in restoration works:- Brick bat, local Sand,

(ii) equipments /Tools being used in Restoration works:- Tractor, JCB, Static Roller,

(iii) Procedure taken up in Restoration Works:- Departmented.

(iv) Restored length:- 450 mtr

work found satisfactory


Signature of Inspecting Officer
(Executive Engineer)
R.W.D. W.D. Raxaul

प्रतिवेदन

कार्य का नाम :- NH 104 Kumhar T.O. to Ghanshyam palku

.....पथ में अप्रत्याशित बाढ़ / अतिवृष्टि 2021 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड :- चकिया

वित्तीय वर्ष : 2021-2022


प्रकलित राशि :-

प्रस्तुत प्राक्कलन, जिसकी प्रकलित राशि2.62..... है, प्रखण्ड चकिया में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।


अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक4275 दिनांक 22/10/21 द्वारा दिये गए निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त भाग में brick Bats & Local sand भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चालू अनुसूचित दर पर तैयार किया गया है। इसकी घटनोत्तर स्वीकृति अपेक्षित है।


23/10/21

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा चकिया


23/10/21

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल चकिया


23/10/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल चकिया

GENERAL ABSTRACT OF COST FOR FDR

Name of road NH 104 Kumhar toli to Ghanshayam Pakri through Siv Mandir
District EAST CHAMPARAN
Block CHAKIA
Division CHAKIA
length of road (in Km) 2.3

SL NO	DESCRIPTION	AMOUNT (LAKHS)
1	Excavation in soil using hydraulic excavator	-
2	Brick bats	237,353.00
3	Sand filling	24,750.00
4	Sand bags	
5	Bamboo piles	
Total		INR 262,103.00

ABW
23/10/21
Junior Engineer
Rural Works Department
Work Section,
Chakia

ABW
23/10/21
Assistant Engineer
Rural Works Department
Work Sub Division
Chakia

ABW
23/10/21
Executive Engineer
Rural Works Department
Works Division,
Chakia

Rest factor *1.15* is accorded for Rs. *236900.00*
1 crore *23* Lacs *thirty six*
thousand *nine* hundred

SE (R.W.D.)
works Circle
Motihani

SL NO.	SBD SL NO.	MORD REF NO.	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT (IN RS.)
1	3.5	302(iii)	Excavation in soil using Hydraulic Excavator excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting only and as per Technical Specification Clause 302.3				
			Appendix -I	cum	0	112.47	0
2			Brick Bats laying Brick Bats in ditches as per direction and specification with all complete job				
			Appendix -II	cum	- 115.20	2060.40	237353
			Sand Filling Filling in foundation trenches as per drawing and technical specification clause 305.3.9				
3			Appendix -III	cum	- 53.82	459.91	24750

1914.89 220595.00

802.50

16281.00

Name of Road :- NH 104 Kumhar toli to Ghanshayam Pakri through Siv Mandir

Block :-

CHAKIA

Appendix - II

sl no	Chainage	no	Length	Width (M)	Avg. Width (M)	Thickness (M)	Av. Thickness (M)	quantity (Cum)
1		1✓	33		3.50		0.225	25.99
2		1	6		1.50		0.175	1.58
3		1	12		2.00		0.300	7.20
4		1	12		1.50		0.200	3.60
5		1	2		1.50		0.100	0.30
6		1	2		3.75		0.200	1.50
7		1	3		1.00		0.150	0.45
8		1	4		1.00		0.175	0.70
9		1	5		1.50		0.150	1.13
10		1	10		1.50		0.225	3.38
11		1	11		3.75		0.300	12.38
12		1	2		1.50		0.150	0.45
13		1	3		3.50		0.200	2.10
14		1	3		1.00		0.150	0.45
15		1	3		1.50		0.150	0.68
16		1	4		1.50		0.150	0.90
17		1	2		3.20		0.150	0.96
18		1	3		1.00		0.150	0.45
19		1	5		1.50		0.175	1.31
20		1	2		3.75		0.175	1.31
21		1	2		1.50		0.100	0.30
22		1	1		3.75		0.200	0.75
23		1	3		3.75		0.200	2.25
24		1	7		2.00		0.175	2.45
25		1	2		3.75		0.175	1.31
26		1	1		4.00		0.150	0.60
27		1	3		1.00		0.175	0.53
28		1	2		1.00		0.150	0.30
29		1	3		3.00		0.175	1.58
30		1	1		1.00		0.100	0.10
31		1	11		2.00		0.225	4.95
32		1	5		2.00		0.200	2.00
33		1	3		1.50		0.150	0.68
34		1	4		2.00		0.150	1.20
35		1	2		2.00		0.150	0.60

36		1	2		3.00		0.150	0.90
37		1	3		3.75		0.200	2.25
38		1	7		2.00		0.175	2.45
39		1	2		3.75		0.175	1.31
40		1	5		2.00		0.200	2.00
41		1	3		1.50		0.150	0.68
42		1	4		2.00		0.150	1.20
43		1	4		1.00		0.175	0.70
44		1	5		1.50		0.150	1.13
45		1	10		1.50		0.225	3.38
46		1	11		3.75		0.300	12.38
47		1	2		1.50		0.150	0.45

Total **115.20**

Abu
23/10/21
Junior Engineer
Rural Works Department
Work Section,
Chakia

P.O.
23/10/21
Assistant Engineer
Rural Works Department
Work Sub Division
Chakia

[Signature]
23/10/21
Executive Engineer
Rural Works Department
Works Division,
Chakia