



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Govt. of Bihar

FDR(Motorable)

Estimate for Motorable of Road from Korwan Ghana Bigha Road to Parbigha Via Aharapar in Nalanda District.



Name of the Road :-

Korwan Ghana Bigha Road to Parbigha Via Aharapar

DISTRICT	:	NALANDA	
DIVISION	:	HILSA	
BLOCK	:	HILSA	
TOTAL COST OF CONSTRUCTION	:	4.136	Lac
TOTAL COST OF PROJECT	:	4.136	Lac

SUBMITTED BY
RURAL WORKS DEPARTMENT
WORKS DIVISION-HILSA

3.545 Lac

25-10-2021
J-E

22/10/21

INSPECTION REPORT FOR FLOOD DAMAGE WORK

2:

1. Name of PIUS :- EE R.W.D. HILSA
2. Name of Block/Road :- HILSA

For Road : Koriwan Ghana Bisha Road to Purbigha Via Ahasaraj

1. Damage Location/Change :-
2. Damage Length :- 26.9 m
3. Nature of Damage :-
4. Details of Restoration Works :-
 - i. Material Being used in Restoration works :- Brickbats
 - ii. Equipment's / Tools being used in Restoration works :- Tractor trolly, J.C.B. Roller
 - iii. Procedure taken up in restoration works :- Mechanically & manually
 - iv. Restored Length :- 26.9 m

For Bridge :

1. Damage Location / Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works :-
 - i. Material Being used in Restoration works :-
 - ii. Equipment's / Tools being used in Restoration works :-
 - iii. Procedure taken up in restoration works :-
 - iv. Restored Length :-

Requirement of New CD/Bridge :

- i. Name of Road :-
- ii. Location Chainage :-
- iii. Type of CD work/Length required :-

- Upload one photograph of damaged portion if available

- Attach minimum two photograph (during restoration & after restoration) photographs should be Geotags and at least one photo be captured in selfie mode.

[Signature]
09.12.2021

JE

[Signature]
9/12/21

AE

EE

[Signature]

Executive Engineer
Rural Works Department
Works Division, Rajgir

The work is satisfactory.

Measurements:

$$\textcircled{1} \quad 10 \text{ m} \times 4.1 \text{ m} \times \frac{2.40 + 3.90 + 2.70}{3} \text{ m} \\ = 10 \text{ m} \times 4.1 \text{ m} \times 3.0 \text{ m} = 123.00 \text{ m}^3$$

$$\textcircled{2} \quad 2.90 \text{ m} \times \frac{1.10 + 1.60 + 1.40}{3} \times 1.3 \text{ m} \\ = 2.90 \text{ m} \times 1.367 \text{ m} \times 1.3 \text{ m} = 5.150 \text{ m}^3$$

$$\textcircled{3} \quad 8.50 \text{ m} \times \frac{1.3 + 1.80 + 2.20}{3} \times \frac{2.10 * 1.9 + 1.8}{3} \\ = 8.50 \text{ m} \times 1.767 \text{ m} \times 1.933 \text{ m} = 29.030 \text{ m}^3$$

$$\textcircled{4} \quad 5.50 \text{ m} \times \frac{2.8 + 2.70 + 2.90}{3} * \frac{2.50 + 2.40 + 2.60}{3} \\ = 5.50 \text{ m} \times 2.8 \text{ m} \times 2.5 \text{ m} = 38.500 \text{ m}^3$$

Ans
09/12/21

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD : Korwan Ghana Bigha Road to Parbigha Via Aharapar

DISTRICT NALANDA
BLOCK HILSA
DIVISION HILSA

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	BRICK BATS	354 500.00 413588.000
	Total	413588.000
	TOTAL COST IN LACS =	4.136
	TOTAL COST OF PROJECT IN LACS =	4.136

Rama
25/10/2021
TE
RWD

Ad
27/10/21
AE
RWD

3.545 Lacs
R
27/10
EE
RWD

Total - 3.545 Lacs

Technically approved for Rs.....

(Rupees.....)

Condition and direction laid down in attached technical notes with DPR is be followed Strictly

S. E.
RWD
Work Circle Nalanda

Technically Sanctioned for Rs. 3 54 500=00
(Rupees Three Lacs Fifty Four Thousand
Five Hundred only)
Condition and direction attached
technical notes with it and Strictly.

Abur
24/12/2021

S. E.

RWD

Work Circle Nalanda

22/12/2021

Estimate for Motorable of Road from Korwan Ghana Bigha Road to Parbiga Via Aharapar in Nalanda District.

Name of Road Korwan Ghana Bigha Road to Parbiga Via Aharapar

Sl. No.	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
	SUB HEAD : EARTHWORK, BRICKS BATS, SAND FILLING								
1	Construction of Bricks Bats								
	Supplying Brick bats with carriage at site including labour cess , GST and seigniorance fee (excluding over head and CP)						167.725 195.680	1,201.00	201437= 2,35,012.00
		cum							
2	Carrige for Brick bats including labour cess & GST (excluding over head and CP)	No					167.725 195.680	564.910	94749= 1,10,542.00
3	Supplying unskilled labour for Brick bats and laying 600 mm dia for spreading and levelling brick bats including labour cess & GST (excluding over head and CP)	No					177.788 207.421	328.00	58314= 68,034.00
									4,13,588.00
									354500=

Bar
28-10-2021
RWD

AE
27/10/21
RWD

EE
27/10
RWD

Name of
Road Korwan Ghana Bigha Road to Parbigha Via Aharapar
Block HILSA
District NALANDA

Calculation of Brick Bats

Sl.No	Lenth (m)	Width(m)	Thickness (m)	Qty. (Cum)
1	5.50 ✓	2.800 ✓	2.500 ✓	38.500 ✓
2	8.50 ✓	1.767 ✓	1.933 ✓	29.030 ✓
3	10.00 ✓	4.100 ✓	3.000 ✓	123.000 ✓
4	2.90 ✓	1.367 ✓	1.300 ✓	5.150 ✓
			Total	195.680

Ram
25.10.2021
J.E

Ad
27/10/21
A.E

R
27/10
E.E

Prith
09/12/21

Quantity after deduction of voids $195.680 \text{ m}^3 \times \frac{12}{17} = 167.725 \text{ m}^3$

Ad
9/12/21
A.E

Ram
09/12/2021
J.E

Analysis for Carriage by Road (By Tractor)

Name of Road:- Korwan Ghana Bigha Road to Parbigha Via Aharapar
 District:- NALANDA Block:- HILSA

Sl No	Item with Source	Unit	Source Up to	Carriage Cost & Lead in Km										Loading & Unloading Cost	Carriage Cost by Rail Head	Total				
				Pucka / Surface					Katcha											
1	Brick bat	Cum	Local	3.60	x	22.24	x	7.00 Km	=	Rs 249.09	3.60	x	27.78	x	1.00 Km	=	Rs 44.46	206.37	0.00	Rs. 499.92
				2.25							2.25									

Carriage Including GST and Labour Cess For Brick
Bats

564.9096

Ram
25/10/21
JE
RWD

Rat
27/10/21
AE
RWD

R
27/10
EE
RWD