

Inspection Report for Flood Damage Work

Date:

1. Name of PIUs – Executive Engineer, R.W.D., Works, Division,

2. Name of Block - TALPUR

3. Name of Road/Bridge - Gonj pul to Boghi

A. for Road

1. Damage Location/Chainage :

2. Damage Length : 59411

3. Nature of Damage

4. Details of Restoration Works :

i. Material being used in Restoration works : BRICK BAT ETC

ii. Equipments/Tools being used in Restoration Works : *TRACTOR, JCB, ROLLER, ETC*

iii. Procedure taken up in Restoration works :

iv. Restored Length : 594M

B. for Bridge

1. Damage Location/Chainage :

2. Damage Length

3. Nature of Damage

4. Details of Restoration Works :

i. Material being used in Restoration works :

ii. Equipments/Tools being used in Restoration Works :

iii. Procedure taken up in Restoration works :

iv. Restored Length :

950w
15104222
J.E.

20412
A.E.

Executive Engineer,
R.W.D. Works Division,
Samsatpur

Signature
(Name of Inspector)

E.E. Bai, a
RND mms w/30y


कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, समस्तीपुर


प्रतिवेदन


योजना का नाम : गंज पुल से बाधी।
लंबाई : 3.334 कि०मी०।
प्राक्कलित राशि : 2.22.6. लाख।
प्रखंड : ताजपुर।

प्रस्तुत प्राक्कलन ताजपुर प्रखंड अन्तर्गत गंज पुल से बाधी पथ के तत्कालीन मरम्मत कार्य के लिए बनाया गया है। विगत दिनों अत्यधिक बरसात होने के कारण उक्त पथ में गड़ढ़े हो जाने के कारण यातायात बाधित हो रहा था। आवागमन सुचारु करने के लिए प्राक्कलन में ब्रीक्स बैट्स एवं 600 mm dia Hume Pipe का प्रावधान इस प्राक्कलन में किया गया है।

प्राक्कलन वर्तमान अनुसूचित दर पर बनाया गया है जिसकी तकनीकी अनुमोदन एवं प्रशासनिक स्वीकृति अपेक्षित है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, ताजपुर


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, ताजपुर


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, समस्तीपुर

**कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, बलिया**

पत्रांक 01, ~~कैम्प सहायिता~~ दिनांक 18/12/21

प्रेषक:- कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बलिया।

सेवा में,
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, समस्तीपुर।

विषय:- FDR योजना के जाँच के संबंध में।

प्रसंग:- आपका पत्रांक 2292 दिनांक 23.11.21
महाशय,


उपर्युक्त विषयक प्रासंगिक पत्र के संबंध में कहना है कि निम्नलिखित योजनाओं की जाँचोपरान्त प्राक्कलन सहित लौटायी जाती है।

क्र०	योजना का नाम	प्रखंड	पथ की लंबाई (कि०मी० में)	प्राक्कलित राशि (लाख में)	अभ्युक्ति
1	पूसा बाजार में राज स्टुडियो के निकट से हाथी चौक पप्पु चौधरी के दुकान तक	पूसा	0.500	2.260	
2	गढ़िया चौक से घोबगामा सीमा	पूसा	3.520	14.810	
3	पूसा बाजार बोस कम्पनी चौक से दुबहा भाया भुसकौल चौक	पूसा	5.900	4.050	
4	हरपुर पीच रोड से जगदीशपुर भाया नावाचक नारायणपुर	पूसा	4.570	9.840	
5	दिधरा पंचायत विशनपुर मोड़ संजय पासवान के घर से कृषि वि० केन्द्र बिरौली	पूसा	3.000	10.120	
6	वैनी टेलीफोन एक्सचेंज से पी.डब्लू.डी. रोड आयरन फैक्ट्री होते हुए चन्दौली	पूसा	6.570	9.650	
7	पी०डब्लू.डी. मोतीपुर चौक से दाउदपुर पैक्स भाया भैरोखरा इमली चौक	समस्तीपुर	3.000	3.923	
8	लक्खी चौक से रसलपुर भाया केवस मंदिर	समस्तीपुर	3.000	1.006	
9	टी०१ से जितवारपुर	समस्तीपुर	1.000	2.240	
10	रामकृष्णपुर आर०ई०ओ० से किशनपुर आर०ई०ओ० तक	समस्तीपुर	1.600	2.820	
11	आधारपुर से विक्रमपुर बान्दे	समस्तीपुर	5.680	1.120	
12	धुरलख मिडिल स्कूल से एन०एच० मोहनपुर	समस्तीपुर	1.200	7.040	
13	हरपुर एलोथ से साह जी टोला	समस्तीपुर	1.050	0.669	
14	एल०४८ से एस०एच० धुरलख	समस्तीपुर	1.560	1.319	
15	एल०६३ एस०एच० से नीरपुर	समस्तीपुर	2.897	0.250	
16	एस०एच० टी०४ से चकअब्दुलगनी	समस्तीपुर	1.200	1.390	

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग कार्य प्रमंडल बलिया

17	कुशैया पारसनाथ ठाकुर के घर से मोईन पोखर गोलक सदा के घर होते हुए विषहर स्थान	वारिसनगर	1.060	5.660	
18	एल051 चकमिल्की से हजपुरवा	वारिसनगर	3.200	3.050	
19	नकटा वारिसनगर से बल्लीपुर	वारिसनगर	7.500	7.140	
20	बसंतपुर रमणी में नक्दोल घाट से कमला बाहा एल027	वारिसनगर	2.500	11.910	
21	इलमासनगर से किशनपुर रेलवे स्टेशन	वारिसनगर	5.000	1.890	
22	भुट्टा राउत चौक बलाही से मोहिउद्दीनपुर भाया तारी टोला	वारिसनगर	3.660	5.080	
23	टी02 परोडिया से मोहिउद्दीनपुर	वारिसनगर	6.100	1.350	
24	प्यारेलाल महतो के घर से शंकर चौक	वारिसनगर	2.430	7.410	
25	लभट्टा चौक से महादलित टोला	वारिसनगर	0.970	1.410	
26	एस0एच0 से नरंगा	कल्याणपुर	2.636	2.579	
27	कुशियारी चौक से परना डरोरी पथ	कल्याणपुर	4.100	6.449	
28	कल्याणपुर चौक से मधुबन किशनपुर	कल्याणपुर	4.100	3.607	
29	लदौरा से चकमहेशी गंगौरा	कल्याणपुर	17.060	7.604	
30	खानपुर पी0सी0सी0 रोड से सिमरी चन्द्रसेन पथ	खानपुर	3.300	3.066	
31	बरगाँव चौक से शोभन घाट	खानपुर	2.600	5.339	
32	खैरी से खैराज पथ	खानपुर	5.450	14.094	
33	खानपुर से मननपुर तक भाया शादीपुर	खानपुर	7.100	7.976	
34	बच चौक से बच घाट पार्ट-1	ताजपुर	0.200	0.890	
35	टी01 सरकरगंज से नून नदी पुल	ताजपुर	0.625	1.467	
36	टी01 से मथुरापुर पार्ट-1	ताजपुर	1.100	1.978	
37	गंज पुल से बाघी	ताजपुर	3.334	2.260	
38	कन्सट्रक्सन रोड जोगिया मठ प्राथमिक विद्यालय पी डबल्यू.डी. पथ के निकट से एन0एच0-28 तक जाने वाली पथ	ताजपुर	1.200	4.67 7.500	
39	एन0एच0-28 से मोतीपुर	ताजपुर	0.600	1.010	
40	एन0एच0-28 पेट्रोल पंप से शंकर सीनेमा	ताजपुर	0.500	1.560	
41	एस0एच0 49 खरहा चौक से मीना रानी	ताजपुर	0.900	0.860	
42	एन0एच0-28 गाँधी चौक से नीम चौक	ताजपुर	0.500	1.470	
43	एन0एच0-28 से शंकर सीनेमा	ताजपुर	0.200	1.720	

अनु0-यथोक्त।

विश्वासभाजन

 कार्यपालक अभियंता
 ग्रामीण कार्य विभाग
 कार्य प्रमंडल, समस्तीपुर बलिया

GENERAL ABSTRACT OF COST

Block-

District - Samastipur

Construction Length of Road -

Name of Road -

Sr.No	Item of work	Amount
A	Total Cost of Construction	200232.00
	Add (GST@12% + labours@1%)	26030.00
	Add Seign Fee	-
	Total cost of Project - A	226262.00

Savan
21/11/21
Junior Engineers

Savan
31/11/21
Assistant Engineers

QPR
21/11/21
Executive Engineers
RWD, Samastipur

Sanctioned by Rs 2,26,262.00 say Two Lakh Twenty Six Thousand Two Hundred Sixty two only including cup and cover.

QPR
24/12/21

बसोबस बांधव
होमोपथ कावे विभाग
आ.कावे बांधव, प्रबन्धन
24/12/21

shym
29/12/21
T.A

mate for Road Gronjpur to Baghi for the year 2021-22

Item of work

supplying filling brickbat compacted manually by ~~the~~ ^{the} ~~or~~ ^{or} hammer including all complete job.

No	L	B	D/H	Quantity
1	30.00 M	1.00 M	0.075 M	2.25 M ³
1	5.00 M	1.00 M	0.075 M	0.375 M ³
1	30.00 M	3.75 M	0.100 M	11.25 M ³
1	30.00 M	1.00 M	0.075 M	2.25 M ³
1	20.00 M	2.00 M	0.075 M	3.00 M ³
1	30.00 M	1.00 M	0.075 M	2.25 M ³
1	10.00 M	1.00 M	0.075 M	0.75 M ³
1	30.00 M	2.00 M	0.075 M	4.5 M ³
1	2.00 M	2.00 M	0.075 M	0.3 M ³
2	30.00 M	2.00 M	0.075 M	4.5 M ³
1	13.00 M	1.00 M	0.075 M	0.975 M ³
1	10.00 M	1.00 M	0.075 M	0.75 M ³
2	25.00 M	2.00 M	0.075 M	7.5 M ³
1	30.00 M	1.50 M	0.075 M	3.375 M ³
1	10.00 M	1.50 M	0.075 M	1.12 M ³
2	20.00 M	2.00 M	0.075 M	6.00 M ³
2	20.00 M	1.50 M	0.075 M	4.50 M ³

176.86

previous quantity = 55.64 m³

No	L	B	D	Quantity
1	10.00 M	2.50 M	0.075 M	1.87 m ³
1	5.00 M	2.00 M	0.075 M	0.75 m ³
1	10.00 M	1.00 M	0.075 M	0.75 m ³
1	4.00 M	3.75 M	0.200 M	3.00 m ³
1	2.50 M	3.75 M	0.300 M	2.81 m ³
1	2.00 M	3.75 M	0.300 M	2.25 m ³
2	30.00 M	1.00 M	0.075 M	4.5 m ³
1	30.00 M	3.75 M	0.150 M	16.87 m ³
1	10.00 M	3.75 M	0.075 M	2.81 m ³
1	2.00 M	1.00 M	0.075 M	0.15 m ³
1	4.00 M	1.00 M	0.075 M	0.3 m ³
1	20.00 M	3.75 M	0.075 M	5.62 m ³
				Total = 97.32 m ³

② @ Rs. 1896.72/m³

Rs. 1,84,588.00

Add

~~Labour 12% and GST 12%~~

~~Rs. 2,39,96.00~~

~~Rs. 2,08,584.00~~

Sharan
21/11/2021
JE

Sharan
31/11/2021
AE

providing & laying NP-3, 600mm dia lime pipe in single
rows -- do -- all complete job.

$$2 \times 2.5 = 5.00 \text{ m}$$

@ Rs. 3128.85/M Rs. 15644.00

Total = 200232.00

Add 12% GST + 1% lab cost Rs. = 26030.00

A. 226262.00

Sd/-
3/11/2024
JEETU PUNJ

Sd/-
3/11/2024
AE

Sd/-
3.11.24

BEST RATE FOR A.D.K. RESTORATION UNIT With C.P. With CARRIAGE, AND WITHOUT CARRIAGE FOR RND Circle SAMASTIPUR.

A. CLEARING, GRUBBING — 59,306 = 02 / Hectare
with C.P. 10%
LABOUR — NO RATE AMOUNT
LABOUR — 150 NO — 304 = 00 — 45600.00
MATE — 6 NO — 321 = 00 — Rs 1926.00
MACHINERY, Rs 612 = 00

TRACTOR MOUNTED
WITH TROLLY — 1.0 HOUR — 612 = 00 — Rs 5776.56
OVER HEAD — 12% — Rs 5391.26
CONTRACTOR PROFIT 10%
Total — 59306 = 02

Say — 59306 = 02 / Hectare.
B. Construction of Embankment
from borrow pits, with lift
1.5M, lead 1000.0M, Table 300.1
300.2, All complete job.
Quantity — 100.0 M³.

LABOUR — 0.04 NO C 321 = 00 — Rs 12.84
MATE — 1.00 NO C 304 = 00 — Rs 304.00
MAXIMUM UNGRAVELLED — 1.00 NO C 304 = 00 — Rs 304.00
MACHINERY
HYDRAULIC EXCAVATOR — 1.67 H C 2702 = 00 — Rs 4512.00
TIPPER 5.5 cum with 10 Capacity — 4.5 H C 1183 = 00 — Rs 5323.50
Add 10% for Cost of Carriage — Rs 5322.35

Doser D 50 for spreading 100 cum — Rs 612 = 00
Water tanker 6000 Capacity — 1.0 Hour C 612 = 00 — Rs 612.00
Three wheel Roller 90 to 100 KN — 2.0 Hour C 907 = 00 — Rs 1814.00
Static roller 80 cum / Hour — 1.25 Hour — C 901 = 00 — Rs 1126.25
Rs 480 = 00

Material
Water — 12.0 K³ — 40.00 — 1
Compensation for Earth — 100.0 M³ C 34 = 82 — Rs 3482.00
Over Head Charge 12% on A+B+C+D — Rs 2380.35
Contractor Profit 10% — Rs 2221.66
Total — 24438.30

Say 24438.30 / M³
Equalling G.S., L.S.S., S.S. free.

24.8.21
24.8.21

C. Water Bound Macadam with
stone screening ... 11%

By Mechanical ...
Output - 360.3 MB.

LABOUR

Mate	0.68 NO	Rs 321=00	Rs 218=28.
Skilled Labor	2.00 NO	Rs 385=00	Rs 770=00
Unskilled Labor	15.00 NO	Rs 304=00	Rs 4560=00

MACHINERY

Tractor mounted
Grader 14.40 Hour - Rs 612=00 - Rs 8812=30

Three wheel, 80-100 KN.

Stake roller 8 MB/Hour - 45.0 Hour - Rs 901=00 - Rs 40545=0

Water Tanker 6 MB Capacity - 24.0 - Rs 907=00 - Rs 21768=0

Material

Grading 3.5 MB to 22.4 MB
0.9 MB/10 M² Compacted
Thickness of 75 MM - 435.60 MB - 503=85 - Rs 2,19,477=66

Stone screening
Type B, 11.2 MM for Grading 11

0.18 MB/10 M² - 144 KB - 40=00 - Rs 5760=00

Water
Over head charge 12% material.
Contractor profit 10% - Rs 4020=00
Rs 37612=48.

Total Rs 4,13,797=30

Say - Rs 1149 = 27/MB. Excluding carriage cost.
Carriage cost on per actual load for, less, 24 MB.
Stone material Grading 11 1.21 MB and.
Screening material 0.24 MB with lowest cost.

For riding and laying cum concrete
NP3 Hummer 600 MM dia in large row.

UMT - 7.5 Meters. 04
Labor - Mate - 0.024 - Rs 224=00 - Rs 12=84

MAXI DEOR

Mens on 1st class - 0.04 day - Rs 408=00 - Rs 16=32=0

Labor on skilled - 0.12 day - Rs 304=00 - Rs 36=48

Sand at site - 0.024 MB - Rs 1512=70 - Rs 36=3

Cement at site - 0.018 Tons - Rs 5732=62 - Rs 103=14

NP3 A.C.C Hummer with
Chlor - 7.50 Meters. - Rs 2490=24 - Rs 18676=80

Collected
...
...

Providing and Laying Unit
Concrete Pipe NPS, as per design
in single row, ... all comp.
Quantity - 7.5 metre, 600 MM dia.

Material

A. Sand at Site — $0.024 \text{ m}^3 \text{ @ } 175 = 80 / \text{m}^3 = \text{Rs } 4 = 21.$
Coarse sand.

B. Cement — $0.018 \text{ MT @ } 5266 = 20 / \text{MT} = \text{Rs } 94 = 79$

C. Hume pipe 600 MM dia - 7.5 metre - $\text{@ } 2310 = 80 / \text{metre} = \text{Rs } 17,325 = 00$

LABOUR

mate — $0.04 \text{ NO @ } 321 = 00 = \text{Rs } 12 = 80$

Menson 1st class $0.12 \text{ NO @ } 408 = 00 = \text{Rs } 48 = 96$

Mazdoor unskilled $0.96 \text{ NO @ } 304 = 00 = \text{Rs } 291 = 84.$

Total - $\text{Rs } 17,777 = 60$

Add over Head Charge 20% on a+b — $\text{Rs } 3555 = 52$

Contractor profit 10% — $\text{Rs } 21,333 = 42$

$\text{Rs } 2133 = 32$

Unit for / M 600 M.M dia H.P NPS
 $\text{Rs } 3128 = 85 / \text{metre}$ including

Carriage Cost of material, GST, L.L.C.S, Surcharge fee.

E. Providing and Laying NPS 1000.0 MM dia
Hume Pipe in single row.
Quantity — 7.5 metre.

Material

A. Sand at Site — $0.040 \text{ m}^3 \text{ @ } 175 = 80 / \text{m}^3 = \text{Rs } 7 = 03$

B. Cement at Site — $0.03 \text{ MT @ } 5266 = 20 / \text{MT} = \text{Rs } 157 = 98$

C. R.C.C NPS H.P 1000 MM
7.5 M — $7.5 \text{ M @ } 5565 = 80 / \text{metre} = \text{Rs } 41737 = 50$

LABOUR

mate — $0.09 \text{ day @ } 321 = 00 / \text{day} = \text{Rs } 28 = 29$

Menson 1st class — $0.25 \text{ day @ } 408 = 00 / \text{day} = \text{Rs } 102 = 00$

unskilled labor — $2.00 \text{ NO @ } 304 = 00 / \text{day} = \text{Rs } 608 = 00$

Total - $\text{Rs } 4264 = 50$

Add over Head Charge 20% — $\text{Rs } 8528 = 25$

Add 10% Contractor profit — $\text{Rs } 51164 = 88$

$\text{Rs } 5116 = 98$

Unit — $\text{Rs } 7504 = 98 / \text{metre}$ including

Carriage cost of materials as per my bill,
Actual land, GST, L.L.C.S, Surcharge fee.

Ch. 24.8.21

प्रमाणित
वाणीय कार्य विभाग
आदर्श संयंत्र, बलसोदी
24/8/21

F. Granular sub base, with met.
Graded material (by mix and
place method) for Grading Two
Material.

Unit - 300.0 M³ out Put

Rate ————— 0.48 M³ C 32 = 10 — Rs 154208
Skilled Labor — 2.0 NO C 385 = 00 — Rs 770 = 00
Un skilled Labor — 10.0 NO C 304 = 00 — Rs 3040 = 00

Machinery

Tractor Mounted Grader for
Grading 100 M³ / Hr — 12.0 C 612 = 00 — Rs 7349200
Three wheel Roller 80-100 KN — 30.0 C 901 = 00 — Rs 27030 = 00
Tractor with rotavator — 12.0 C 573 = 20 — Rs 6878 = 40
Water Tanker 6 K³ Capacity — 5.0 C 907 = 00 — Rs 4535 = 00

Material

26.5 MM to 9.5 MM — 35% — 134.40 C 595 = 36 — Rs 80,016 = 38
9.5 MM to 2.36 MM — 25% — 96.00 C 506 = 92 — Rs 48664 = 32
2.36 MM Below — 40% — 153.60 C 141 = 85 — Rs 21788 = 16
Water — — — 3049 C 40 = 00 — Rs 1240 = 00

over Head Charge 12% — Rs 24170 = 44

Contractor Profit 10% — Rs 22559 = 08

Hence Basic Rate / M³ — 827 = 17 / M³

Total = 2,48,49 = 86

Including Carriage, GST, L.I.C.S, Enginist fee.

(G.)

Water Bound Macadam with.

Grade II, by mechanical means

out Put — 360.0 M³

Rate — 0.68 NO C 321 = 00 / NO — Rs 218 = 28.
Skilled Labor — 2.00 NO C 385 = 00 / NO — Rs 770 = 00
Un skilled Labor — 15.00 NO C 304 = 00 / NO — Rs 4560 = 00

Machinery

Tractor Mounted Grader — 14.40 Hr C 612 = 00 / Hr — Rs 8812 = 00
Three wheel 80-100 KN Roller — 45.04 C 901 = 00 / Hr — Rs 40545 = 00
Water Tanker 6 K³ Capacity — 24.0 H C 907 = 00 / Hr — Rs 21768 = 00

Material

63 MM to 45 MM — 435.60 M³ C 473 = 70 / M³ — Rs 2,06,343.
Stone screening 11.2 MM — 96.01 M³ C 392 = 53 / M³ — Rs 3768
Binding Material — 28.80 M³ C 158 = 55 — Rs 4560 = 48
Water — 144 K³ C 40 = 00 — Rs 5760 = 00

over Head Charge — 12% — Rs 30723 = 00

10% Contractor Profit — Rs 37074 = 81

Hence Basic Rate — 1192 = 84 / M³

Total = 4,07,822 = 00

Including Carriage, GST, L.I.C.S, 10% Enginist fee

24-8-21

प्रमाणित

आधीच कारे विना

आधीच कारे विना

A. Labor for cutting 64 M to
75 M dia Bamboo Piles assuming
20.0 M pile, Sink - 1.55 M deep.
Total Sink depth — 90.50 M.

Total brick depth — 30' — Rs 102 = 00
 Labor — 0.25 No @ 408 = 00 — Rs 760 = 00
 for skilled labor — 2.50 No @ 304 = 00 — Rs 862 = 00
 Add over head charge — 12% — Rs 103 = 44
 Add Contractor profit 10% — Rs 965 = 44
 Rs 96 = 54
 Rs 1061 = 98

Spoke Rate/mile - $\frac{106.98}{30.50 \text{ M}} = R$ 34 = 81/mile.

2. Labor for fitting and finishing lumber
over on each in position with all.
Complete job. Put - 9.90 M 2

Complete 200' Put - 9.90M2

Materials
Nails 75mm to 100mm - 0.25 kg
Carpenter
unskilled labor
Add over Head Charge 12%
Total = 814 = 72
81 = 47

Add 10% C.P.

d 10% C.P
same Rate/m² — R.D. 96 = 36/m² R.D. 896 = 19
including 96%, L.S.C. 5% per

Labour for fitting long bamboo
runner with all complete set,
including, out put - 2

(624 ft to 75 MM dia), out put - 30.50M

Material
75 mm to 100 mm long nails — 0.25 NO CF 304 = 60/NO
w/ skilled labor — 0.125 NO CF 408 = 60/NO — 5 = 00
 Carpenter — Total — 142 = 40
 — 17 = 09

~~14.00~~
~~11.00~~
~~17.00~~
~~15.95~~
 Add overhauled chest 12% 1.91
 15.95

Add 10% C:np

Add 10% Comp
Share Rate / mitte — R 5 = 75 / mehr. 175 = 4
Beyung 6, 95, C. 2. 28, 2. 28, 2. 28, 2. 28

1
 4
 24.8.21
 24.8.21

Dr. Ironing - 1
 spreading, Hand packing with
 Cl Hammer in 1000 75 mm dia
 including cost of light bar
 daiger, equal Churnidog, tagu
 royalty etc all complete job.

Quantity - 2.832 MB

A. Labour unskilled - 1.50 NO @ 304 = 00 - Rs 456 = 00

B. Compaction of Irons - 0.67 NO @ 304 = 00 - Rs 203 = 68

C. Brick Bat - 2.832 MB @ 1069 = 00 - Rs 3010 = 41

D. Local Sand - 0.632 MB @ 141 = 85/MB - Rs 89 = 65

Total - 3759 = 74
 Rs 451 = 16

Add over Head charge 12%

Rs 4210 = 90
 Rs 421 = 09

Add 10% Contractor Profit

Rs 4631 = 99
 Rs 1635 = 58/MB

Item a rate / MB

Carriage of Materials

Carriage for Bricks 1 MB Brick Bat (300 NO) - Rs 232 = 99
 @ Rs 776 = 64/100

Carriage for Local Sand

Lead 300 ft: 0.22 MB @ Rs 127 = 99/MB - Rs 28 = 15

Total - Rs 1896 = 72/

E. Labour cost, including cost of material, Carriage, for Empty cement Bag Arling. Exchanging Brs, LBS, MB
 Cold Bag reusing - all complete job. Single bag fee.
 out put 100.0 NO

Labour cost

unskilled Labour -
 3000

Labour for Carrying and Reusing

C.C. Bag unskilled Labour -

Material

Local Sand - for 100 Bag

Cost of Empty cement Bag (Reused) 100 NO @ 2 = 92 -

Add over Head charge 12%

Total -

Add 10% Contractor Profit

Rs

Add Carriage Cost for Local Sand

Rs

Many Rate / Bag - 3.5 MB @ 127 = 99

Rs

Rs

Rs

Rs

Handwritten signature and stamp.

24.8.2021

Supplying of empty cement bags
 (Re used in good condition)
 of 1.2 ccf capacity with Carriage,
 Labour cost, Local sand with Consp,
 stretching of Bag, stretching and expense
 200 as per spec. for extra and deduction
 of 219.

Qty - 1,000 NO (one Hundred NO)

Un skilled Labor - 1.67 NO @ 304 = 507.68,
 for firing.
 Un skilled Labor for Carrying
 and stretching and packing - 3.0 NO @ 304 = 912.00
 Un skilled Labor for stretching - 0.33 NO @ 385 = 127.05
 Empty cement Bag (Re used) - 100 NO @ 2.92 = 292.00
 2511 Nylon for stretching - 2 NO @ 30 = 60.00
 Local sand 3.5 MB @ 141 = 496.50
 Hire Charge of Machine 0.93 Hr @ 50 = 46.50

Total - Rs 2411.70

Add over Head charge 12%

Rs 289.40

Add 10% Contractor Profit

2700.10

2700.10

Carriage Cost for Empty cement Bag @ Rs 113 = 2970.10

Carriage Cost for Local sand 3.5 MB @ 127 = 447.75

Machine Rate / Bag - Rs 34 = 29 / Bag, Total - Rs 3429.85
 excluding 5% tax, 12% S.S., 10% Profit.

for Supply of Bamboo -

As per R.M.D - Bamboo 2nd class 75MM dia -

2.1M to 3.0M Long - Rs 25 = 52.50 / NO

As per R.M.D - Bamboo 75MM dia. 6M to

8.0M Long - Rs 141.20 each
 without Carriage.

Area of 1 Bamboo for Chack - 170L

= 3.14 x 0.075 x 8.0M = 1.884

Area . Complete rate for Bamboo woven Chack

96 = 36 (Labor) + 92 = 16 Cost of Bamboo
 over head charge and Profit

Make Profit rate for

Bamboo woven Chack - Rs 188.53
 including Cost of Bamboo

Signature

Handwritten signature and text in Hindi.

24/8/21