

Inspection Report for Flood Damage Work

Date:

1. Name of PIUs – Executive Engineer, R.W.D., Works, Division, Samaratpur

2. Name of Block –

Wazirnagar

3. Name of Road/Bridge –

Basantpur Ramni one Navtol ghat to
Kamla baha L027

A. for Road

1. Damage Location/Chainage

: 0.200 km

2. Damage Length

: 0.200 km

3. Nature of Damage

4. Details of Restoration Works

i. Material being used in Restoration works: Brick Bat, Sand Bag, Bamboo

ii. Equipments/Tools being used in Restoration Works: Tractor, JCB

iii. Procedure taken up in Restoration works:

iv. Restored Length:

0.100 km

B. for Bridge

1. Damage Location/Chainage

2. Damage Length

3. Nature of Damage

4. Details of Restoration Works

i. Material being used in Restoration works:

ii. Equipments/Tools being used in Restoration Works:

iii. Procedure taken up in Restoration works:

iv. Restored Length:

Wm, har, found
Gat's factory.

25/4/22

J.E.

25/04/22

A.E.

25.4.22
Executive Engineer,
R.W.D. Works Division,
Samaratpur

Signature

(Name of Inspector)

E.B. Bala

R.M. Wm's Division


कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, समस्तीपुर


प्रतिवेदन


योजना का नाम	: बसन्तपुर रमणी में नवटोल घाट से कमला बाहा एल027 तक।
लंबाई	: 2.50 कि0मी0।
प्राक्कलित राशि	: ...11.29... लाख।
प्रखंड	: वारिसनगर।

प्रस्तुत प्राक्कलन वारिसनगर प्रखंड अन्तर्गत बसन्तपुर रमणी में नवटोल घाट से कमला बाहा एल027 तक पथ के तत्कालीन मरम्मत कार्य के लिए बनाया गया है। विगत दिनों बाढ़ के पानी के कारण उक्त पथ के पहले कि0मी0 में कटाव हो जाने के कारण यातायात बाधित हो रहा था। आवागमन सुचारु करने के लिए प्राक्कलन में बांस गड़ाई, सैन्ड बैग एवं ब्रीक्स बैट्स का प्रावधान इस प्राक्कलन में किया गया है।

प्राक्कलन वर्तमान अनुसूचित दर पर बनाया गया है जिसकी तकनीकी अनुमोदन एवं प्रशासनिक स्वीकृति अपेक्षित है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, वारिसनगर


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, वारिसनगर


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, समस्तीपुर

GENERAL ABSTRACT OF COST

Block Warisnagar
 construction length of Road
 Name of Road

District- Samastipur
 2.500 KM
 Basantpur ramani me navtol ghat to kamla baha

Sr.no	Item of work	Amount
A	Total cost of Construction	1084750.1
	Add GST@12%	126570.01
	Add labour Cess@1%	10547.501
	Total Project Cost(A)	1191867.6

[Signature]
 27/10/21
 Junior Engineer

[Signature]
 27/10/21
 Assistant Engineer

[Signature]
 Executive Engineer

Sanctioned
For 11,91,868 = 12 Lakhs Given
Lower Ministry one thousand Eight Hundred Sixty Eight
only including C.P and O.H.C.

[Signature]
 24/12/21
 वरिष्ठ निरीक्षक
 राष्ट्रीय राजमार्ग विभाग
 नई दिल्ली, भारत
 24/12/21
 T.A

**Details Estimate of FDR from Basantpur ramani me navtol ghat
to kamla baha L027 road for year 2021-22**

Item.No.	Item of work	Unit	rate	Qty	Amount
1	supplying & Filling Bricks Bat & compacting Manually by CI hammer including all Complete Job				
		cum	1896.72	403.425	724841.8
2	Supply of empty cement bag with carriage ,labour cost, local sand with stitching				
		No	34.29	9360	320954.4
3	Supply of bamboo 2nd class 75mm dia.. 2.1m to 3.0 m long				
		No	25	127	3175
4	labour for cutting 60 mm to 75 mm dia Bamboo... piling				
		meter	34.81	123.00	4281.63
5	labour for fitting fixing bamboo..with all complete job				
		meter	5.75	260.40	1497.3
				Total	1054750

for 27/10/21
JK

Chamunda
27/10/21
A.E.

**Details measurement FDR from Basantpur ramani me
navtol ghat to kamla baha L027 road for year 2021-22**

item.No.	Item of work
----------	--------------

- 1 supplying & Filling Bricks Bat & compacting Manually by CI hammer including all Complete Job

CH-1.200-1.300 KM

No	length	width	thickness	Qty
1	15.000	3.200	2.500	120.000
1	15.000	4.650	2.500	174.375
1	12.000	3.125	2.500	93.750
3	1.200	3.75	0.600	8.100
1	4.000	3	0.600	7.200
Total Qty				403.425 cum

2	Supply of empty cement bag with carriage, labour cost, local sand with stitching
---	--

9	8	130	9360	No
---	---	-----	------	----

3	Supply of bamboo 2nd class 75mm dia..2.1mto 3.0 m long
---	--

		127		127	No
--	--	-----	--	-----	----

4	labour for fitting fixing bamboo .. Runner.....with all complete job
---	--

NO	Length	Qty
6	42.00	252.00
14	0.60	8.40
Total Qty		260.40 mtr

5	labour for fitting fixing bamboo Piling....with all complete job
---	--

NO	Length	Qty
41	3.00	123.00 mtr

R Rsh 27/10/21
JC

Chamlingas
27/10/21
A.E

Opd
27/10/21