

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, समस्तीपुर

प्रतिवेदन

योजना का नाम	: कुशैया पारसनाथ ठाकुर के घर से मोईन पोखर
लंबाई	: गोलक सदा के घर होते हुए विषहर स्थान तक।
क्षतिग्रस्त लंबाई	: 1.060 कि०मी०।
प्राक्कलित राशि	: 0.150 कि०मी०
प्रखंड	: 5.66 लाख।
	: वारिसनगर।

प्रस्तुत प्राक्कलन वारिसनगर प्रखंड अन्तर्गत कुशैया पारसनाथ ठाकुर के घर से मोईन पोखर गोलक सदा के घर होते हुए विषहर स्थान तक पथ के तत्कालीन मरम्मत कार्य के लिए बनाया गया है। विगत दिनों अत्यधिक बाढ़ के पानी के कारण पथ में पी.सी.सी. के नीचे कटाव हो जाने के कारण यातायात बाधित हो रहा था। आवागमन सुचारु रूप से करने के लिए प्राक्कलन में ब्रीक्स बैट्स का प्रावधान इस प्राक्कलन में किया गया है। यह पथ पंचवर्षीय अनुरक्षण अवधि के अधीन है।

प्राक्कलन वर्तमान अनुसूचित दर पर बनाया गया है जिसकी तकनीकी अनुमोदन एवं प्रशासनिक स्वीकृति अपेक्षित है।

Rsh
6/11/21

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, वारिसनगर

Chinn
6/11/21

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, वारिसनगर

Chinn
6/11/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, समस्तीपुर

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, बलिया

पत्रांक 01, ~~कैम्य सगरमिड~~ दिनांक 15/12/21

प्रेषक:- कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बलिया।

सेवा में,
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, समस्तीपुर।

विषय:- FDR योजना के जाँच के संबंध में।


प्रसंग:- आपका पत्रांक 2292 दिनांक 23.11.21
महाशय,

उपर्युक्त विषयक प्रासंगिक पत्र के संबंध में कहना है कि निम्नलिखित योजनाओं की जाँचोपरान्त प्राक्कलन सहित लौटायी जाती है।

क्र०	योजना का नाम	प्रखंड	पथा की लंबाई (कि०मी० में)	प्राक्कलित राशि (लाख में)	अभ्युक्ति
1	पूसा बाजार में राज स्टुडियो के निकट से हाथी चौक पप्पु चौधरी के दुकान तक	पूसा	0.500	2.260	
2	गढ़िया चौक से घोबगामा सीमा	पूसा	3.520	14.810	
3	पूसा बाजार बोस कम्पनी चौक से दुबहा भाया भुसकौल चौक	पूसा	5.900	4.050	
4	हरपुर पीच रोड से जगदीशपुर भाया नावाचक नारायणपुर	पूसा	4.570	9.840	
5	दिधरा पंचायत विशनपुर मोड़ संजय पासवान के घर से कृषि वि० केन्द्र बिरौली	पूसा	3.000	10.120	
6	वैनी टेलीफोन एक्सचेंज से पी०डब्लू०डी रोड आयरन फैक्ट्री होते हुए चन्दौली	पूसा	6.570	9.650	
7	पी०डब्लू०डी. मोतीपुर चौक से दाउदपुर पैक्स भाया भैरोखरा इमली चौक	समस्तीपुर	3.000	3.923	
8	लक्खी चौक से रसलपुर भाया केवस मंदिर	समस्तीपुर	3.000	1.006	
9	टी०१ से जितवारपुर	समस्तीपुर	1.000	2.240	
10	रामकृष्णपुर आर०ई०ओ० से किशनपुर आर०ई०ओ० तक	समस्तीपुर	1.600	2.820	
11	आधारपुर से विक्रमपुर बान्दे	समस्तीपुर	5.680	1.120	
12	धुरलख मिडिल स्कूल से एन०एच० मोहनपुर	समस्तीपुर	1.200	7.040	
13	हरपुर एलाय स साह जी टोला	समस्तीपुर	1.050	0.669	
14	एल०४८ से एल०एच० धुरलख	समस्तीपुर	1.560	1.319	
15	एल०६३ एस०एच० से नीरपुर	समस्तीपुर	2.897	0.250	
16	एस०एच० टी०४ से नरकअब्दुलगनी	समस्तीपुर	1.200	1.390	

17	कुशीया पारसनाथ ठाकुर के घर से मोईन पोखर गोलक सदा के घर होते हुए बिहार स्थान	वारिसनगर	1.060	5.660	
18	एल081 चकमित्की से हजपुरवा	वारिसनगर	3.200	3.050	
19	नकटा वारिसनगर से बत्तीपुर	वारिसनगर	7.500	7.140	
20	बसंतपुर रमणी में नकटोल घाट से कमला बाहा एल027	वारिसनगर	2.500	11.910	
21	इलमासनगर से किशनपुर रेलवे स्टेशन	वारिसनगर	5.000	1.890	
22	भुट्टा राजत चौक बताही से मोहिउद्दीनपुर भाया तारी टोला	वारिसनगर	3.660	5.080	
23	टी02 परोडिया से मोहिउद्दीनपुर	वारिसनगर	6.100	1.350	
24	प्यारेला महतो के घर से शंकर चौक	वारिसनगर	2.430	7.410	
25	लभट्टा चौक से महादलित टोला	वारिसनगर	0.970	1.410	
26	एस0एच0 से नरगा	कल्याणपुर	2.636	2.579	
27	कुशियारी चौक से परना डोरी पथ	कल्याणपुर	4.100	6.449	
28	कल्याणपुर चौक से मधुबन किशनपुर	कल्याणपुर	4.100	3.607	
29	लदौरा से चकमहेशी गंगौरा	कल्याणपुर	17.060	7.604	
30	खानपुर पी0सी0सी0 रोड से सिमरी चन्द्रसेन पथ	खानपुर	3.300	3.066	
31	बरगौंव चौक से शोभन घाट	खानपुर	2.600	5.339	
32	खैरी से खैराज पथ	खानपुर	5.450	14.094	
33	खानपुर से मननपुर तक भाया शादीपुर	खानपुर	7.100	7.976	
34	बच चौक से बच घाट पार्ट-1	ताजपुर	0.200	0.890	
35	टी01 सरवरगंज से नून नदी पुल	ताजपुर	0.625	1.467	
36	टी01 से मथुरापुर पार्ट-1	ताजपुर	1.100	1.978	
37	गंज पुल से बाघी	ताजपुर	3.334	2.260	
38	कन्सट्रक्शन रोड जोगिया मठ प्राथमिक विद्यालय पी डबल्यू डी पथ के निकट से एन0एच0-28 तक जाने वाली पथ	ताजपुर	1.200	7.500	
39	एन0एच0-28 से मोतीपुर	ताजपुर	0.600	1.010	
40	एन0एच0-28 पेट्रोल पंप से शंकर सीनेमा	ताजपुर	0.500	1.560	
41	एस0एच0 49 खरहा चौक से मीना रानी	ताजपुर	0.900	0.860	
42	एन0एच0-28 गाँधी चौक से नीम चौक	ताजपुर	0.500	1.470	
43	एन0एच0-28 से शंकर सीनेमा	ताजपुर	0.200	1.720	

अनु0-यथोक्त ।

विश्वासभाजन

 कार्यपालक अभियंता
 ग्रामीण कार्य विभाग
 कार्य प्रमंडल, समस्तीपुर

GENERAL ABSTRACT OF COST

Block Warisnagar
construction length of Road
Name of Road

District- Samastipur
1.06 KM
Kusaiya parasnath thakur ke ghar se moin pokhar
,golakh sada ke ghar hote hue bishar sthan tak

Sr.no	Item of work	Amount
A	Total cost of Construction	501428.3
	Add GST@12%	60171.39
	Add labour Cess@1%	5014.283
	Total Project Cost(A)	566614

[Signature]
6/11/21
junior Engineer

[Signature]
6/11/21
Assistant Engineer

[Signature]
6/11/21
Executive Engineer

Pranismanoj & chun' cany Sanetimed 1 for Rs 5,66,614:00 can for the
Laksh, Sathy Sra Hanan and Sra Han d'vial four four may
in'c'ing C.P and O.H.C.

[Signature]
24/12/21
T.A.

Details Estimate of FDR from Kusaiya paras nath thakur ke ghar se
moinpokhar golakh sda ke ghar hote hue bistar asthan tak road for year 2021-22

item.No.	Item of work	Unit	rate	Qty	Amount
1	supplying & Filling Bricks Bat & compacting Manually by CI hammer Including all Complete Job				
	As per calculation sheet	cum	1896.72	264.366	501428.3
				Total	501428.3

Rs. 5/11/21
JE

Chandra
6/11/21
A.E.

Details measurement FDR from kusaiya parasnath thakur ke ghar se moin pokhar, golak sada ke ghar hote hue bishar asthan hote hue

item.No.	Item of work					
1	supplying & Filling Bricks Bat & compacting Manually by CI hammer Including all Complete Job					
	No	length	width	thickness	Qty	
Under road crust	1	30.00	1.50	0.35	15.75	
Under road crust	1	23.00	1.80	0.30	12.42	
Under road crust	1	9.50	2.40	0.45	10.26	
Under road crust	1	30.00	1.80	0.45	24.30	
Under road crust	1	30.00	1.50	0.45	20.25	
Under road crust	1	15.00	1.20	0.30	5.40	
Under road crust	1	30.00	2.40	0.45	32.40	
Flank pond side	1	30.00	2.80	0.30	19.32	
Flank pond side	1	23.00	2.80	0.35	7.98	
Flank pond side	1	9.50	2.40	0.30	25.20	
Flank pond side	1	30.00	2.80	0.45	33.75	
Flank pond side	1	30.00	2.50	0.30	9.90	
Flank pond side	1	15.00	2.20	0.60	6.48	
Flank pond side	1	9.00	1.20	0.60	2.43	
Flank pond side	1	4.50	0.90	0.60	6.48	
Flank pond side	1	12.00	0.90	0.75	20.25	
Flank pond side	1	30.00	0.90	0.60	3.78	
Flank pond side	1	7.00	0.90	0.60	2.70	
Flank pond side	1	5.00	0.90	0.60	2.51	
Near Culvert	1	3.80	2.20	0.20	1.08	
	1	3.00	1.80	0.60	1.73	
Flank pond side	1	2.40	1.20			
Total Qty					264.37	

Rsh 6/11/21

(Signature)
6/11/21

With C.P. With CARRIAGE, AND WITHOUT CARRIAGE FOR RND Circle SAMASTIPUR.

A. CLEARING, GRUBBING - 59,306 = 02/Hec. 100

<u>LABOUR</u> NO	<u>RATE</u>	with C.P 10%
<u>LABOUR</u> — 150 NO —	304 = 00	<u>AMOUNT</u>
MATE — 6 NO —	321 = 00	45600.00
MACHINERY.		Rb 19200

TRACTOR MOUNTED
WITH TROLLY - 1.0 HOUR - 612.00
OVER HGA - 12 %
CONTRACTOR PROFIT 10 %

Say - 59306 = 02 / Hectare.
 amount including GST, 10% tax, 10% fee.

B. Construction of Embankment from borrow pits, with width 1.5M, 1 end 100.0M, Table 300.1

300.2, All Complete 2012.

Quartzly. $\leftarrow$ 100.0 MB.

LABOUR
Mgt. — 0.04 No. 321 = 00 — Rs 12.84
— 0.04 No. 804 = 00 — Rs 309.00

Maxdars ungkutil - 1.00 NO C 304 = 20 — B 45/25

MACHTIGARX

Hydraulic Excavator - 1.67 H.C. 1102-10 - R₀ 5323-50

Tipper 5.5 km with 10. 4.5H C 1183 = 00 - 10

Capacity 24
Add 10% for Cost of Carriage

Doser 7.99 for 3 spreading 100 cm
1.0 other c 612:00 R 612:00
R 1819:00

Water tanker B.O.K's Capacity - 2.0 M³ @ 907.00 Rs 1814.00

Three whl. R. 120's go to 1st whl.
Static rolling @ 80 km/h. 1.25 hr - @ 901:00 R. 120's
R. Green

Material 100 kg — £70.00

$\frac{1791-80}{\text{water}} = 12.0 \text{ kg} - 670.00$

Companion to Earth $\rightarrow M_3$ 100.0M' 57-82
A $\rightarrow R_2$ 23.8-93

Over Head Charge 12% on A+B+C+D _____ Rs 222.66

Contractor profit 10% 24438.30
Total 24438.30

Eq. 44 chg Soy 244 = 38 / 113.
Gst, L-side, Signon fee.

14 Mar
29-8-21
बौद्धिक बलिदान
आर्थिक कार्य विज्ञान
आर्थिक संघ, प्रबन्धकीर्ण

AC
24.8.21

C. Water Bound Macadam with
stone screening Type B, Grade III
... an complete job.

By Mechanical Means
out put - 360.0 MB.

LABOUR
Mate - 0.68 NO - C 321=00 - Rs 218=28.
Skilled Labors - 2.00 NO - C 385=00 - Rs 770=00
Unskilled Labors - 15.00 NO - C 304=00 - Rs 4560=00
MACHINERY
Tractor Mounted Grader 14.40 Hrs - C 612=00 - Rs 8812=30

Three wheels, 80-100 KN.
Stone roller C 8 MB/Hrs - 45.0 Hrs - C 901=00 - Rs 40545=00
Water Tanker 615 Capacity - 24.0 - C 907=00 - Rs 21768=00

Material
Grading 9.53 MM to 22.4 MM
C 0.91 MB/10 M² Compacted
Thickness of 75 MM - 435.60 MB - 503=85 - Rs 219477=06
Stone screening
Type B, 11.2 MM for Grading III - 86.40 MB - 392=53 - Rs 33919=59
C 0.18 MB/10 M²
Water 144 KG - 40=00 - Rs 5760=00
Over Head Charge 12% material. Rs 40297=69
Con tractor Profit 10% Rs 37612=48.
Total Rs 4,13,737=30

Say - Rs 1149=27/MB. Excluding Carriage Cost.
Carriage Cost on per Actual load for 1.21 MB and.
Stone material Grading III 1.21 MB and.
Screening material 0.24 MB with 10% loss.
Providing and Laying Cement Concrete
NP3 Humc pipe 600 MM dia large row.
UMT - 7.5 Meters. 0.04 day - C 408=00 - Rs 16=32-0
Labour - Mate - 0.024 day - C 304=00 - Rs 36=48
Mens 1st class - 0.04 day - C 408=00 - Rs 16=32-0
Labour unskilled - 0.12 day - C 304=00 - Rs 36=48
Sand at site - 0.024 MB - C 1512=70 - Rs 36=32-0
Cement at site - 0.018 Tons - C 5732=62 - Rs 103=11-0
NP3 x.c.c Humc pipe with
Chills 7.50 Meters. C 2490=24 - Rs 18676=80

By Mr. N. S. Srinivasan
Sd/-
N. S. Srinivasan
Sd/-
N. S. Srinivasan

Providing and Laying Unit
Concrete Pipe NP3, as per design
in single row, ... all comp.
Quantity - 7.5 metre, 600MM dia.

Material

- A. Sand at Site — $0.04 \text{ m}^3 \text{ @ } 175 = 80/\text{m}^3 - \text{Rs}$
 B. Cement — $0.018 \text{ MT @ } 5266 = 20/\text{MT} - \text{Rs } 94 = 79$
 C. Hume pipe 600MM dia - 7.5 metre - $\text{Rs } 2310 = 60/\text{metre} - \text{Rs } 17,335 = 60$

LABOUR

- Mate — $0.04 \text{ NO @ } 321 = 00 - \text{Rs } 12 = 20$
 Mason 1st class $0.12 \text{ NO @ } 408 = 00 - \text{Rs } 48 = 96$
 Mazdoor unskilled $0.96 \text{ NO @ } 304 = 00 - \text{Rs } 291 = 84$

Add over Head Charge 20% mat + b

Contractor profit 10%

Total - Rs
 $17,777 = 20$
 $\text{Rs } 3555 = 52$
 $\text{Rs } 21,393 = 42$
 $\text{Rs } 2133 = 37$
 $\text{Rs } 23466 = 49$

Unit for / M 600MM dia H.P NP3

Rs. 3128 = 85/metre Ex clud 9.

Carriage Cost of material, GST, L.I.C.S, Surcharge for

E. Providing and Laying NP3 1000MM dia
 Hume Pipe in single row.
 Quantity — 7.5 metre.

Material

- A. Sand at Site — $0.04 \text{ m}^3 \text{ @ } 175 = 80/\text{m}^3 - \text{Rs}$
 B. Cement at Site — $0.03 \text{ MT @ } 5266 = 20/\text{MT} - \text{Rs } 157 = 98$
 C. R.C.C NP3 H.P 1000MM dia — $7.5 \text{ M @ } 5565 = 60/\text{metre} - \text{Rs } 41737 = 60$

LABOUR

- Mate — $0.09 \text{ day @ } 321 = 00/\text{day} - \text{Rs } 28 = 29$
 Mason 1st class — $0.25 \text{ day @ } 408 = 00/\text{day} - \text{Rs } 102 = 00$
 Unskilled Labor — $2.00 \text{ NO @ } 304 = 00/\text{day} - \text{Rs } 608 = 00$

Add over Head Charge 20%

Add 10% Contractor profit

Total - Rs
 $4264 = 50$
 $\text{Rs } 8538 = 24$
 $\text{Rs } 51164 = 69$
 $\text{Rs } 5116 = 98$

Self - Rs 7504 = 88/metre Ex clud - Rs 56286 = 58.
 Carriage cost of materials at 16 row 20;
 Actual land, GST, L.I.C.S, Surcharge for.

अथर्व
 अथर्व
 अथर्व
 अथर्व
 अथर्व

F. Granular sub base, with well graded natural clay mix and place method for grading two materials.

Unit - 300.0 M³ out put

Material
 Mate — 0.48 M³ @ 321 = 154.88
 Skilled labor — 2.0 NO @ 385 = 770.00
 Unskilled labor — 10.0 NO @ 304 = 3040.00

Machinery

Tractor mounted Grader for grading 120 M³/hr — 12.0 @ 612 = 7344.00
 Three wheel mixer 80-100 M³/hr — 30.0 @ 901 = 27030.00
 Tractor with rotavator — 12.0 @ 573 = 6876.00
 Water tanker 6 K³ Capacity — 5.0 @ 907 = 4535.00

Material

26.5 MM to 9.5 MM — 35% — 134.40 @ 595 = 80,016.00
 9.5 MM to 2.36 MM — 25% — 96.00 @ 586 = 56,256.00
 2.36 MM Below — 40% — 153.60 @ 141 = 21,657.60

Water

Over Head Charge 12%

Contractor Profit 10%

Hence Basic Rate / M³ — 827.17 / M³

Leaving 6% Contingency, 1% L.S., 1% S.G. for

(G.)

Water Bound Macadam WBM.

Grade II, by mechanical means

out put — 360.0 M³

Material
 Mate — 0.68 NO @ 321 = 218.28
 Skilled labor — 2.00 NO @ 385 = 770.00
 Unskilled labor — 15.00 NO @ 304 = 4560.00

Machinery

Tractor mounted Grader — 14.40 Hrs @ 612 = 8812.80
 Three wheel 80-100 KN static roller — 45.0 H @ 901 = 40545.00
 Water tanker 6 K³ Capacity — 24.0 H @ 907 = 21768.00

Material

13 MM to 4.75 MM — 435.60 M³ @ 473 = 2,06,343.00
 Stone screening Type B 11.24 M³ — 96.01 M³ @ 392 = 37,686.00
 Binding material — 28.80 M³ @ 158 = 4560.00

Water

Over Head Charge 12%

10% Contractor Profit

Hence Basic Rate — 1132.84 / M³

Leaving 6% Contingency, 1% L.S., 1% S.G. for

44-8-21

संयोजक अधिकारी
 आजीव कार्य विभाग
 आजीव कार्य, अहमदाबाद

A. Labour for cutting bamboo
 75MM dia Bamboo Piles assuming
 20.0M pile, 5m x 1.525m dia.
 Total 5m x depth — 30.50M.

Labour
 Carpenter — 0.25 hr @ 408/- = Rs 102/-
 4 unskilled labour — 2.50 hr @ 304/- = Rs 760/-
 for 5m x dia
 Add over head charge — 12%
 Add Contractor Profit 10%
 Rate/m — $\frac{1061.98}{30.50M} = Rs 34 = 81/m$
 Rs 102 = 11
 Rs 760 = 10
 Rs 862 = 10
 Rs 103 = 11
 Rs 965 = 11
 Rs 96 = 51
 Rs 1061 = 98

B. Labour for fitting and fixing bamboo
 woven chairs in position with all
 complete job.

Materials
 Nails 75MM to 100MM lg — 0.25 kg @ 61 = 74/m² — Rs 15 = 43
 Carpenter
 unskilled labour — 1 hr @ 408 = 10/10 — Rs 408 = 10
 1 hr @ 304 = 10/10 — Rs 304 = 10
 Add over head charge — 12%
 Add 10% C.P.
 Rate/m² — Rs 96 = 96/m² — Rs 896 = 19
 Rs 727 = 19
 Rs 87 = 29
 Total = 814 = 72
 81 = 17

C. Labour for fitting and fixing bamboo
 woven chairs with all complete job,
 (62MM to 75MM dia), out put — 30.50M

Material
 75MM to 100MM long nails — 0.25 kg @ 61 = 74/m² — 15 = 43
 unskilled labour — 0.25 hr @ 304 = 10/10 — 76 = 10
 Carpenter — 0.125 hr @ 408 = 10/10 — 51 = 10
 Rate/m² — Rs 17 = 09
 Add over head charge 12%
 Add 10% C.P.
 Rate/m² — Rs 19 = 95
 Rs 5 = 75/m² — 175 = 47
 Rs 175 = 47

Signature

प्रमाणित कार्य विभाग
 आर. ए. मंडल, मयपुरी

24.8.71

Spreading, Hand filling with
Cl Hammer in layers 75mm thick
including cost of light barriers
dagger, equal thickness layers
royalty etc all complete job.
Quantity - 2.832 MB

A. Labour unskilled - 1.50 NO	C 304 = 00	-	Rs 456 = 00
B. Compaction of bricks - 0.67 NO	C 304 = 00		Rs 203 = 68
unskilled labor - 0.67 NO	C 1069 = 00		Rs 3018 = 41
C. Brick sat - 2.832 MB	C 141 = 85	/MB	- Rs 89 = 65
D. Local sand - 0.632 MB	C 141 = 85	/MB	- Rs 89 = 65
Total -			3759 = 74
Add over Head charge 12%			Rs 451 = 16
Add 10% Contractor Profit			Rs 4210 = 90
			Rs 421 = 09
			Rs 4631 = 99
			Rs 1635 = 58/MB

Hence rate / MB	
Carriage of Materials	
Carriage for Bricks 1 MB Brick sat (300 NO)	Rs. 232 = 99
Carriage for Local sand	Rs 776 = 64/MB
Local sand: 0.22 MB	C Rs 127 = 99/MB
	Rs 28 = 15
Total -	Rs 1896 = 72/MB

E. Labour cost, including cost of Material, Carriage, for Empty cement Bag Arising. Exchanging 65, 65, 55, MB
Cost of Bag released - all complete job. Singuon fee.
out put 100.0 NO

Labour cost	
unskilled labor	
sat 11	
labor for carrying and running	
C.C. Bag	
unskilled labor	

Handwritten signature and date: 24.8.2021

Material	
Local sand - for 100 Bag	
Cost of Empty cement Bag (Released)	100 NO C 2292 =
Add over Head charge 12%	Total -
Add 10% Contractor Profit	Rs
Add Carriage cost for Local sand	Rs
3.5 MB	C 127 = 99
Menu Rate / Bag	Rs

of 219.
Aug - 1,000 NO (one thousand NO)

Un skilled labor for carrying
and stacking and packing - 3.0111

Empty cement Bag (2 used) - 100 NO 22-02/10- B 242
 1400 per Shching - 2 NO 22-02/10- B 60
 1400 per Shching - 2 NO 22-02/10- B 446

Local sand 8.5 M - 0.30 m 2.50 m - R₀ 16.5
 Stirring charge of machine - 0.30 m 2.50 m - R₀ 16.5
 Total - R₀ 24.11 = "

Add over Head Charge 12%

2. 2070 = 11

Spice Rate / bag — Rs 34 = 29/bag. Total — Rs 3429 = 118

Asfr R.m.D - Bamboo 2nd class 75 mmdia -
in the Bon Long - R 2500/150

8.0M Loss 9 — Rs 1415.00 each
w/ half Canvass.

$$= 3.14 \times 0.075 \times 8.017 = 1.989$$

— $96 = 36 (\text{Labor}) + 92 = 16 \text{ Cst of Bank}$

1907
100-18

4/10/1944
H. C. [unclear] [unclear]
[unclear] [unclear] [unclear]

Inspection Report for Flood Damage Work

Date:

1. Name of PIUs - Executive Engineer, R.W.D. Works Division, Samastipur

2. Name of Block -

Wazirnagar

3. Name of Road/Bridge -

A. for Road

Kusaiya Parasnath Thakur ka ghar to
Moin Pokhar golak sada ka ghar
hote hue bishon Aethon.

1. Damage Location/Chainage

AT CH - 0.450 km

2. Damage Length

0.100 km

3. Nature of Damage

4. Details of Restoration Works

i. Material being used in Restoration works: Brick Ballt, sand

ii. Equipments/Tools being used in Restoration Works: Tractor, JCB

iii. Procedure taken up in Restoration works:

iv. Restored Length:

0.100 km

B. for Bridge

1. Damage Location/Chainage

2. Damage Length

3. Nature of Damage

4. Details of Restoration Works

i. Material being used in Restoration works:

ii. Equipments/Tools being used in Restoration Works:

iii. Procedure taken up in Restoration works:

iv. Restored Length:

Wm have found Sark's factory

Roh
25/4/22

J.E.

M
25/04/22

A.E.

Executive Engineer,
R.W.D. Works Division,
Samastipur

Wad
20/4/22

Signature

(Name of Inspector)

E. C. Ban'a

Rd mngs assty