

BIHAR RURAL ROADS PROJECT
Bihar Rural Road Development Agency (BRRDA)
Govt. of Bihar

**EMERGENT REPAIR OF ROAD FROM GHOSWARI
KARRA PMGSY ROAD To KANYA VIDYALAYA
PAIJNA UNDER FDR**



Name of the Road :-

**EMERGENT REPAIR OF ROAD FROM GHOSWARI KARRA PMGSY ROAD To KANYA VIDYALAYA
PAIJNA UNDER FDR**

DISTRICT	:	Patna	
DIVISION	:	Barh	
BLOCK	:	GHOSWARI	
Total length of Road		1.100	Km
Damaged length of Road		60.00	m
TOTAL COST OF CONSTRUCTION	:	10.334	Lacs
TOTAL COST OF PROJECT	:	10.334	Lacs

Executive Engineer

Rural Works Division,

BARH

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :	EMERGENT REPAIR OF ROAD FROM GHOSWARI KARRA PMGSY ROAD To KANYA VIDYALAYA PAIJNA UNDER FDR	
DISTRICT	PATNA	
BLOCK	GHOSWARI	
DIVISION	BARH	
Total length of Road	1.100KM	
Damaged length of Road	60.00M	
SL No.	DESCRIPTION	AMOUNT (LAKHS)
1	COST OF ITEM	885821.00 ₹ 1,033,348.50
	TOTAL COST IN LACS =	10.334 8.858

By Kumar
30/10/21
JE
RWD

AE
RWD

20/10/21
EE
RWD

Technically sanctioned for Rs. 8.858 lac. ~~Eight lakh.~~
~~Eighty five thousand and eight hundred only,~~
~~including five year Maintenance Cost~~

sd *sd*
तकनीकी सलाहकार Superintending Engineer
ग्रामीण कार्य विभाग R.W.D. WORKS CIRCLE, PATNA
कार्य अंचल, पटना

Certified and
Approved
16/12/2021
Superintending Engineer
R.W.D. WORKS CIRCLE, PATNA
15/11/21

प्रतिवेदन

कार्य का नाम :

घोसवरी- कर्र पी०एम०जी०एस०वाई० पथ से कन्या विद्यालय
पैज्ना पथ का बाढ़ क्षतिग्रस्त पथांश का आपातकालीन मरम्मत ।

क्षतिग्रस्त पथांश की लम्बाई :

60.00 मी०

प्राक्कलित राशि :

रू० 10.334 लाख

मद :

एफ० डी० आर०

प्रस्तुत प्राक्कलन घोसवरी प्रखण्ड अंतर्गत घोसवरी- कर्र पी०एम०जी०एस०वाई० पथ से कन्या विद्यालय पैज्ना पथ का बाढ़ क्षतिग्रस्त पथांश का आपातकालीन मरम्मत का एकरारनामित दर पर रू० 10.334 लाख (दस लाख तैंतीस हजार चार सौ) रूपये मात्र का तैयार किया गया है । इस वर्ष के भीषण बाढ़ से पथ तीन स्थानों पर **Wash out** हो गया है । विभागीय निदेशानुसार पथ को यातायात योग्य बनाना है, जिसके लिए पूर्व से ही संवेदक चयनित है । पथ के कटे भाग में ब्रीक्त् वैट भर दिया गया है । आवागमन चालू है । अतः कार्यहित में प्राक्कलन की स्वीकृति अपेक्षित है ।

Bkumar
30/10/24

कनीय अभियंता
घोसवरी

सहायक अभियंता
घोसवरी

30/10/24
कार्यपालक अभियंता
(ग्रामीण कार्य विभाग)
कार्य प्रमंडल, बाढ़

पुनर्वचः काम की जांच अंशतः द्वारा निष्पत्ति
अंशतः काम प्रमंडल द्वारा करा ली गई है
जांच प्रतिवेदन संलग्न है

RWD, Works Division, Barh

Flood Damaged Road List of Barh (With Google Sheet)

Sl. No	Name of Block	Name of Road	Damage Location and Size	Status of Restoration			Traffic Status	Remarks
				Work Completed	Work in Progress	Work Yet To Be Started		
1	Belchhi	Korari to Paighamberpur	0.750 Km To 0.760 Km (10 M)	Work Completed			Traffic is smooth	Required one H/P Culvert, Traffic restored
2	Pandarak	L049-T02 to Shahzadpur Bathoi	1st Time-0.950 Km To 0.970 & 2.200 Km to 2.210 (30 M), 2nd Time-0.850 Km To 0.885 Km (35)	Work Completed			Traffic is smooth	Required 1x6 M and 1x3 M RCC Culvert, Traffic restored, 2nd Time-35 M Traffic Restore.
3	Ghoswari	Ghoswari Karra PMGSY Road to Kanya Vidalya pajina	0.550 Km To 0.675 Km (125 M)	Work Completed			Traffic is smooth	1x3 M New RCC Culvert is require in place of damage hurne pipe culvert constructed by Panchayat. Flood Water Logged. Traffic is Smooth.
4	Barh	NH-30A (Saksohra Barh Road) to Brahmini Asthan	0.350 Km To 0.500 Km (150 M)			Work Yet To Be Started	Traffic is not smooth	Flood/Rain Water Log In 200 M Length. Require RCC Culvert (1 X 6 X 4 M). Traffic is not smooth
5	Ghoswari	MRL11-NH 82 to NH 31 Via Gosai gaon.	1.600 Km To 1.900 Km (300 M)	Work Completed			Traffic is smooth	No any damage. Traffic is smooth.
6	Mokama	MRL07-More to Tartar	2.000 Km To 6.00 Km, 6.500 Km To 6.520 Km (4020 M)	Work Completed			Traffic is smooth	Old weir damage and 1x25 M H/L Bridge required. 4.00 Km Flank damage.

F6

NAME OF ROAD **EMERGENT REPAIR OF ROAD FROM GHOSWARI KARRA PMGSY ROAD TO KANYA**
VIDYALAYA PAIJNA UNDER FDR

SL No.	SDB SL NO	MORD ReLNo	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1			Supplying Brick bats with carriages at site including labour cess, GST and seigniorage fee (excluding over head and CP).								
				Cum					435.857		758827.00
									508.50	1,741.00	885298.50
2			Supplying Unskilled Labour for Brick bats for spreading compacting and leveling including labour cess, GST and (excluding over head and CP).								
				nos.					386.10		126594.10
									450.00	329.00	148050.00
									TOTAL	Rs	14933348.50

885821.10
= 8.858 lac

Sumit
30/10/21
JE (RWD)

AE (RWD)

30/10/21
EE (RWD)
WORK DIVISION
Barh

अधीक्षण अभियंता का कार्यालय,
ग्रामीण कार्य विभाग, कार्य अंचल, पटना।

पत्रांक-
प्रेषक,

851 (3-30)

/पटना, दिनांक-21/06/2021

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, पटना

सेवामें,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बाढ़।

विषय:- **Very Short Notice No. RWD/FDR/Patna /01(2021-22)** के तहत आमंत्रित कोटेशन
अंतर्गत कार्य प्रमंडल, बाढ़ में न्यूनतम दर दाता के साथ एकरारनामा करने के संबंध में।

महाराज,

उपर्युक्त विषय के संबंध में कहना है कि कोटेशन के माध्यम से प्राप्त आमंत्रित निविदा में तकनीकी विवरणी एवं वित्तीय विवरणी में सफल एवं न्यूनतम दर दाता **M/S Sundar Nirman** घोषित किए गए हैं। इनके द्वारा उद्धृत न्यूनतम दर इस पत्र के साथ संलग्न कर भेजी जा रही है। यदि दरों में कोई त्रुटि दृष्टिगोचर हो तो अविलंब उसका निराकरण करा लिया जाये।

अतः आपको निदेश दिया जाता है, कि उक्त संवेदक से 03 (तीन) दिनों के अंदर एकरारनामा करते हुए उसकी सूचना अधोहस्ताक्षरी के कार्यालय में समर्पित करना सुनिश्चित करें साथ ही साथ अन्य संवेदक अगर इसी न्यूनतम दर पर कार्य करने हेतु ईच्छुक हो तो उन्हें भी सूचीबद्ध कर ली जाये, ताकि भविष्य में आवश्यकता पड़ने पर उनसे काम लिया जा सके।

संबंधित संवेदक का प्राप्त अग्रधन की राशि पत्र के साथ संलग्न की जा रही है।
अनु0-यथोक्त।

विश्वासभाजन

[Signature]
21/6/21

अधीक्षण अभियंता
ग्रामीण कार्य विभाग, कार्य अंचल, पटना

[Signature]
21.06.21

[Signature]
21.06.21

Sl. No.	Material	Specifications	Unit	Lowest Bidder Sundar Nirman Bidder Rate	Amount in Word
1	Empty Cement Bags	Empty Cement Bags, Synthetic should be old but in good condition of 1.20 cft. Capacity.	Each	8.71	Eight Rupees & Seventy One Paise
2	Bamboos	Bamboos should be 100mm dia 6 to 8m long.	Each	170.00	One Hundred & Seventy Rupees
3	Brickbats		M3	1741.00	One Thousand Seven Hundred & Forty One Rupees
4	Local Sand		M3	337.00	Three Hundred & Thirty Seven Rupees
5	Kiln Rubbish		M3	1068.00	One Thousand & Sixty Eight Rupees
6	Hume Pipe (NP3) 600mm Dia		M	1044.50	One Thousand Forty Four & Fifty Paise
7	Hume Pipe (NP3) 1000mm Dia		M	3362.80	Three Thousand Three Hundred Sixty Two & Eighty Paise
8	Boulders	Minimum Size 300mm	M3	1861.35	One Thousand Eight Hundred Sixty One & Thirty Five Paise
9	Granular Sub base Material Grading-II		M3	1814.00	One Thousand Nine Hundred & Ninety Rupees
10	Stone Metal Aggregates Gr-II		M3	1857.00	One Thousand Eight Hundred & Fifty Seven Rupees
11	Stone Metal Aggregates Gr-III		M3	1810.26	One Thousand Eight Hundred Ten & Twenty Six Paise
12	Screening Material Type-B		M3	2712.58	Two Thousand Seven Hundred Twelve & Fifty Eight
13	Nylone Crate	Nylone crate of size 1m3(1mx1mx1m) with 20mm mesh of specification 1260/3/4/2/1 ie has 1023 threads of weight 165 1/2-5gm.	Each	45.00	Forty Five Rupees


Estimator
R.W.D. Patna
Waste Circle, Patna

माननीय सचिव
ग्रामीण कार्य विभाग

Superintending Engineer
R.W.D. WASTAGE CIRCLE, PATNA

	Type	Output	Unit	Lowest MS Sunday Normal Bidder Rate	Amount in Word
1	Unskilled Labour	110 cft. Soft Earth.	Each	329.00	Three Hundred & Twenty Nine Rupees
2	Semi Skilled Labour		Each	343.00	Three Hundred & Forty Three Rupees
3	Skilled labour		Each	418.00	Four Hundred & Eighteen Rupees
4	Mason		Each	396.00	Three Hundred & Ninty Six Rupees
5	Head mason		Each	445.00	Four Hundred & Forty Five Rupees
6	Bhisti		Each	329.00	Three Hundred & Twenty Nine Rupees
7	Carpenter		Each	396.00	Three Hundred & Ninty Six Rupees
8	Head Carpenter		Each	445.00	Four Hundred & Forty Five Rupees
9	Night Guard		Each	343.00	Three Hundred & Forty Three Rupees
10	Electrician		Each	421.00	Four Hundred & Twenty One Rupees


Estimator
 R.W.D
 Works Circle, Patna


 प्राकलन पदाधिकारी
 जमीन कार्य विभाग
 कार्य अंचल पटना


 तपस्विनी सलाहकार
 ग्रामीण कार्य विभाग
 कार्य अंचल, पटना


 Superintending Engineer
 R.W.D. WORKS CIRCLE, PATNA

Sl.	Description of Machine	Activity	Output of Machine	Output	Unit	Lowest M/S Sundry Bidder Rate	Amount in Word
1.	Front End Loader 1.0 cum bucket capacity (JCB)	Soil Loading/Aggregate Loading	Cum/hour	60/25	Per Hour	1585.00	One Thousand Five Hundred & Eighty Five Rupees
2.	8-10 Ton Smooth Wheeled Roller	Compaction/Consolidation	Cum/hour	70/25	Per Hour	907.00	Nine Hundred & Seven Rupees
3.	Tractor with Trolley	Transportation of Material	25 HP Capacity	3 to 5 Ton	Ton/ Trip	647.00	Six Hundred & Forty Seven Rupees
4.	Tipper	Transportation of Material	Cum	5.50	Ton/ Trip	41.50	Forty One & Fifty Paise
5.	Tractor with Tipper	Transportation of Material	25 HP Capacity	3 to 5 Ton	Ton/ Trip	667.50	Six Hundred Sixty Seven & Fifty Paise
6.	Generator Set	Generation of Electrical energy	KVA	5	Per Hour	4183.00	Four Thousand One Hundred & Eighty Three Rupees

[Signature]
21/06/21

Estimator

R.W.D.

Works Circle, Patna

[Signature]
21/06/21

प्रारंभिक पदाधिकारी

आजीवन कार्य विभाग

कार्य अंचल, पटना

[Signature]
21/06/21

सहायक सलाहकार

प्राथमिक कार्य विभाग

कार्य अंचल, पटना

[Signature]
21/06/21

Superintending Engineer

R.W.D. WORKS CIRCLE, PATNA

अधीक्षण अभियंता का कार्यालय,
ग्रामीण कार्य विभाग, कार्य अंचल, पटना।

पत्रांक- 851 (अनुब)
प्रेषक,

/पटना, दिनांक- 21/06/2021

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, पटना

सोपाने,
कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बाढ़।

विषय:- Very Short Notice No. RWD/FDR/Patna /01(2021-22) के तहत आमंत्रित कोटेशन
अंतर्गत कार्य प्रमंडल, बाढ़ में न्यूनतम दर दाता के साथ एकरारनामा करने के संबंध में।

महाराज,

उपर्युक्त विषय के संबंध में कहना है कि कोटेशन के माध्यम से प्राप्त आमंत्रित निविदा में
तकनीकी विवरणी एवं वित्तीय विवरणी में सफल एवं न्यूनतम दर दाता M/S Sundar Nirman घोषित
किए गए हैं। इनके द्वारा उद्धृत न्यूनतम दर इस पत्र के साथ संलग्न कर भेजी जा रही है। यदि दरों में
कोई त्रुटि दृष्टिगोचर हो तो अविलंब उसका निराकरण करा लिया जाये।

अतः आपको निदेश दिया जाता है कि उक्त संवेदक से 03 (तीन) दिनों के अंदर एकरारनामा
करते हुए उसकी सूचना अधोहस्ताक्षरी के कार्यालय में समर्पित करना सुनिश्चित करें साथ ही साथ अन्य
संवेदक अगर इसी न्यूनतम दर पर कार्य करने हेतु ईच्छुक हो तो उन्हें भी सूचीबद्ध कर ली जाये, ताकि
भविष्य में आवश्यकता पड़ने पर उनसे काम लिया जा सके।

संबंधित संवेदक का प्राप्त अग्रघन की राशि पत्र के साथ संलग्न की जा रही है।

अनु०-यथोपत।

विश्वासभाजन

[Signature]
21/6/21

अधीक्षण अभियंता
ग्रामीण कार्य विभाग, कार्य अंचल, पटना

[Signature]
D:\Bipin\2021\FOR\FDR Work Order.DOCX

[Signature]
28/06/21
Executive Engineer
R. Scanned by CamScanner
28/6/21 BARH 28/6/21

Scanned with CamScanner

Lowest Bidder Rate
Works Division : Barh

Sl. No.	Material	Specifications	Unit	Lowest M/S Sundar Niranjan Bidder Rate	Amount in Word
1	Empty Cement Bags	Empty Cement Bags, Synthetic should be old but in good condition of 1.20 cft. Capacity.	Each	8.71	Eight Rupees & Seventy One Paise
2	Bamboos	Bamboos should be 100mm dia 6 to 8m long.	Each	170.00	One Hundred & Seventy Rupees
3	Brickbats		M3	1741.00	One Thousand Seven Hundred & Forty One Rupees
4	Local Sand		M3	337.00	Three Hundred & Thirty Seven Rupees
5	Klin Rubbish		M3	1068.00	One Thousand & Sixty Eight Rupees
6	Hum Pipe (NP3) 600mm Dia		M	1044.50	One Thousand Forty Four & Fifty Paise
7	Hum Pipe (NP3) 1000mm Dia		M	3362.80	Three Thousand Three Hundred Sixty Two & Eighty Paise
8	Boulders	Minimum Size 300mm	M3	1861.25	One Thousand Eight Hundred Sixty One & Thirty Five Paise
9	Granular Sub base Material Grading-II		M3	1814.00	One Thousand Nine Hundred & Ninety Rupees
10	Stone Metal Aggregates Gr-II		M3	1857.00	One Thousand Eight Hundred & Fifty Seven Rupees
11	Stone Metal Aggregates Gr-III		M3	1810.26	One Thousand Eight Hundred Ten & Twenty Six Paise
12	Screening Material Type-B		M3	2711.58	Two Thousand Seven Hundred Twelve & Fifty Eight
13	Nyloine Crute	Nyloine crute of size 1m3(maximum) with 20cm mesh of specification 12600/412/1c having 24no threads of weight 165 +/- 5gm.	Each	45.00	Forty Five Rupees

Estimator

Supervisor

Inspector

Supervisor

21/11/2021

Signature

Executive Engineer
R.W.D. Works Division
BARH
21/11/2021

II. LABOUR

Works Division : Barh

	Type	Output	Unit	Lowest M/S Sundar Nirman Bidder Rate	Amount in Word
1	Unskilled Labour	110 cft. Soft Earth.	Each	329.00	Three Hundred & Twenty Nine Rupees
2	Semi Skilled Labour		Each	343.00	Three Hundred & Forty Three Rupees
3	Skilled Labour		Each	418.00	Four Hundred & Eighteen Rupees
4	Mason		Each	396.00	Three Hundred & Ninety Six Rupees
5	Head mason		Each	445.00	Four Hundred & Forty Five Rupees
6	Blister		Each	329.00	Three Hundred & Twenty Nine Rupees
7	Carpenter		Each	396.00	Three Hundred & Ninety Six Rupees
8	Head Carpenter		Each	445.00	Four Hundred & Forty Five Rupees
9	Night Guard		Each	343.00	Three Hundred & Forty Three Rupees
10	Electrician		Each	421.00	Four Hundred & Twenty One Rupees

Estimator

Director of Public Works

Barh

Superintending Engineer
R.W.D. WORKS CIRCLE, PATNA

Rajesh Kumar

Executive Engineer
H.W.D. Works Division
BARH
28/06/21

Scanned with CamScanner

III. TOOLS PLANTS & MACHINERIES WITH DRIVER & FUEL

Works Division : Barh						
Description of Machine	Activity	Output of Machine	Output	Unit	Lowest M/S Sundar Nirman Bidder Rate	Amount In Word
Front End Loader 1.0 cum bucket capacity (JCB)	Soil Loading/Aggregate Loading	Cum/hour	60/25	Per Hour	1585.00	One Thousand Five Hundred & Eighty Five Rupees
8-10 Ton Smooth Wheeled Roller	Compaction/Consolidation	Cum/hour	70/25	Per Hour	997.00	Nine Hundred & Seven Rupees
Tractor with Trolley	Transportation of Material	25 HP Capacity	3 to 5 Ton	Ton/ Trip	647.00	Six Hundred & Forty Seven Rupees
Tipper	Transportation of Material	Cum	5.50	Ton/ Trip	41.50	Forty One & Fifty Paise
Tractor with Tipper	Transportation of Material	25 HP Capacity	3 to 5 Ton	Ton/ Trip	667.50	Six Hundred Sixty Seven & Fifty Paise
Generator Set	Generation of Electrical energy	KVA	5	Per Hour	4183.00	Four Thousand One Hundred & Eighty Three Rupees

[Signature]
Estimator
R.W.D.
Works Circle, Patna

[Signature]
प्रमुख पदाधिकारी
आजीवन कार्य विभाग
खरद अंचल, पटना

[Signature]
सहायक सहायक
आजीवन कार्य विभाग
खरद अंचल, पटना

[Signature]
Superintending Engineer
R.W.D. WORKS CIRCLE, PATNA

[Signature]
R.W.D. Khari

[Signature]
Executive Engineer
R.W.D. Works Division
BARH 25/06/21

Scanned with CamScanner

कार्यपालक अभियन्ता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, बाढ़

पत्रांक 784 / बाढ़ / दिनांक 28/06/21
प्रेषक,

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल बाढ़।

सेवा में,

मेसर्स सुन्दर निर्माण,
सहजानन्द नगर, बार्ड नं०-01, बाढ़, पटना।

विषय :- बाढ़/अतिवृष्टि से क्षतिग्रस्त पथों के परिचालन हेतु सामग्रियों की आपूर्ति
हेतु कार्यादेश के सम्बन्ध में।

प्रसंग :- एकरारनामा संख्या 02/एफ02/2021-22

महाशय,

उपर्युक्त विषय के सम्बन्ध में कहना है कि अधीक्षण अभियन्ता ग्रामीण कार्य
विभाग, कार्य अंचल पटना के पत्रांक 851 अनु० दिनांक 21.06.2021 के आलोक में
विषयगत कार्य हेतु आपका एकरारनामा कर लिया गया है। जिसका एकरारनामा
संख्या 02/एफ02/2021-22 दिनांक 28.06.2021 है। उक्त एकरारनामा वित्तिय वर्ष
2021-22 के लिए मान्य होगा।

सूचनार्थ प्रेषित।

विश्वासमाजन

28/06/21
कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बाढ़
28-6-21

कार्यपालक अभियन्ता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, बाढ़

पत्रांक 784 / बाढ़ / दिनांक 28/06/21

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल बाढ़।

सेवा में,

मेसर्स सुन्दर निर्माण,
सहजानन्द नगर, वार्ड नं०-01, बाढ़, पटना।

विषय :- बाढ़/अतिवृष्टि से क्षतिग्रस्त पथों के परिचालन हेतु सामग्रियों की आपूर्ति हेतु कार्यादेश के सम्बन्ध में।

प्रसंग :- एकरारनामा संख्या 02/एफ02/2021-22

महाशय,

उपर्युक्त विषय के सम्बन्ध में कहना है कि अधीक्षण अभियन्ता ग्रामीण कार्य विभाग, कार्य अंचल पटना के पत्रांक 851 अनु० दिनांक 21.06.2021 के आलोक में विषयगत कार्य हेतु आपका एकरारनामा कर लिया गया है। जिसका एकरारनामा संख्या 02/एफ02/2021-22 दिनांक 28.06.2021 है। उक्त एकरारनामा वित्तिय वर्ष 2021-22 के लिए मान्य होगा।
सूचनार्थ प्रेषित।

विश्वासभाजन

28/06/21
कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बाढ़।

ज्ञापार्क / बाढ़ / दिनांक

प्रतिलिपि :- अधीक्षण अभियन्ता, ग्रामीण कार्य विभाग, कार्य अंचल पटना को सूचनार्थ समर्पित।

28/06/21
कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बाढ़।

ज्ञापार्क / बाढ़ / दिनांक

प्रतिलिपि :- समी कनीय अभियन्ता/सहायक अभियन्ता ग्रामीण कार्य विभाग कार्य प्रमंडल बाढ़ को सूचनार्थ एवं आवश्यक कारवाई हेतु समर्पित।

28/06/21
कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बाढ़।

Inspection Report for Flood Damage Work

Date :- 24.11.21

1. Name of PIUs :- Executive Engineer, R.W.D. Works(D), Barh
 2. Name of Block / Road :- Ghoswari / Ghoswari Karna PMGSY Road to Kanya vidyalaya Paigra
- A. For Road
1. Damage Location / Chainage :- Ch. 0.600 to 0.700 Km
 2. Damage Length :- 60 m
 3. Nature of Damage :- Breach and scum in the road due to flood
- i. Material being used in Restoration works :- Brick Bats
 - ii. Equipments / Tools being used in Restoration works : J.C.B, tractor
 - iii. Procedure taken up in Restoration works : Brick bats laying & spreading.
 - iv. Restored Length : 56.0 m

B. For Bridge


1. Damage Location / Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works :-

- i. Material being used in Restoration works :-
- ii. Equipments / Tools being used in Restoration works :
- iii. Procedure taken up in Restoration works :
- iv. Restored Length :

Work is Satisfactory.

N/A

Humy
02.12.21
AC


Name of Inspector
Executive Engineer
R.W.D. Works Division, Patna