

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये
रु.1000

ONE THOUSAND RUPEES
Rs.1000



सत्यमेव जयते

INDIA

जिला कोषागार पदाधिकारी
बिहार BIHAR
मोतिहारी

25 MAY 2022

दरीय कोषागार पदाधिकारी
पूर्व जिला कोषागार

1025 से. 312. एन। धाका/ममगसि (WB)
10-6-22

वास्तु कार्य में रु. 1000

AP 553151

कृष्ण कुमार

कृष्ण कुमार
मुद्रांक विभाग
बिहार न्यायालय, मोतिहारी
LN-78/31

Supplementary Agreement

SBD/ R.W.D. Dhaka/MMGSY(WB)

This agreement, made the ____ day of ____ 20____,

Between Executive Engineer RWD (W) Div. , Dhaka of the one part, and M/S R.N. Construction, Bhawanipur Jirat, Motihari, Dist- East Champaran of the another part. Whereas the Employer is desirous that the Contractor execute Construction of Pachpakri Gurhenwa to Yadavpur Nanka Tola Under MMGSY(WB) and the employer has accepted the Bid by the contractor for the execution and completion of such works and the remedying of any defects therein at a cost of Rupees 41,95,410.00 (Rupees Forty One Lac Ninty Five Thousand Four hundred Ten) Only

NOW THIS REVISED AGREEMENT WITNESSETH as follows:

1. In this Revised Agreement, words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.

2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute

M/S R. N. Construction
होना/ममगसि
Partner

Executive Engineer
R. W. D. (W) Div.
Dhaka
23/6/22

BILL OF QUANTITY

Name of Road:-- Pachpakri Gurhenwa to Yadavpur Nanka Tola

MMGSY (WB)

Length of the Road:- 3.700 KM.

Block :- Dhaka

District:- East Champaran

SI No	Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
		3	4	5	6
1	Construction of Embankment with Material Obtained from Borrow Pits	Cum	2913.00	168.28	490199.64
2	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	Cum	299.29	2470.00	739255.56
3	Granular Sub-base Construction of granular sub-base by providing well graded material (Crushed Stone Aggregates and Local Sand), spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with three wheel 80-100 kN static roller capacity to achieve the desired density, complete as per Technical Specification Clause 401	Cum	127.26	4417.70	562179.94
4	WBM Gr-II (Water Bound Macadam with Stone screening) Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	Cum	139.29	4300.68	599057.84
5	WBM Gr-III (Water Bound Macadam with Stone screening) Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	Cum	1857.25	32.37	60119.18
6	Prime Coat Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0kg/sqm using mechanical means as per Technical Specification Clause 502	Sqm	1857.25	97.27	180654.71
6	Providing and laying surface dressing as wearing course consisting of a layer of bitumen binder laid on the prepared surface, followed by a cover of crushed stone chippings of specified size and rolling with 80-100 kN roller including cleaning the road surface as per Technical Specification. Nominal chipping size 13.2 mm	Sqm			

Executive Engineer

MMGSY (WB)

East Champaran

23/06/22

अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, मोतिहारी

No	Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	2	3	4	5	6
7	Providing and laying surface dressing as wearing course consisting of a layer of bitumen binder laid on the prepared surface, followed by a cover of crushed stone chippings of specified size and rolling with 80-100 kN roller including cleaning the road surface as per Technical Specification. Nominal chipping size 9.5 mm	Sqm	1857.25	78.74	146239.87
8	Earth work in excavation of foundation trenches :- Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materia	Cum	130.80	248.48	32501.18
9	Providing RCC M25 :- Providing and laying reinforced cement concrete in superstructure (Deck slab M25) as per drawing and technical specifications Clauses 800, 1205.4, 1205.5	Cum	163.84	7922.64	1298045.34
10	Providing weep holes in abutement :- Providing Weepholes in brick masonry, Plain / Reinforced concrete abutement, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing	No.	40.00	122.27	4890.80
11	Supplying, fitting and placing HYSD bar reinforcement in sub-structure complete as per drawing and technical specifications	MT	1.63	50470.00	82266.10
	TOTAL AMOUNT :-				4195410.16

~~Handwritten~~
30.5.22
EE

B.O.Q. for Balance work damaged due to Flood is approved for RS 4195410.00
(Forty One Lacs Ninety five Thousand Four hundred Ten only)

~~Signature~~ 07/06/2022
S.E. (R.W.D)
WORKS Circle
Motihari

~~Signature~~ 23/06/22
R.W.D. (Works)
Division Dhaka

~~Signature~~ 23/06/22
Executive Engineer
R.W.D. (Works)
Division Dhaka

मुख्य अभियंता -3 का कार्यालय
ग्रामीण कार्य विभाग, बिहार, पटना
पटना दिनांक:-

पत्रांक:- II/मु0अ0-3,त0स्वी0-7-74/22

प्रेषक,

मुख्य अभियंता-3,
ग्रामीण कार्य विभाग,
बिहार, पटना।

सेवा में,

अधीक्षक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, मोतिहारी।

विषय- शीर्ष एम0एम0जी0एस0वाई0 अन्तर्गत कार्य प्रमंडल, ढाका के अधीन बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ के पुनर्स्थापन हेतु प्राप्त 04 अदद पथों के प्राक्कलन पर पुनरीक्षित तकनीकी स्वीकृति प्रदान करने के संबंध में।


प्रसंग-आपका पत्रांक-100 अनु0 दिनांक-23.02.2022 एवं अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना का पत्रांक-551,552 अनु0 दिनांक-10.06.2021, पत्रांक-651 दिनांक-10.07.2021 एवं पत्रांक-754 अनु0 दिनांक-03.08.2021

महाशय,

उपयुक्त विषयक प्रासंगिक पत्र द्वारा प्राप्त कार्य प्रमंडल, ढाका के अधीन स्वीकृत पथ के प्राक्कलन पर विभागीय पत्र में दिये गये निर्देश के आलोक में पुनरीक्षित तकनीकी स्वीकृति प्रदान कर लौटाया जा रहा है जिसकी विवरणी निम्न है-

Sl. No	Name of Division	Name of Scheme	Length (in KM)	Department Ref No./Date	A.A. Amount (in Lakh) Construction & Maintenance Cost	Revised T.S. Amount (in Lakh) (At. Agemt. Rate)	F.D.R. Damage Repair Cost (in Lakh)
1.	Dhaka	Bangali Tola to Dakshin Tola (Jamia path)	1.716	172/12.02.18	122.140	113.00	4.308
2.	Dhaka	Sapahi Chhitkahi Road to Naya Tola (Word No.07)	1.176	112/11.01.16	93.740	90.40	6.013 5.682
3.	Dhaka	Pachpakri Gurhenwan Road To Murali Purvi Tola	1.175	112/11.01.16	92.870	91.59	4.087
4.	Dhaka	Pachpakri Guhenwa To Yadavpur Nanka Tola	3.700		315.26	285.31	41.954

- निर्माण कार्य एम0एम0जी0एस0वाई0 योजना की मार्गदर्शिका के अनुरूप किया जाएगा।
- स्वीकृत प्राक्कलन की जाँच अधीक्षक अभियंता, अपने स्तर से कर लेंगे यदि किसी प्रकार की संशोधन की आवश्यकता हो, तो मुख्यालय को सूचित करेंगे।
- समर्पित किए गए प्राक्कलन की तकनीकी स्वीकृति इस आधार पर दी जाती है कि प्रस्तुत किए गए प्राक्कलन वार्षिक कार्य स्थल के निर्माण के लिए कार्य स्थल के अनुरूप तैयार की गई है, जिसमें पथ एवं पुल निरूपण सम्बंधित सारी आवश्यकता पूरी कर ली गई है।


Executive Engineer
R. W. D. (Works)
Division Dhaka
23.04.22

5. अधीक्षण अभियंता, पथों का निरीक्षण प्रतिवेदन एवं कार्यों के संबंध में समीक्षात्मक टिप्पणी मुख्यालय को 5वीं तिथि को उपलब्ध कराना सुनिश्चित करेंगे।
6. पुनरीक्षित प्राक्कलन के नये मदों का दर प्राथमिक एकरारनामा के दर से निर्धारित होगी, जिसका तात्पर्य यह है कि प्राथमिक एकरारनामा के समय सक्षम पदाधिकारी द्वारा अनुमोदित दर अतिरिक्त मद की दर के लिए मार्गदर्शक होगी। यह उससे कम हो सकती है किन्तु किसी भी परिस्थिति में यह प्राथमिक एकरारनामा की दर से अधिक नहीं होगी। प्राक्कलन की स्वीकृति दरों की स्वीकृति नहीं समझी जाये।
7. पुनरीक्षित प्राक्कलन का दर मूल एकरारनामा के दर के समान होगा तथा नया मद का दर भी मूल एकरारनामा के दर पर आधारित होगा।
8. अधीक्षण अभियंता, कार्य अंचल, मोतिहारी ऐसे मदों के दर जो, अनुसूचित दर में नहीं है, कर दर अपने अंचल स्तर से राज्यस्तरीय, अनुसूचित दर निर्धारण समिति के द्वारा अनुमोदित सामाग्रियों के दर के आधार पर MORD Data book analysis के आधार पर दर विश्लेषण करते हुए मुख्यालय को सूचित करेंगे। ताकि मुख्यालय अनुसूचित दर निर्धारण समिति की बैठक में उसका अनुमोदन का S.O.R तैयार करने की दिशा में कार्रवाई की जा सके।
9. स्थल पदाधिकारी द्वारा लम्ब काट एवं आड़ी काट के आधार पर मिट्टी की मात्रा की गणना कर भुगतान किया जायेगा।
10. अधीक्षण अभियंता, कार्य अंचल, मोतिहारी को निदेश दिया जाता है कि नये मद का दर विश्लेषण जाँच कर संतुष्ट हो लेंगे एवं पुनरीक्षित तकनीकी स्वीकृति के उपरान्त लोक निर्माण संहिता के सुसंगत कड़िका के अनुरूप अग्रेतर आवश्यक कार्रवाई करेंगे।

अनु०- स्वीकृत प्राक्कलन की मूल प्रति।

विश्वासभाजन

ह०/-

मुख्य अभियंता-3, पटना

पटना, दिनांक:- 22-4-22

झापाक:- 1841

प्रतिलिपि-कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, ढाका को सूचनार्थ एवं आवश्यक कार्रवाई हेतु अग्रसारित।

मुख्य अभियंता-3, पटना

Division Office
R. W. O. (Civil)
Buxar