



1021 से आर.एन.सी. जगत
10-6-22 से एच.टी.सी. से 2 करोड़ (1000) करोड़ रुपये का कार्य

AP 553147

Supplementary Agreement

कृष्णा कुमार श्रीवास्तव
मुद्रांक विक्रेता
बिहार न्यायालय, मोतिहारी
L.N.-79/81

11819 SBD/ R.W.D. Dhaka/NABARD

This agreement, made the ____ day of _____ 20_____,
Between Executive Engineer RWD (W) Div. , Dhaka of the one part, and M/S R.N.
Construction, Bhawanipur Jirat, Motihari, Dist- East Champaran of the another
part. Whereas the Employer is desirous that the Contractor execute Construction of Dhaka
Belwa ghat Mohabbatpur Dhaka to Hanuman Nagar, Anusuchit Jati tola Under
NABARD and the employer has accepted the Bid by the contractor for the execution and
completion of such works and the remedying of any defects therein at a cost of Rupees
29,73,363.00 (Rupees Twenty Nine Lac Seventy Three Thousand Three hundred Sixty
Three) Only

NOW THIS REVISED AGREEMENT WITNESSETH as follows:

1. In this Revised Agreement, words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute

M/S R. N. Construction
मोतिहारी
Partner

23/6/22
Executive Engineer
R. W. D. (Works)
Division Dhaka
23/6/22

मुख्य अभियंता -3 का कार्यालय
ग्रामीण कार्य विभाग, बिहार, पटना

पत्रांक:- II/मु0अ0-3,त0स्वी0-7-74/22
प्रेषक,

पटना दिनांक:-

मुख्य अभियंता-3,
ग्रामीण कार्य विभाग,
बिहार, पटना।

सेवा में,

अधीक्षक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, मोतिहारी।

विषय:- शीर्ष राज्य योजना (नाबार्ड ऋण सम्पोषित योजना) अन्तर्गत कार्य प्रमंडल, ढाका के अधीन बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ के पुनर्स्थापन हेतु प्राप्त 01 अदद पथों के प्राक्कलन पर पुनरीक्षित तकनीकी स्वीकृति प्रदान करने के संबंध में।

प्रसंग:-आपका पत्रांक-100 अनु0 दिनांक-23.02.2022 एवं अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना का पत्रांक- 2209 अनु0 दिनांक-24.07.2021

महाशय,

उपर्युक्त विषयक प्रासंगिक पत्र द्वारा प्राप्त कार्य प्रमंडल, ढाका के अधीन स्वीकृत पथ के प्राक्कलन पर विभागीय पत्र में दिये गये निदेश के आलोक में पुनरीक्षित तकनीकी स्वीकृति प्रदान कर लौटाया जा रहा है जिसकी विवरणी निम्न है:-

Sl. No.	Name of Division	Name of Scheme	Length (in KM)	Department Ref Lett. No./Date	A.A. Amount (in Lakh) Construction Cost & Maintenance Cost	Revised T.S. Amount (in Lakh) (At. Agemt. Rate)	F.D.R. Damage Repair Cost (in Lakh)
1.	Dhaka	पूर्वी चम्पारण जिलान्तर्गत कार्य प्रमंडल, ढाका के अधीन ढाका प्रखंड बेलवा घाट सड़क से महबूतपुर ढाका से हनुमान नगर अनुसूचित जाति टोला तक पथ निर्माण कार्य।	2.481	2379/02.07.18	172.189	197.64	29.73

- निर्माण कार्य राज्य योजना की मार्गदर्शिका के अनुरूप किया जाएगा।
- स्वीकृत प्राक्कलन की जाँच अधीक्षक अभियंता, अपने स्तर से कर लेंगे यदि किसी प्रकार की संशोधन की आवश्यकता हो, तो मुख्यालय को सूचित करेंगे।
- समर्पित किए गए प्राक्कलन की तकनीकी स्वीकृति इस आधार पर दी जाती है कि प्रस्तुत किए गए प्राक्कलन वास्तविक कार्य स्थल के निर्माण के लिए कार्य स्थल के अनुरूप तैयार की गई है, जिसमें पथ एवं पुल निरूपण सम्बंधित सारी आवश्यकता पूरी कर ली गई है।
- अधीक्षक अभियंता, पथों का निरीक्षण प्रतिवेदन एवं कार्यों के संबंध में समीक्षात्मक टिप्पणी मुख्यालय को 5वीं तिथि को उपलब्ध कराना सुनिश्चित करेंगे।
- पुनरीक्षित प्राक्कलन के नये मदों का दर प्राथमिक एकरारनामा के दर से निर्धारित होगी, जिसका तात्पर्य यह है कि प्राथमिक एकरारनामा के समय संक्षम पदाधिकारी द्वारा अनुमोदित दर अतिरिक्त मद की दर के लिए मार्गदर्शक होगी। यह उससे कम हो सकती है किन्तु किसी भी परिस्थिति में यह

[Signature]
Executive Engineer
R. W. D. (Works)
Division Dhaka
25.07.22

- प्राथमिक एकरारनामा की दर से अधिक नहीं होगी। प्राक्कलन की स्वीकृति दरों की स्वीकृति नहीं समझी जाये।
7. पुनरीक्षित प्राक्कलन का दर मूल एकरारनामा के दर के समान होगा तथा नया मद का दर भी मूल एकरारनामा के दर पर आधारित होगा।
 8. अधीक्षण अभियंता, कार्य अंचल, मोतिहारी ऐसे मदों के दर जो अनुसूचित दर में नहीं है, कर दर अपने अंचल स्तर से राज्यस्तरीय, अनुसूचित दर निर्धारण समिति के द्वारा अनुमोदित सामाग्रियों के दर के आधार पर MORD Data book analysis के आधार पर दर विश्लेषण करते हुए मुख्यालय को सूचित करेंगे। ताकि मुख्यालय अनुसूचित दर निर्धारण समिति की बैठक में उसका अनुमोदन का S.O.R तैयार करने की दिशा में कार्रवाई की जा सके।
 9. स्थल पदाधिकारी द्वारा लम्ब काट एवं आड़ी काट के आधार पर मिट्टी की मात्रा की गणना कर भुगतान किया जायेगा।
 10. अधीक्षण अभियंता, कार्य अंचल, मोतिहारी को निदेश दिया जाता है कि नये मद का दर विश्लेषण जाँच कर संतुष्ट हो लेंगे एवं पुनरीक्षित तकनीकी स्वीकृति के उपरान्त लोक निर्माण संहिता के सुसंगत कंडिका के अनुरूप अग्रेतर आवश्यक कार्रवाई करेंगे।
- अनु0- स्वीकृत प्राक्कलन की मूल प्रति।

विश्वासभाजन

ह0/-

मुख्य अभियंता-3, पटना

ज्ञापक:- 1840

पटना, दिनांक:- 22-4-22

प्रतिलिपि:-कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, ढाका को सूचनार्थ एवं आवश्यक कार्रवाई हेतु अग्रसारित।

मुख्य अभियंता-3, पटना

BILL OF QUANTITY

Name of Road:- Dhaka Belwa Ghat Mohabbatpur Dhaka to Hanuman Nagar Anusuchit Jati Tola

NABARD

Block :- Dhaka

District:- East Champaran

Length of the Road:- 2.481 KM.

Sl No	Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	2	3	4	5	6
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m. transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	Cum	1080.00	155.23	167643.40
2	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with three wheel 80-100 kN static roller capacity to achieve the desired density, complete as per Technical Specification Clause 401 (Gr-1 Materials)	Cum	114.80	2962.18	340058.26
3	Water Bound Macadam Grading 3 - Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	Cum	57.03	3772.45	215142.82
4	Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502	Sqm	74.25	47.84	3552.12
5	Earth work in excavation for foundation of structures upto 3.0 m depth as per drawing and technical specification clause 1104	Cum	254.27	288.02	73234.85
6	Sand Filling in Foundation Trenches as per drawing and technical specification Clause 1108 - rate as per item No. 11.2 (I) of Chapter 11	Cum	11.95	364.55	4356.37
7	Providing PCC Grade M15 for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	Cum	19.77	6806.00	134554.62
8	Providing Reinforced cement RCC GRADE M-25 concrete in box cell complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204.	Cum	127.05	8749.74	1111654.47
9	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 (Granular Materials)	Cum	28.80	2992.08	86171.90
10	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7	Nos.	40.00	103.18	4127.20

22/6/22
R. N. Construction
Son

11/06/22

Executive Engineer
R. W. D. (Works)
Division Dhaka
23/06/22

Approved

अधीक्षक अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, मोतिहारी

01/06/2022

BILL OF QUANTITY

Name of Road:- Dhaka Belwa Ghat Mohabbatpur Dhaka to Hanuman Nagar Anusuchit Jati Tola

NABARD

Block :- Dhaka

District:- East Champaran

Length of the Road:- 2.481 KM.

SI No	Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	2	3	4	5	6
11	Providing and laying boulder apron for bed protection with stone boulders of minimum size and weight as per Table 1300.1, no fragment weighing less than 25 kg laid dry complete as per drawing and technical specifications Clause 1301.	Cum	88.02	3538.63	311470.21
12	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202	Mt	7.09	75519.40	535432.55
	Less 0.47% Below				-14040.80
	TOTAL OF CONSTRUCTION PART				2973362.97

Handwritten:
30.5.22
EE
B.O.Q. For Balance work damaged due to flood is approved for

B.O.Q. Approved for Construction Cost PART-A' SI. No. 1 To... 12... For
 ₹ 2973363.003 Crores Twenty Nine Lakhs
 Seventy Three Thousand Three Hundred Sixty Three (Only)
 And maintenance Cost Estimated at Rs 0.00
 (₹) Crores Lacs Thousand
 Hundred (Only)

Handwritten:
07/06/2022
SE (R)
Ak
07/06/2022

Handwritten:
B.R. Construction
Partner

Handwritten:
Executive Engineer
R. W. D. (Works)
Division Dhaka
23.6.22
29/6/22