

FLOOD DAMAGED REPORT

GENERAL ABSTRACT OF COST

Block:--

Isuapur

District:- Chapra

Length of Road:--

0.340 KM

Name of Road:--

Agothar Sundar To Harijan Tola

SL. No.	Item of Work	Amount
A	TOTAL COST OF CONSTRUCTION	1.298 Lacs
	TOTAL	1.298 Lacs

Junior Engineer

Asstt. Engineer

Executive Engineer

T/S

for Rs. 1,29,800/-
Twenty Nine thousand
SE
RWD

(Rupees One Lakh
Eight hundred) only.

Superintending Engineer
Rural (Works) Deptt.
Works Circle, Chapra

FLOOD DAMAGED REPORT

GENERAL ABSTRACT OF COST

Block:-- Isuapur

District:- Chapra

Length of Road:-- 0.340 KM

Name of Road:-- Agother Sundar To Harijan Tola

SL. No.	Item of Work	Amount
A	TOTAL COST OF CONSTRUCTION	1.298 Lacs
	TOTAL	1.298 Lacs

Junior Engineer

Asstt. Engineer

Executive Engineer

T/S

for Rs. 1,29,800/-
Twenty Nine thousand
SE
RWD

(Rupees One Lakh
Eight hundred) only.

Superintending Engineer
Rural (Works) Deptt.
Works Circle, Chapra

Inspection Report for flood Damage Work

Date :-

1- Name of PIUs :- R.W.D., (W) Division, Chapra - 11

2- Name of Block/Road :-

I Shafur
Agar Sunda to Harifan Tola

A. FOR ROAD

1- Damage Location/Chainage :- at start point (go to 400m)

2- Damage Length :- 0.340 km.

3- Nature of Damage :-

Shoulder and Road Cent due to flood

4- Details of Restoration :-

i- Material being used in Restoration

Pieces of Bats and sand bags

ii- Equipment/Tools being used in Restoration Works

:- Manual

iii- Procedure taken up in Restoration Works

:- Manual

iv- Restored Length

:- 0.340 km.

B. FOR BRIDGE

1- Damage Location/Chainage :-

2- Damage Length :-

3- Nature of Damage :-

4- Details of Restoration :-

i- Material being used in Restoration

:-

ii- Equipment/Tools being used in Restoration Works

:-

iii- Procedure taken up in Restoration Works

:-

iv- Restored Length

:-

Satisfactory



Signature of JE/AE/EE



19.11.24

R.R.


Signature


(Name of Inspector)
Chapra-1

प्रतिवेदन

1. पथ का नाम :- अगौथर सुन्दर से हरिजन टोला तक
2. क्षतिग्रस्त भाग की लंबाई :- 0.340 कि०मी०
3. प्राक्कलित राशि :- 1.298 लाख

प्रस्तुत प्राक्कलन इसुआपुर प्रखंड अंतर्गत अगौथर सुन्दर से हरिजन टोला तक पथ में वर्ष 2021 के बाढ़/अतिवृष्टि से हुए क्षति से बचाने के कार्य एवं क्षतिग्रस्त पथांश को Motorable करने से संबंधित है। मूलतः यह पथ मुख्यमंत्री ग्राम सड़क योजनान्तर्गत निर्मित है, जिसकी कुल लंबाई 0.970 कि०मी० है। वर्तमान में यह पथ पंचवर्षीय अनुरक्षण अवधि के प्रथम वर्ष के अंतर्गत है, यह पथ नदी के बगल में ही अवस्थित है। वर्ष 2021 के अतिवृष्टि एवं बाढ़ के कारण यह पथ अत्यधिक प्रभावित हुआ है। इस पथ के 400 मीटर लंबाई में तीन से चार फीट पानी का बहाव लगभग दो महीने तक पथ के उपर से होता रहा। जिस कारण पथ के 340 मीटर के लंबाई में पथ के Crust एवं Flank को बचाने हेतु Flood Fighting कार्य के तहत Sand Bag का प्रावधान पथ के दोनों तरफ औसत 0.800×0.600 (चौड़ाई एवं मोटाई में) Flood Protection का कार्य कराया गया है। इसके साथ ही एक जगह पर पथ में अधिक कटाव होने के कारण औसतन $5 \times 7 \times 0.500$ मीटर में Brick Bats Filling कर पथ को आवागमन सुचारु रखने हेतु Motorable कार्य कराया गया है। जिसकी सूचना कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, छपरा-2 के द्वारा V.C. के माध्यम से उच्चाधिकारियों को दी गयी एवं MIS पर कारण सहीत पथ का फोटोग्राफ के साथ Upload भी कर दिया गया।

यह पथ पूर्ण रूप से Endeavour Infratech & Consultancy Pvt. Ltd. द्वारा किये गये एकरारनामा के अनुसार करवाया गया है एवं प्राक्कलन में प्रस्तावित दर विभाग द्वारा किये गये निविदा के आधार पर न्यूनतम दर पर स्वीकृत/अनुमोदित दर के अनुरूप तैयार किया गया है। इस पथ के प्राक्कलन की तकनीकी एवं प्रशासनिक स्वीकृति अपेक्षित है।


R.W.D.
Chapra-2

A.E.
R.W.D.
Chapra-2


E.E.
R.W.D.
Works Division,
Chapra-2

GENERAL ABSTRACT OF COST FOR Motorable of Road

NAME OF ROAD :

Agother Sundar To Harijan Tola

DISTRICT

Chapra

BLOCK

Isuapur

DIVISION

Chapra 2

LENGTH OF ROAD (in Km)


0.340

Sl. No.	DESCRIPTION	Amount	1 % Labour Cess	12 % GST	1% Labour Cess & 12% GST AMOUNT (LAKHS)
PART-A	INITIAL RECTIFICATION INCLUDING SURFACE RENEWAL				
1	Brick Bats	0.315	0.003	0.038	0.356
2	Local Sand	0.834	0.008	0.100	0.942
	SUB TOTAL OF SURFACE RENEWAL	1.149	0.011	0.138	1.298
	TOTAL COST OF PROJECT IN LACS =	1.149	0.011	0.138	1.298


RWD 29/10/21

AE
RWD

EE
RWD


29.10.21

Sl. No.	SDB SL.NO	MORD Ref.No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (In Rs.)
1			Brick Bats Providing brick bats including spreading laying hand packing and compacting with C.I. Hammer in layers not exceeding 75 mm thick including cost of light barriers, danger signals, chowkidar, taxes, royalty etc. all complete job as per specification and direction of E/I including carriage cost of bricks.								
				Cum	1	5.00	7.00	0.50	17.50		
				Cum					17.50	1,798.45	31,473.00
2			Providing & Laying Local sand on brick bats with rolling etc completed <i>-filled cement bags</i>								
				Cum	2	155.00	0.80	0.60	148.80		
				Cum	2	180.00	0.80	0.60	172.80		
				No.					321.60	259.28	83,384.00
A) SUB TOTAL OF CRUST =											1,14,857.00

29.10.21