

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, दरभंगा-1

प्रतिवेदन

पथ का नाम :- चकमसूदपुर से प्रेमजीवर

पथ की लम्बाई :- 3.330 किलोमीटर
क्षतिग्रस्त पथांश की लम्बाई :- 0.054 किलोमीटर

प्राक्कलित राशि :- रु0 1,07,307 मात्र

प्रमंडल का नाम :- कार्य प्रमंडल, दरभंगा-1

अंचल का नाम :- कार्य अंचल दरभंगा

योजना शीर्ष :- FDR

योजना वर्ष :- 2021

प्रस्तुत प्राक्कलन चकमसूदपुर से प्रेमजीवर पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण कटाव / जलजमाव / Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था। फलतः ग्रामीणों को आवागमन में कठिनाईयों का सामना करना पड़ रहा था।

यह प्राक्कलन सचिव, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक-मु0अ0 -4-मु0-विविध कार्य 23-60 / 2020-1937 पटना, दिनांक-07.07.2021 के आलोक में तैयार किया गया है।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईंट के टुकड़ों से भरकर उसका संपीड़न किया जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन वर्तमान स्वीकृत अनुसूचित दर विश्लेषित कर संवेदक लाभांश छोड़कर तैयार किया गया है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है। यह कार्य विभागीय रूप से सम्पादित करा लिया गया है।


प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर जो संवेदक लाभांश को छोड़कर था, उसे प्रावधान करते हुए तैयार किया गया है।


06.11.2021

कनीय अभियंता,
ग्रामीण कार्य विभाग,


सहायक अभियंता
ग्रामीण कार्य विभाग,


कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, दरभंगा-1



बिहार सरकार

ग्रासीण कार्य विभाग

Rural Works Department, Govt. of Bihar

FDR

ESTIMATE FOR MOTERABLE OF ROAD

YEAR - 2021-22

DISTRICT :- DARBHANGA

BLOCK :- BAHADURUR

Total Cost of Project:- Rs. 1.07307 Lacs

1.07307

Name of Raad :- Chakmasudpur to Premjiver.

Total Length :- 3.330 KM.

Effective Length :- 0.054 KM.

EXECUTIVE ENGINEER
RWD, DARBHANGA-1

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Darbhanga1 Inspected by Benipar
Name of Block/Road:- Chakmasudpur to Premjiwar

A. For Road

1. Damage Location Chainage:- 0 to 3.33 km
2. Damage Length :- 54 m
3. Nature of Damage :- Flank Damage
4. Details of Restoration Works
 - i. Material being used in Restoration works:- Brick Bat
 - ii. Equipment's /Tools being used in Restoration works:- JCB Loader
 - iii. Procedure taken up in Restoration works:- Laying of Brick Bats with light tamping.
 - iv. Restored Length:- 54 m

B. For Bridge

1. Damage Location Chainage:-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Material being used in Restoration works:-
 - ii. Equipment's /Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

“Work found Satisfactory”

28/2/22

Signature of JE/AE/EE

Charvi
11/12/21
AE

Signature

(Name of Inspection)

FDR

DISTRICT :-	DARBHANGA	
BLOCK :-	BAHADURPUR	
Name of Raad :-	Chakmasudpur to Premjiver.	
	Length of the Road:-	3.330 KM.
	Effective Length	0.054 KM.

GENERAL ABSTRACT OF COST

Sl No.	Item of Work				Amount
					(in Rs.)
1	Cost for restoration				87,516.50 90,824.69
2	Add 12 % GST				10,501.98 10,898.96
3	Add 1 % Labour Cess				875.16 908.25
4	Seigniorage Fee	Quantity (in cum)	Rate (in Rs.)	%	
	(Br. Bats) in cum	45.300 43.65	1032.00	10.00	4504.68 4,674.96
	Total cost:-				1,03,398.32 1,07,306.86
	Say Rs.				1,03,398/- 1,07,307.00

[Signature]
66.11.2021
Junior Engineer
Bahadurpur

[Signature]
66.11.21
Assistant Engine
Bahadurpur

[Signature]
Executive Engineer
R.W.D.(W) Division, Darbhanga-1

कार्यपालक अभियंता बेरीपुर के लॉच प्रतिवेदन के आधार पर
Technically sanctioned for Rs 1,03,398 200
[on lakhs three thousand three hundred Ninety Eight
only].

[Signature]
अधिक्षण अभियंता
कार्य अंचल, दरभंगा
HS/22

Detailed estimate for making moterable road.

Name of Raad :- Chakmasudpur to Premjher.

BLOCK > BAHADURUR

DISTRICT > DARBHANGA

R.W.D. Works Division Darbhanga-1

Sl. No.	Item	Unit	No.	L	B			D/H				Quantity	Rate	Amount		
				Length (m)	Breadth (m)	Breadth (m)	Av. Breadth (m)	Depth / Height (m)	Depth / Height (m)	Depth / Height (m)	Av. Depth / Height (m)					
1	Labour and Placing Brick Bats with Light raming including cost of brick bats by tractor			1st KM												
				Start near RCD Road At RCC Culvert on Nala												
		cum	1	4.30	1.25	2.25	1.75		0.200	0.100	0.150	13.545				
		cum	1	4.00			3.0575	0.200	0.300	0.150	3.750	2.3				
		cum	1	6.50			1.30	0.200	0.100	0.150	1.268					
		cum	1	30.00			3.20	0.100	0.300	0.200	19.200					
		cum	1	9.00	3.20	3.50	3.35	0.300	0.200	0.250	7.538					
		cum									45.300	2004.96	40824.69			
		cum											40824.69			
														40824.69		

Signature
06.11.2021

Junior Engineer
Bahadurpur

Signature

Assistant Engineer
Bahadurpur

Signature
15/10/21

Executive Engineer
R.W.D.(W) Division, Darbhanga-1

Verified & found correct

Signature
11/12/21
AE

Signature
11-12-21
JE

Signature
11/12/21