

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :	EMERGENT REPAIR OF ROAD FROM DUMAR BIGAHA TO DAMAR BIGHA UNDER FDR	
DISTRICT	PATNA	
BLOCK	DHANARUA	
DIVISION	MASAUHRI	
Total Damaged length of Road	33.75 m	
SI. No.	DESCRIPTION	AMOUNT (LAKHS)
1	COST OF ITEM	816925 29,67,935.69 9,45,610 = 9
	TOTAL COST IN LACS =	9.679 9.46 8.169 lacs


 JE
 RWD



 AE
 RWD


 EE
 RWD


Technically sanctioned for Rs. 8.169 (Rupees Eight

lacs, sixteen thousand and no paise only)

including five year Maintenance Cost


Estimator
 R.W.D.
 Works Circle, Patna

तकनिकी सलाहकार
 ग्रामीण कार्य विभाग
 कार्य अंचल, पटना



Superintending Engineer
 R.W.D. WORKS CIRCLE, PATNA

Inspection Report for Flood Damage Work

Date :-

1. Name of PIUs E.E. R.W.D (W) Division Masaurhi
2. Name of Block / Road :- Dhanarua / Emergent repair of Road from Dumar bigaha to Damar Digaha under FDR
 - A. For Road
 1. Damage Location / Chainage :- Near River side at 0.500 KM.
 2. Damage Length :- 33.75 Meters
 3. Nature of Damage :- Plank & crust (in some width 0.5m) from toe of embankment due to heavy flood
 - i. Material being used in Restoration works :- Brick bats
 - ii. Equipments / Tools being used in Restoration works : Tractor, J.C.B. Labour etc.
 - iii. Procedure taken up in Restoration works : By filling breach portion with Brick bats, levelled compacted manually
 - iv. Restored Length : 33.75 Meter
 - B. For Road Bridge
 1. Damage Location / Chainage :-
 2. Damage Length :-
 3. Nature of Damage :-
 4. Details of Restoration Works :-
 - i. Material being used in Restoration works :- ~~Grass~~ Brick bats
 - ii. Equipments / Tools being used in Restoration works : ~~Butter~~
 - iii. Procedure taken up in Restoration works : —
 - iv. Restored Length : 33.75 m

Satisfactory


Name of Inspector
Executive Engineer
R.W.D. Works Division Barh