



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :- **Bitupur Rajapakar Road ke Dihwarni Asthan Chowk
(Dena Chowk) Ramdaha Word No-13**

DISTRICT **Vaishali**

DIVISION **Hajipur**

BLOCK **Hajipur**

DAMAGED LENGTH OF ROAD	:	0.000	KM
CONSTRUCTION COST	:	5.62 6.159	Lac

Submitted By :-
Executive Engineer
RWD Work Division, Hajipur

प्रतिवेदन

कार्य का नाम:- Bidupur Road Pakar Rd ke Diwanmari Station chaurak ke Ransdhrh W-B

.....पथ में अप्रत्याशित बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- 1431/158
वित्तीय वर्ष - 2021-22
प्राक्कलित राशि - Rs. 6.189 Lacs
5.62

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 5.62 6.189 Lacs है, Diwanmari Station to Ransdhrh, W-B प्रखंड- 1431/158 में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 1937 दिनांक 07.07.21 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी घटनोत्तर स्वीकृति अपेक्षित है। MIS S-No -38

27.11.21
27.11.21
27.11.21

कनीय अभियंता

सहायक अभियंता

29/11/21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल:-

Inspection Report for Flood Damage Work

Date:-

1 Name of PIUs :- RWD Works division, Hapur

2 Name of Block/Road :- Hapur / Bidpur Rajapakar road ke Dihwarni Asthan chowk (Dena chowk) Randaha ward No-13

(A) For Road:

1. Damage Location/Chainage :- 0.0 - 0.500, 0.80 km - 0.90 km
2. Damage Length :- 0.600 km
3. Nature of Damage :- Due to flood water
4. Details of Restoration Works :-
 - (i) Material being used in Restoration works:- 1000 Mandi HP → 10M, Bolek bats → 253.09M³
 - (ii) Equipment's/Tools being used in Restoration works:- J.C.D, Roller (Road) etc
 - (iii) Procedure taken up in Restoration works:-
 - (iv) Restored Length :- Work is satisfactory.

(B) For Bridge:

1. Damage Location/Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works :-
 - (i) Material being used in Restoration works:-
 - (ii) Equipment's/Tools being used in Restoration works:-
 - (iii) Procedure taken up in Restoration works:-
 - (iv) Restored Length :-

Signature
27/11/21

Signature of JE/AE/EE

Signature
27/11/21

Signature
27/11/21

Signature
27/11/21

Signature

(Name of Inspection)

GENERAL ABSTRACT

Name of Road Bitupur Rajapakar Road ke Dihwami Asthan Chowk (Dena Chowk) Ramdaha Word No-13

District Vaishali

Block Hajipur

Division Hajipur

Length of Road (in Km)

0.000 Km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Earthwork	0.000
2	Brick Bats	5.225 5.745
3	Sand Filling	0.000
4	Sand bag	0.000
5	Bamboo Piles	0.000
6	bamboo runners	0.000
7	H.P.	0.395 0.414
	SUB TOTAL	5.62 6.159
	GRAND SUB TOTAL	5.62 6.159

KA
27.11.21

JE
RWD

Sanjay
27.11.21

AE
RWD

Jan
27.11.21
EE
RWD

As Per S.E. RWD (M) Circle Muz

Letter No 1179 Dated 01/11/2021

Estimate has been verified by

E.E. RWD, (M) Division Muz West

Technically Sanctioned for Rs. 5.62 lacs
(Rs. Five lacs Sixty two thousand) only
(provisionally)

Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

27.12.21

DETAILED COST ESTIMATE OF HUME PIPE

Sl. No.	SOR Item no.	Description	Qty. (Nos.)	Length (m)	Quantity	Unit	Rate (Rs)	Amount in Rs.
1 No.								
1	9.3	Providing and Laying Reinforced Cement Concrete Pipe NP3 1000 mm dia as per design in Single Row (Vide MB No-2805 & Page No-3)	4	2.5	10.00	m	3956.05 4,144.19	39560.5 41,441.92
Grand Total :							41,441.92	

39560.5
 291 "

24	CE-3, Patna	Muzaffarpur	Vaishali	Hajipur	Hajipur	Senduari high school to godam pokhar sisauni rajauli	MMGSY-NDB(BRICS)-I	Completed	Yes	1.1	0.100	3.00	Temporary restoration done.	2021-22	Road	:
25	CE-3, Patna	Muzaffarpur	Vaishali	Hajipur	Hajipur	Noonpur Simana to Noonpur Near Binda paswan House	MMGSY[SC]	On Going	No	0.625	0.250	4.50	Temporary restoration done.	2021-22	Road	:
26	CE-3, Patna	Muzaffarpur	Vaishali	Hajipur	Hajipur	hariharpur - satihara	PMGSY-NEA	On Going	No	1.4	0.010	2.00	Temporary restoration done.	2021-22	Road	:
27	CE-3, Patna	Muzaffarpur	Vaishali	Hajipur	Hajipur	Arra - Dharhara High School	PMGSY-NEA	Completed	No	2.2	0.250	9.35	Temporary restoration done.	2021-22	Road	:
28	CE-3, Patna	Muzaffarpur	Vaishali	Hajipur	Hajipur	Ekara Chowk - Anwarpur Chowk	PMGSY-NEA	Completed	No	7	0.450	15.90	Temporary restoration done.	2021-22	Road	:
29	CE-3, Patna	Muzaffarpur	Vaishali	Hajipur	Hajipur	Dayalpur High School Se Rajapakar Bidhupur Road ki Aur Jane Wali Sadak Main Ravindra Singh ke Ghar tak		Completed	No	0.65	0.300	4.50	Temporary restoration done.	2021-22	Road	:
30	CE-3, Patna	Muzaffarpur	Vaishali	Hajipur	Hajipur	Bidupur Rajapakar Road ke Dihwarni Asthan Chowk(Dena Chowk) Se Randaha Ward No.13		Completed	No	1.8	0.600	6.00	Temporary restoration done.	2021-22	Road	2:
31	CE-3, Patna	Muzaffarpur	Vaishali	Hajipur	Lalganj	Purntand to Dilawarpur Chowk	MR	Completed	No	3.1	0.291	4.85	Temporary restoration done.	2021-22	Road	:
32	CE-3, Patna	Muzaffarpur	Vaishali	Hajipur	Lalganj	Shital bhakurahat se patehra	MR	Completed	No	5.5	1.037	15.94	Temporary restoration done.	2021-22	Road	:
33	CE-3, Patna	Muzaffarpur	Vaishali	Hajipur	Lalganj	Etbarpur sisaula road	MR	Completed	No	2.3	0.207	5.76	Temporary restoration done.	2021-22	Road	:
34	CE-3, Patna	Muzaffarpur	Vaishali	Hajipur	Lalganj	Amarsingh Asthan to Primary School Ramnagar Pakrikanth	GTSNY	Completed	Yes	0.5	0.380	14.80	Temporary restoration done.	2021-22	Road	:

sqms.rwdbihar.gov.in/Flood/ActualFloodDamageReports.aspx

Sd/-
27-11-21