



प्रतिवेदन


प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि मात्र रुपये ~~16,30,100/-~~ 16,30,100/- (सोलह लाख तीस हजार एक सौ) का है। यह प्राक्कलन मटिहानी प्रखण्ड के 701 से कासिमपुर गाँव का है। अनिवारित एवं गंगा नदी के बहाव से जहाँ-तहाँ पथ काफी क्षतिग्रस्त हो गया है। इस पथ की कुल लम्बाई 6.0 KM है। इस बीछण वारिस तथा गंगा जल स्तर के कारण कुछ पथों के किनारे हिस्से में खराब हो गया है। प्रपक्षरूप पथों में सुगम यातायात वाधित हो गया है। इसलिए इन्हीं लम्बे पथों को सुगम यातायात सुनिश्चित हेतु पथों में Borewell तथा submersible / Local Pond का प्रावधान कर पथों को सुगम यातायात का प्रावधान किया गया है।

यह प्राक्कलन कार्यपालक अभियन्ता तथा ग्रामीणों के आदेशानुसार तैयार किया गया है। पथ को Marketable बनाने हेतु पथ के क्षतिग्रस्त विभिन्न अंशों में Borewell तथा submersible / Local Pond से भरे हुए सुगम यातायात बनाने का प्रावधान किया गया है। प्राक्कलन PDR गड की शर्त से भारित होगा।

प्राक्कलन तकनीकी अनुमोदन एवं प्रशासनिक स्वीकृति हेतु समर्पित की जाती है। भयाशील स्वीकृति प्रदान करने की कृपा की जाए।


30/10/21
J. E


30/10/21
A. E


30/10/21
E. E

Detailed Estimate of F.D.R of road from Tol to
Kashipur PMGSY Path under work Division
R.W.D Begusarai for Yr 2021-22.

Item No1 Providing E/Work filling
in Diversion road Compacting
by power road roller all
Complete job.

नेर्मिन पुल के

चम भण - $1 \times 65.0 \times 4.50 \times 3.50 = 1023.75$

नेर्मिन पुल के
भाजा - $1 \times 28.0 \times 4.5 \times 3.5 = 441.0$

ने कलमई
उत्तर साईड - $1 \times 13.5 \times 1.40 \times 1.10 = 20.79$

ने कलमई के
साईड - $1 \times 8.0 \times 1.10 \times 1.10 = 9.68$
1495.22

Deduction - $1 \times 65.0 \times 2.50 \times 1.10 = 178.75$

$1 \times 28.0 \times 2.50 \times 1.70 = 119.0$
297.0

Net qty = $1495.22 - 297.0 = 1198.22 M^3$

Ch 244.38 / M³

R 2,92,821.00

Item No2 Providing and Supplying
filling in road embankment
with brick bats properly
laying & Compacting by
power road roller all
Complete job.

$1 \times 65.0 \times 3.75 \times 0.300 + 0.400 = 85.312$
2

$1 \times 28.0 \times 3.75 \times 0.300 = 31.5$

$1 \times 13.5 \times 1.10 \times 0.150 = 2.227$

$1 \times 8.0 \times 1.0 \times 0.150 = 1.20$

$1 \times 38.0 \times 3.05 \times 0.350 = 40.565$

$2 \times 30.0 \times 3.05 \times 0.150 = 27.45$

$18 M^3 \times 1.10 \times 1.25 \times 0.250 = 6.187$

$3 M^3 \times 30.0 \times 3.05 \times 0.250 = 68.625$
263.066 M³

R 2,92,821.00

$14,430.56 = 00$ R $14,42,637.00$
 Add 12% G.S.T + 1% Lab chgs $1,87,597 = 00$ R $1,87,543.00$
Total $16,30,653 = 00$
 Total R $16,30,180 = 00$

Say R 16,30,100/-

Say $16,30,653 = 00$

~~Signature~~
30/10/21
 J. E

~~Signature~~
30/10/21
 A. E

~~Signature~~
30/10/21
 E. E

Technically Approved for $16,30,653 = 00$ say -
 Sixteen Lakh Thirty thousand Six Hundred and
 fifty three say including over head chgs 12% -
 Contractor Profit 10%

Signature
 10.12.21

Signature
10/12/21
 T. A

ज्योतिष कर्मिणा
 ज्योतिष कार्य विभाग
 कार्य विभाग, प्रशासकीय

Inspection Report for flood Damage Work

Date:-

1 Name of PIUs- Executive Engineer, R.W.D. Works Division, Begusarai

2 Name of Block:- Matilani

3 Name of Road/ Bridge:- Tol to Kasimpur Pragy Path.

4 For Road:- 700

A Damage Location/Chainage:- N/A

1 Damage Length:- 673.0 M

2 Nature of Damage:- Flank. Road crust damaged

3 Details of Restoration Works:- Earth work, Brick bats, used on flank & Road crust.

4 Material Being used in Restoration Works:- Earth work & Brick bat used

i Equipments/Tools being used in Restoration Works:- J.C.B, tractor, Roller, water tank.

ii Procedure taken up in Restoration Works:- N/A

iii Restored Length:- 673.0 m

iv For Bridge:- N/A

1 Damage Location/ Chainage:- N/A

2 Damage Length:- N/A

3 Nature of Damage:- N/A

4 Details of Restoration Works:- N/A

i Material Being used in Restoration Works:- N/A

ii Equipments/Tools being used in Restoration Works:- J.C.B, Tractor

iii Procedure taken up in Restoration Works:- Brick bats and levelling dressing

iv Restored Length:- 673.0 M

[Signature]
5/5/22
J.E

[Signature]
5/5/22
A.E

[Signature]
5/5/22
Executive Engineer
R.W.D. Works. Division,
Begusarai

[Signature]
5/5/22
Satisfactory
Signature
कार्यपालिक अभियंता
(Name of Inspector)
ग्रामीण कार्य विभाग
कार्य प्रमंडल, रोसड़ा