



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

TALHARI BLOCK TO SAHEBGANJ TO GADIA MAHARAJPUR

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 5425	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	5.425	KM
TOTAL COST OF F.D.R. PART - A	Rs. 15.979	Lacs
ADD G.S.T @ 12%	Rs. 1.917	Lacs
ADD Labour Cess @ 1%	Rs. 0.160	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.181	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 18.237	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

Date : Inspection Report for flood damage work.

1. Name of PIUs Manihari
2. Name of Block/Road Amdabad / Talhari Block To Sahabganj To Gadai Maharajpur.

A for Road

1. Damage location : 2.2 To 2.5 km
2. Damage Length : 0.263 km
3. Nature of Damage : Cross Cut & washout
4. Details of Restoration :
 - i. Material being used in Restoration Earthwork & G.S.B.
 - ii. Equipment/Tools being used in Restoration Works : JCB, Tractor Trolley
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.263 km

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EE
26/11/24

Signature
(Name of Inspector)

कार्यपालक अभियन्ता

ग्रामीण कार्य विभाग

प्रमण्डल, मनिहारी (कटिहार)


प्रतिवेदन


पथ का नाम	:- Talhari Block To Sahebganj To Gadai Maharajpur
पथ की लम्बाई	:- 5.425 KM
प्राक्कलित राशि	:- 18.237 Lac
वित्तीय वर्ष	:- 2021-22 / FDR-2021
प्रखंड	:- Amdabad


प्रस्तुत प्राक्कलन मो0 18.237 लाख (अठारह लाख तईस हजार सात सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के Talhari Block To Sahebganj To Gadaimaharajpur पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाद एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक— मु0अ0-4 (मु0) विविध (कार्य)— 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त पथ गंगा नदी और गंगा के धार के बीच में स्थित है, प्रत्येक वर्ष नदी के बहाव में बड़े-बड़े गढ़े बन जाते हैं। प्राक्कलन में बने हुए बड़े-बड़े गढ़ों में मिट्टी भरने का प्रावधान किया गया है। जिस स्थान पर WBM Gr-III, GSB भी बह चुका है उस स्थान पर GSB का भी प्रावधान किया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : TALHARI BLOCK TO SAHEBGANJ TO GADIA MAHARAJPUR

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 5.425

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	10.374
2	HUME PIPE	0.000
3	BRICK BAT	0.000
4	SAND BAGS	0.000
5	G.S.B.	5.605
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		15.979
Add G.S.T. @ 12%		1.917
Add Labour Cess @ 1%		0.160
Add Seigniorage Fee @ 10%		0.181
Total Cost of Restoration Work =		18.237

[Signature]
J.E.
RWD

[Signature]
A.E.
RWD

[Signature]
E.E.
RWD

Technically Sanction for Rs. 18.237 Lac (Rs.

Crone. Eighteen Lac. Twenty three

Thousand. Seven Hundred. Only

[Signature]
Superintendent Engineer
Rural Works Department
Works Circle, Purnea