

217

47



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

S041 TO PANKHWA TOLA

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 700	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	0.700	KM
TOTAL COST OF F.D.R. PART - A	Rs. 6.275 3.202	Lacs
ADD G.S.T @ 12%	Rs. 0.753 0.384	Lacs
ADD Labour Cess @ 1%	Rs. 0.063 0.032	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.160 0.098	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 7.251 3.716	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

Date :

Inspection Report for flood damage work

Name of PIUs

Manihari

2. Name of Block/Road

Amdabad / SO 41 To Pankhwa Tola

A for Road

1. Damage location : 0.25 km, 0.29 km, 3.2 & 3.5 km

2. Damage Length : 0.119 km

3. Nature of Damage : Washout, Cross Cut

4. Details of Restoration :

i. Material being used in Restoration Earth work, Sand bags

ii. Equipment/Tools being used in Restoration Works : JCB, Tractor Trolley

iii. Procedure taken up in Restoration works: Manual

iv. Restored Length 0.119 km

B. for Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i. Material being used in Restoration :

ii. Equipment/Tools being used in Restoration Works :

iii. Procedure taken up in Restoration works:

iv. Restored Length

Signature of JE/AE/EE

Signature
(Name of Inspector)

कार्यपालक अभियन्ता

ग्रामीण कार्य विभाग

कार्य प्रमण्डल, मनिहारी (कटिहार)


प्रतिवेदन


पथ का नाम :- S041 To Pankhwa Tola
पथ की लम्बाई :- 0.700 KM
प्राक्कलित राशि :- ^{2.716} 2.251 Lac
वित्तीय वर्ष :- 2021-22 / FDR-2021
प्रखंड :- Amdabad


प्रस्तुत प्राक्कलन मो 0 ^{2.716} 2.251 लाख (सप्त लाख पच्चीस हजार एक सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के S041 To Pankhwa Tola पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में पथ में बने हुए गढ़े को भरकर GSB का प्राक्धान कर पथ में आवागमन चालू किया गया है। दोनो साईड Sand Bag डालकर पथ को कटाव से बचाया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : S041 TO PANKHWA TOLA

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 0.700

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	2.892 2.319
2	HUME PIPE	0.000
3	BRICK BAT	0.000
4	SAND BAGS	0.798 0.882
5	G.S.B.	2.585
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		6.275 3.202
Add G.S.T. @ 12%		0.753 0.384
Add Labour Cess @ 1%		0.063 0.032
Add Seigniorage Fee @ 10%		0.160 0.078
Total Cost of Restoration Work =		7.251

3.716

J.E.
RWD
26/11/21

A.E.
RWD
16/11

E.E.
RWD
16/11

Technically Sanction for Rs. 3.716 Lac (Rs.

Crone. Three Lac. seventy one

Thousand. Six Hundred.

Superintendent Engineer
Rural Works Department
Works Circle, Purnea