



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

S028 TO BANDH GANGA

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 990		
DISTRICT	KATIHAR		
BLOCK	AMDABAD		
DIVISION	MANIHARI		
TOTAL LENGTH OF ROAD	0.990	KM	
TOTAL COST OF F.D.R. PART - A	Rs. 7.656	Lacs	
ADD G.S.T @ 12%	Rs. 0.919	Lacs	
ADD Labour Cess @ 1%	Rs. 0.077	Lacs	
ADD Seigniorage Fee @ 10%	Rs. 0.107	Lacs	
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 8.759	Lacs	

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

Date : Inspection Report for flood damage work

1. Name of PIUs Manihari
2. Name of Block/Road Amdabad / SO28 To Bondh Ganga

A for Road

1. Damage location : 0.3, 0.45, 0.55 km, 0.67 km
2. Damage Length : 0.194 km
3. Nature of Damage : wash out & cross cut
4. Details of Restoration :
 - i. Material being used in Restoration Earthwork & G.S.B
 - ii. Equipment/Tools being used in Restoration Works : Tractor Trolley, JCB
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.194 km

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AF/EE

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, नमिहारी (कटिहार)

Signature
(Name of Inspector)


प्रतिवेदन

पथ का नाम	:- S028 To Bandh Ganga
पथ की लम्बाई	:- 0.990 KM
प्राक्कलित राशि	:- 8.759 Lac
वित्तीय वर्ष	:- 2021-22 / FDR-2021
प्रखंड	:- Amdabad

प्रस्तुत प्राक्कलन मो0 8.759 लाख (आठ लाख पचहत्तर हजार नौ सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के **S028 To Banfh Ganga** पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक— मु0अ0-4 (मु0) विविध (कार्य)— 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में बड़े-बड़े कटाव के स्थान पर मिट्टी भरने के पश्चात GSB का प्रावधान कर आवागमन चालू किया गया है।


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


26/11/21

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


26/11/21

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


26/11/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : S028 TO BANDH GANGA

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 0.990

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	4.879
2	HUME PIPE	0.000
3	BRICK BAT	0.000
4	SAND BAGS	0.000
5	G.S.B.	2.777
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		7.656
Add G.S.T. @ 12%		0.919
Add Labour Cess @ 1%		0.077
Add Seigniorage Fee @ 10%		0.107
Total Cost of Restoration Work =		8.759

J.E.
RWD

A.E.
RWD

E.E.
RWD

Technically Sanction for Rs. 8.759 Lac (Rs.,

Creore..... Eight Lac. Fifty seventy five

Thousand..... Nine Hundred. Only

Superintendent Engineer
Rural Works Department
Works Circle, Purnea