



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

ABBAS CHOWK MADARSA TO KADIR TOLA

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1940	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.940	KM
TOTAL COST OF F.D.R. PART - A	Rs. 6.770 4.138	Lacs
ADD G.S.T @ 12%	Rs. 0.812 0.496	Lacs
ADD Labour Cess @ 1%	Rs. 0.068 0.042	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.309 0.156	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 7.960 4.832	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

Date : Inspection Report for flood damage work.

1. Name of PIUs Manihari
2. Name of Block/Road Amdabad / Abbas Chowk madarsa to Kadir Tola.

A for Road

1. Damage location : 0.95 km
2. Damage Length : 0.045 km
3. Nature of Damage : Wash out & cross cut
4. Details of Restoration :
 - i. Material being used in Restoration Bamboo, E/W, Brick bats Sand bag.
 - ii. Equipment/Tools being used in Restoration Works : Tractor Trolley, JCB
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.045 km

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EE

Signature
(Name of Inspector)

प्रतिवेदन

पथ का नाम :- Abbas Chowk Madarsa To Kadir Tola
पथ की लम्बाई :- 1.940 KM
प्राक्कलित राशि :- 7960 Lac 4.832
वित्तीय वर्ष :- 2021-22 / FDR-2021
प्रखंड :- Amdabad 4.832

प्रस्तुत प्राक्कलन मो 0 7.960 लाख (सात लाख छियानवे हजार) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के Abbas Chowk Madarsa To Kadir Tola पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में पथ के कटे हुए स्थान पर Bamboo Piling & Runner के पश्चात Sand Bag का प्रावधान किया गया है तथा कटे हुए स्थान पर मिट्टी भरकर ईंट का टुकरा देते हुए पथ को आवागमन लायक बनाया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद
26/11/21

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद
26/11/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी
26/11/21

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : ABBAS CHOWK MADARSA TO KADIR TOLA

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 1.940

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	1.351
2	HUME PIPE	0.000
3	BRICK BAT	4.639 2.008
4	SAND BAGS	0.512
5	G.S.B.	0.000
5	BAMBOO WORK	0.268
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		6.770 4.158
Add G.S.T. @ 12%		0.812 0.496
Add Labour Cess @ 1%		0.068 0.042
Add Seigniorage Fee @ 10%		0.309 0.156
Total Cost of Restoration Work =		7.960

4.832

[Signature]
26/11/21
J.E.
RWD

[Signature]
26/11/21
A.E.
RWD

[Signature]
E.E.
RWD

Technically Sanction for Rs. 4.832 Lac (Rs.
 Crore. Four Lac. Eighty three
 Thousand. Two Hundred. (.....) Only

[Signature]
K. S. ...
Works Circle, Purnea