



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

T01 TO MANDAL TOLA BELGACHHI

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 950	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	0.950	KM
TOTAL COST OF F.D.R. PART - A	Rs. 7.688	Lacs
ADD G.S.T @ 12%	Rs. 0.923	Lacs
ADD Labour Cess @ 1%	Rs. 0.077	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.319	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 9.007	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari


प्रतिवेदन

पथ का नाम :- T01 To Mandal Tola Belgachi
पथ की लम्बाई :- 0.950 KM
प्राक्कलित राशि :- 9.007 Lac
वित्तीय वर्ष :- 2021-22 / FDR-2021
प्रखंड :- Amdabad


प्रस्तुत प्राक्कलन मो0 9.007 लाख (नौ लाख सात हजार) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के T01 To Mandal Tola Belgachi पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)-23/291/2019-4275/पटना, दिनांक 22.10. 2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में पथ के गहरे कटाव स्थान पर मिट्टी भरने के पश्चात ईट का टुकड़ा डाला गया है तथा फलैंक में जहाँ पानी का कटाव हो रहा था उस स्थान पर बास का बल्ला गाड़कर चचरी के बाद ईट का टुकड़ा दिया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Mani hauri
2. Name of Block/Road Amdeabad / Toi To Mandal Tola Belgach

A for Road

1. Damage location : 0.00 km, 0.30, 0.460,
2. Damage Length : 0.064 Km
3. Nature of Damage : Scour & Partially Cut.
4. Details of Restoration :
 - i. Material being used in Restoration E/w, Sand bag, bamboo, bricksbat
 - ii. Equipment/Tools being used in Restoration Works : Tractor, JCB,
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.064 km

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EE

Executive Engineer
Rural Works Department
Works Division, Manihari

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : T01 TO MANDAL TOLA BELGACHHI

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 0.950

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	3.867
2	HUME PIPE	0.000
3	BRICK BAT	2.643
4	SAND BAGS	1.178
5	G.S.B.	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		7.688
Add G.S.T. @ 12%		0.923
Add Labour Cess @ 1%		0.077
Add Seigniorage Fee @ 10%		0.319
Total Cost of Restoration Work =		9.007

Cipre
26/11/24
J.E.
RWD

Cipre
26/11/24
A.E.
RWD

[Signature]
26/11/24
RWD

Technically Sanction for Rs 9.007 lac (Rs Nine lac seven hundred only).

[Signature]
Superintendent Engineer
Rural Works Department
Works Circle, Purnea