

प्रतिवेदन

~~3,34,504=00~~

यह प्रोजेक्ट जो मात्र (अथवा) 356743-00 का है, मरिहानी पुलकट के ~~द्वारा~~ गणरुप से मीणापुरा रामदीरी 1 PM 414 प्लॉट का Flood Damaged Restor-
न के लिए तैयार किया गया है।

यह पथ मरिहानी पुलकट के पूर्णतः बाढ़ प्रभावित क्षेत्र में पड़ा है। इसका आगे भीषण बाढ़ में यह पथ दो गजह से कट गया जिसके कारण यातायात बाधित हो गया था।

यातायात चालू करने के उद्देश्य से वर्तमान रूप से इस करिग में Block Bit मान का प्रावधान किया गया है। साथ-साथ shoulder में मिट्टी डालने का भी प्रावधान किया गया है। यह वर्तमान अनुसूचित दायरे तैयार की तकनीक ^{अनुमान} स्वीकृत एवं प्रशासनिक स्वीकृति हेतु समर्पित किया जाता है।

किंगड
29/10/21
G.E
matihani

अनुमान
29/10/21
A.E
matihani

अनुमान
29/10/21
E.E
R.D.(w) Matihani
Begusar

Flood Damaged Repair Estimate for the road from Jagatpur to minapur (Ramdini) for the year 2021

- ① Supplying filling and levelling brick bat
with all complete job

$$1^{st} cutting - 1 \times 13.0 \times 6.75 \times 0.75 av = 65.8125 m^3$$

$$1 \times 7.0 \times 1.75 \times 0.75 av = 9.1875 m^3$$

$$1 \times 7.0 \times 1.25 \times 0.60 av = 5.25 m^3$$

$$2^{nd} cutting - 2 \times 10.0 \times 1.0 \times 0.60 av = 12.0 m^3$$

$$2 \times 13.0 \times 1.0 \times 0.60 av = 15.60 m^3$$

$$1 \times 9.0 \times 5.0 \times 0.90 av = 40.50 m^3$$

$$\underline{148.3495 m^3}$$

$$@ ₹ 1896.72 / m^3 \quad \text{---} \quad ₹ 281377 = 00$$

- ② construction of embankment with
all complete job.

$$1 \times 13.0 \times 6.75 = 87.75 m^2$$

$$1 \times 7.0 \times 1.75 = 12.25 m^2$$

$$1 \times 7.0 \times 1.25 = 8.75 m^2$$

$$2 \times 10.0 \times 1.0 = 20.0 m^2$$

$$2 \times 13.0 \times 1.0 = 26.0 m^2$$

$$1 \times 9.0 \times 5.0 = 45.0 m^2$$

$$\underline{199.75 m^2}$$

$$@ m^2 - 1 \times 199.75 m^2 \times 0.30 av = 59.925 m^3$$

$$@ ₹ 244.38 / m^3 \quad \text{---} \quad ₹ 14644 =$$

$$\underline{₹ 296021 =}$$

$$\text{Add GST + 4 cess @ 13\% = ₹ 38483 =}$$

$$\underline{₹ 334504 =}$$

By
29/10/21
J.E
RWD (matilahi)

By
29/10/21
A.E
matilahi

By
29/10/21
E.E
RWD (W) Division
Begusarai

Tech in Charge approved for 3,34,500.00 say Three
Lakh, Thirty four thousand five hundred only.

By
10/12/21
T.A

By
10/12/21
अधीक्षक अभियंता
राजीव चंद मिश्रा
जंटे चंपन, प्रमोदी

Inspection Report for flood Damage Work

Date:-

- 1 Name of PIUs- Executive Engineer, R.W.D. Works Division, Begusarai
- 2 Name of Block:- *Motihani*
- 3 Name of Road/ Bridge:- *Jagatpura to Minapur (Ramdini)*
- 4 For Road:- *Yes*
- A Damage Location/Chainage:- *N/A*
- 1 Damage Length:- *82m*
- 2 Nature of Damage:- *Earth work, Road crust*
- 3 Details of Restoration Works:- *Earth work, Back bat*
- 4 Material Being used in Restoration Works:- *Earth work, Back bat*
 - i Equipments/Tools being used in Restoration Works:- *DCB, Roller*
 - ii Procedure taken up in Restoration Works:- *N/A*
 - iii Restored Length:- *82m*
 - iv For Bridge:- *N/A*
- 1 Damage Location/ Chainage:- *N/A*
- 2 Damage Length:- *N/A*
- 3 Nature of Damage:- *N/A*
- 4 Details of Restoration Works:- *N/A*
 - i Material Being used in Restoration Works:- *N/A*
 - iii Equipments/Tools being used in Restoration Works:- *N/A*
 - iii Procedure taken up in Restoration Works:- *N/A*
 - iv Restored Length:-

[Signature]
J.E.

[Signature]
A.E. 5/5/2022

[Signature]
Executive Engineer
R.W.D. Works. Division,
Begusarai

[Signature]

[Signature]
05/05/22

कार्यपालक अभियंता
(Name of Inspector)
प्रमाण कार्य विभाग
कार्य प्रमंडल, रोसड़ा