

RURAL WORKS DEPARTMENT GOVT. OF BIHAR



Name of Work:- Bachhopatti Narha Gachhi Tola (PWD Road) to
Supilgadha Got Pipradhi Inrwa Tola Purani Dhar up to Adhwara.
Block:- Bajpatti.

F.D.R

Rs. 52054.00

35573.00


Year-2021-22.

Name of Circle:- R.W.D. Works Circle, Sitamarhi.

Name of Division:- R.W.D. Works Division, Pupri.

बाढ़ क्षतिग्रस्त पथों का अन्तर प्रमंडलीय जाँच प्रतिवेदन हेतु प्रपत्र

1	निरीक्षी पदाधिकारी का नाम एवं पदनाम:-	ई0 विनोद कुमार साह, कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, सीतामढ़ी।
2	निरीक्षण की तिथि:-	22-12-21
3	पथ का नाम (शीर्ष के साथ)	Bachhobatti Narsha Gachhi Tola (PWD Road) to Supilgadh Ghat Pipradhi Inrwa Tola Purani Dhar upto Adhura
4	पथ की लम्बाई	4.5 KM
5	कार्य प्रमंडल का नाम	ग्रामीण कार्य विभाग, कार्य प्रमंडल, पुपरी।
6	प्रखंड का नाम	बाजपट्टी।
7	पथ की स्थिति	(Completed/Ongoing)
8	पथ अनुरक्षण अवधि में हैं	(Yes/No)
9	क्षतिग्रस्त भाग की लम्बाई	4.1 M
10	क्षतिग्रस्त भाग में कराये गये कार्य का विवरणी (लम्बाई x ऊँचाई x गहराई)	<p>All Mesurment are attached in estimate</p> <p>Qty of Brick Bats :- 16.0904 CUM</p> <p>Qty of Rubbish:- 4.0226 CUM</p> <p>Total Qty :- 20.1130</p> <p>Entered in MB No:- 2703</p> <p>Page No:- 1 to 3</p>
11	अस्थायी पुर्नस्थापन में किस-किस सामग्रीयों को उपयोग किया गया है। उसकी विवरणी	Brick Bats & Rubbish
12	अभ्युक्ति	संतीष पद


 22-12-2021
 निरीक्षी पदाधिकारी का हस्ताक्षर
 पदनाम सहित

DETAILED ESTIMATE FOR F.D.R

General Abstract of Cost

Name of Road:-Bachhopatti Narha Gachhi Tola (PWD Road) to
Supilgadha Got Pipradhi Inrwa Tola Purani Dhar up to Adhwara

Length of Road:- 4.500 Km

Block:-Bajpatti.

District:-Sitamarhi

S. No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	44370.00
2	Labour cess @1%	443.70
3	GST @12%	5324.40
4	Seigniorage Fee @ 10%	1916.32
5	Total Cost of Road Repair	52054.42

Say Rs. ~~52054.00~~


35573=00


JE


AE


E

अभियन्ता-प्रमुख ग्रामीण कार्य विभाग के पत्रांक-4849
दिनांक-07/12/2021 के आदेशानुसार प्रशासनिक
स्वीकृति के प्रत्याशा में औपबंधित तकनीकी स्वीकृति प्रदान
की जा रही है। प्रशासनिक स्वीकृति प्राप्त होने के उपरान्त
पुनः तकनीकी स्वीकृति प्रदान की जायेगी। औपबंधित तकनीकी
स्वीकृति रुपये....355.73=00 (Thirty five thousand five hundred seventy three only.)
की प्रदान की जाती है।



अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, सीतामढ़ी

Schedule of Quantity

Name of Road:-Bachhopatti Narha Gachhi Tola (PWD Road) to Supilgadha Got Pipradhi
Inrwa Tola Purani Dhar up to Adhwara

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	488.11	0.00
2	Providing and laying of Brick Bat obtained from Chimney with machanical means with all spreading, grading to required slope and compacted at OMC to achieve required density with all complete as per the direction of engineer in charge.	20.1130			0.00
	Less 20% for Voids	4.0226		1233=25	27887=0
		16.0904	Cum	2105.01	33870.4529
3	Single bamboo paiasiding/ walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and Struts 1.5m apart longitudinally and providing brush wood as per drawing and technical specification clause 1302.5	0.00	m	140.4	0.00
4	Providing, Laying and placing empty cement bag filled with local sand including stiching with sutall etc. do.....do.....all complete job as per specification and direction of E/I. (including Royalty and all Taxes)	0.00	no.	9.63	0.00
5	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 1000) as per design in Single Row with old available pipe	0.00	m	3400.00	0.00
6	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 600) as per design in Single Row with old available pipe	5.00	m	850.00 835=00	4250.00 4175=00
7	Providing Quarry Material Rabbish for filling the voids in bricks batsdo.....all complete job as per specification and diretion of E/I.				
	Taking 20% of Brick Qty for Rabbish	4.0226	Cum	1553.68 873=02	6249.833168 3511=00
				Total	44370.29
				Say	44370.00 35573=00

[Signature]
JE

[Signature]
AE

[Signature]
PE

Details of Measurement of ditches filled by brick bats and rabbish

Name of Road:-Bachhopatti Narha Gachhi Tola (PWD Road) to Supilgadha Got Pipradhi Inrwa Tola Purani Dhar up to Adhwara

	Nos.	L	W		H		VOLUME
At Primary School Inrwa Tola Pipradhi	1	1.90	5.300	Av	1.000		10.0700
	1	2.20	4.150		1.100		10.0430
		Total (in Cum)					20.1130
Laying Hume Pipe of 1000 mm dia		0	0		0		0.00
Laying Hume Pipe of 600 mm dia	2	2.5	0		0		5.00
Cement Bage							

Handwritten signature
5-11-21

JE

Handwritten signature
5-11-21

AE

Handwritten signature
5-11-21