

क्रमांक 18990 तारीख 20-2-14 मूल्य 1000 साट स...  
 सेवा का नाम एवं पता मनीष कुमार शिवपुरी गढ़नी चौराहा  
 जनादन 18/03/14  
 का. सं. 30/14 निबन्धन कार्यालय, पटना

## AGREEMENT

Date of work order: 03.03.2014  
 Date of completion: 02.12.2014  
 Agreement No. - 18/PM/414/13-14  
 Rate: 5% Below.

This agreement, made 03rd day of March 2014 between Executive Engineer, Rural Work Department, Work Division, Mahnar, [Hereinafter called "the (Manish Kumar, Chitkore, Anishabad, Patna)] hereinafter called "the Contractor of the other part.

Whereas the Employer is desirous that the Contractor execute Const. of Road from Sautaniya Inara Bindu Choudh.

(hereinafter called "the works") and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein, at a cost of Rs. 14669923.00 (One Crore forty six Lakh sixty nine thousand nine hundred twenty three only).

Manish Kumar

*(Signature)*  
 Executive Engineer  
 R.W.D., Works Div., Mahnar  
 3-3-14

Tender Inviting Authority: Engg-In Chief RWD Patna				<input checked="" type="checkbox"/> VALIDATE <input type="checkbox"/> PRINT <input type="checkbox"/> HELP	
Name of Work: Construction of Road from Sautaniya Inara to Bindl Chowk					
Contract No: Civil Works/					
Bidder Name:	Manish Kumar	Less (-)		10.50	%

#### SCHEDULE OF WORKS

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	Setting Out Pillars - Providing & Fixing of Bench Mark Pillars @ four nos per km as per drawings given and direction of E/I	12.00	Nos	1661.40	Rupees One Thousand Six Hundred & Sixty One and Paise Forty Only	19936.80
2.00	Cleaning and Grubbing Road Land ( By manual means) including uprooting wild vegetation , grass	1.39	Ha	34134.48	Rupees Thirty Four Thousand One Hundred & Thirty Four	47446.93
3.00	Removing all types of Hume pipe and stacking within a lead of 1000m including earthwork and				Rupees only	0.00
4.00	A) Upto 600 mm dia	15.00	M	116.42	Rupees One Hundred & Sixteen and Paise Forty Two	1746.30
5.00	Dismantling of cement concrete pavements by mechanical means using pneumatic tools breaking	38.25	cum	1282.24	Rupees One Thousand Two Hundred & Eighty Two and	49045.68
6.00	Construction of embankment with approved material deposited from road way cutting and	106.13	cum	52.24	Rupees Fifty Two and Paise Twenty Four Only	5544.23
7.00	Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including	265.32	cum	63.42	Rupees Sixty Three and Paise Forty Two Only	16826.59
8.00	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m ,				Rupees only	0.00
9.00	For 100 m lead	3239.79	cum	120.94	Rupees One Hundred & Twenty and Paise Ninety Four	391819.72
10.00	For 1000 m lead	1260.73	cum	157.02	Rupees One Hundred & Fifty Seven and Paise Two Only	197959.98
11.00	Construction of granular sub-base by providing well graded material, spreading in uniform layers with	1535.17	cum	2361.44	Rupees Two Thousand Three Hundred & Sixty One and	3625211.84
12.00	Brick Soling Laying brick soling layer on prepared sub-grade	410.00	sqm	440.16	Rupees Four Hundred & Forty and Paise Sixteen Only	180465.60
13.00	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of	578.81	cum	4006.16	Rupees Four Thousand & Six and Paise Sixteen Only	2318805.47
14.00	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound	578.81	cum	3973.59	Rupees Three Thousand Nine Hundred & Seventy Three	2299953.63
15.00	Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface	7717.50	sqm	48.44	Rupees Forty Eight and Paise Forty Four Only	373835.70
16.00	Providing and applying tack coat with bitumen emulsion (RS ) using emulsion distributor @ 0.25	7717.50	sqm	15.86	Rupees Fifteen and Paise Eighty Six Only	122399.55
17.00	Providing , laying and rolling of open graded premix carpet of 20 mm thickness composed of	7717.50	sqm	214.50	Rupees Two Hundred & Fourteen and Paise Fifty Only	1655403.75
18.00	Providing , laying seal coat sealing the voids in a bituminous surface laid to the specified levels	7717.50	sqm	58.10	Rupees Fifty Eight and Paise Ten Only	448386.75
19.00	Construction of un-reinforced , dowel jointed at expansion and construction joint only , plain	613.47	cum	6832.05	Rupees Six Thousand Eight Hundred & Thirty Two and	4191257.71
20.00	Providing Reinforced Cement Concrete M15 grade kilometre stone/local sand of standard design as				Rupees only	0.00
21.00	ordinary K.M post (precast)	3.00	Each	2075.78	Rupees Two Thousand & Seventy Five and Paise Seventy Eight Only	6227.34
22.00	200 mtr stone (precast)	11.00	Each	559.88	Rupees Five Hundred & Fifty Nine and Paise Eighty Eight	6158.68
23.00	Providing and fixing of semi reflective cautionary , mandatory and informatory sign				Rupees only	0.00

*Manish Kumar*  
Signature of Tenderer with seal


Tender Inviting Authority: Engg-in Chief RWD Patna			<input checked="" type="checkbox"/> VALIDATE <input type="checkbox"/> PRINT <input type="checkbox"/> HELP	
Name of Work: Construction of Road from Sautaniya Inara to Bindi Chowk				
Contract No: Civil Works/				
Bidder Name:	Manish Kumar	Loss (-)	10.50	%

#### SCHEDULE OF WORKS

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
24.00	900 mm equilateral & triangle , OR	1.00	Nos	1660.95	Rupees One Thousand Six Hundred & Sixty and Paise	1660.95
25.00	600 mm equilateral & triangle, OR	1.00	Nos	1518.65	Rupees One Thousand Five Hundred & Eighteen and	1518.65
26.00	600 mm circular , OR	1.00	Nos	1581.10	Rupees One Thousand Five Hundred & Eighty One and	1581.10
27.00	800 mm x 600 mm rectangular, OR	1.00	Nos	1677.97	Rupees One Thousand Six Hundred & Seventy Seven	1677.97
28.00	600 mm x 450 mm rectangular, OR	1.00	Nos	1574.71	Rupees One Thousand Five Hundred & Seventy Four and	1574.71
29.00	600 mm x 600 mm, OR	1.00	Nos	1618.96	Rupees One Thousand Six Hundred & Eighteen and	1618.96
30.00	900 mm side octagon, OR	1.00	Nos	1772.38	Rupees One Thousand Seven Hundred & Seventy	1772.38
31.00	Providing and erectig direction and place identification semi reflective sign board as per	3.00	sqm	2059.83	Rupees Two Thousand & Fifty Nine and Paise Eighty	6179.49
32.00	Providing and fixing of typical MGSY inforatory sign board with Logo as per MORD specifications	2.00	Nos	6291.70	Rupees Six Thousand Two Hundred & Ninety One and	12583.40
33.00	Providing and fixing of typical Citizen's Information board with Logo as per MORD specifications and drawing. Two nos. MS Plates of 1.6 mm thick, duly welded with 5mm thick steel plate on back on edges. The four nos. steel plates will be welded horizontally with two nos. 75 mm x 75 mm of 12 SWG sheet tube post duly embedded in cement	1.00	sqm	9500.00	Rupees Nine Thousand Five Hundred Only	9500.00
34.00	Painting lines, dashes, arrows, etc. on roads in two coats on new work with ready mixed road marking	490.00	sqm	90.24	Rupees Ninety and Paise Twenty Four Only	44217.60
35.00	Earth work in excavation of foundation trenches :- Earthwork in excavation for	54.01	cum	163.07	Rupees One Hundred & Sixty Three and Paise Seven Only	8806.76
36.00	Sand Filling in Foundation :- Sand Filling in Foundation Trenches as per drawing and technical specification Clause 1108 - rate as per item No. 11.2 (I) of Chapter 11	5.06	cum	113.70	Rupees One Hundred & Thirteen and Paise Seventy Only	575.44
37.00	Brick Flat Soling in Foundation & Flooring :- Brick Flat Soling in foundation Trenches as per drawing	50.81	cum	230.81	Rupees Two Hundred & Thirty and Paise Eighty One	11726.30
38.00	Plain cement concrete M10 (1:3:6 nominal mix) in levelling course below open foundation of head walls as per drawing and technical specification clause 1109	10.65	cum	5772.62	Rupees Five Thousand Seven Hundred & Seventy Two and Paise Sixty Two Only	61495.72
39.00	Brick Masonary in C.M.(1:4) in Foundation :- Brick masonry work in cement mortar (CM 1:4) in	31.65	cum	4988.65	Rupees Four Thousand Nine Hundred & Eighty Eight and	157890.77
40.00	Maintenance for 1st year	1.00	Year	16287.00	Rupees Sixteen Thousand Two Hundred & Eighty Seven	16287.00
41.00	Maintenance for 2nd year	1.00	Year	18029.00	Rupees Eighteen Thousand & Twenty Nine Only	18029.00
42.00	Maintenance for 3rd year	1.00	Year	20852.00	Rupees Twenty Thousand Eight Hundred & Fifty Two	20852.00
43.00	Maintenance for 4th year	1.00	Year	23675.00	Rupees Twenty Three Thousand Six Hundred &	23675.00
44.00	Maintenance for 5th year	1.00	Year	29320.00	Rupees Twenty Nine Thousand Three Hundred &	29320.00
Total Estimated Cost in Figures						16390975.46
Quoted Amount					14669923.04	14669923.00

*Manish Kumar*  
Signature of Tenderer with seal



Tender Inviting Authority: Engrg in Chief RWD Patna					<input checked="" type="checkbox"/> VALIDATE <input type="checkbox"/> PRINT <input type="checkbox"/> HELP	
Name of Work: Construction of Road from Sautaniya Inara to Bindi Chowk						
Contract No: Civil Works/						
Bidder Name:	Manish Kumar		Less (-)	10.00%		
<b>SCHEDULE OF WORKS</b>						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
Quoted Rate in Words		#NAME?				



Executive Engineer  
J.R.D., Works Div., Mahan

Manish Kumar  
Signature of Tenderer with seal