

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000



Standard Form Agreement
Notes on Standard Form of Agreement
The Agreement should incorporate any corrections of errors (Instructions to
of modification to the Bid resulting Form corrections of errors (Instructions to
Bidders, Clause 26.

D.O. Commencement 30/6/2022

D.O. Completion 29/3/2023

Below-11/-

Agreement: 08MBD/2022-23

This agreement made the.....30..... day of ...6...../2022,
between Executive Engineer, Rural Works Department, (Govt. of
Bihar) Works Division, Simri Bakhtiyarpur (name and address of
Employer) (hereinafter Called "the Employer") of the one part,
M/s PRASUN KUMAR SINGH. Add-Jamuniya. Ward No-04,
Sardiha, S.B.Pur. Simri Bakhtiyarpur. Dist-Saharsa, .Reg. No-
1180182,, Class-Ist Mob-9430250111, PAN No-BHJPS0040P,
GSTIN-10BHJPS0040P2ZC. (hereinafter called "the contractor") of
the other Part.

Whereas as the employer is desirous that the Contractor
execute Name of works under MR-3054 Package No-MR-N/20-21
Simri Bakhtiyarpur/01 In Saharsa District, (Tender ID-113209) and
(Bid Id-485420) (Name and identification number of Contract)
(hereinafter called "the works") and the Employer has accepted the Bid
by the Contractor for the execution and completion of such works and
the Routine maintenance of the work for 5 year the contract period and
remedying of any defects there in at the cost of (Construction cost
Rs.2,97,24,193/- and Maintenance Cost Rs.1,36,13,292/-) Total
Rs.4,33,37,485/- (Four Corer Thirty Three Lakh Thirty Seven
Thousand Four Hundred Eighty Five) Only.

Executive Engineer
R.W.D. Works Division
Simri Bakhtiyarpur

MR-3054

BILL OF QUANTITIES (BOQ)

Name of Road :	Murli Chowk NH-107 to Kuershan	District :	Saharsa		
Block :	Banma Ithari				
Length :	2.20 km				
Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
SCHEDULE A					
1	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	Ha	0.44	56,929.61	25049.03
2	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	Cum	1,980.00	211.53	418829.40
3	<u>Granular Sub-base with Well Graded Material (Grade 2)</u> : Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	Cum	76.41	2,453.63	187481.87
4	<u>Water Bound Macadam with Stone Screening Gr-II</u> : Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	Cum	65.54	4,324.87	283451.98
5	<u>Water Bound Macadam Gr III</u> : Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	Cum	124.19	3,981.30	494437.65

R.W.D. Works Division
Sunribhupur

Approved as Corrected

14/06/24

S.E.

R.W.D. Works Division, Saharsa

Executive Engineer
R.W.D. Works Division

Cross Drainage Works/Protection/Repair				
18	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	Sqm	267.44	107.63
19	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	sqm	93.92	176.69
20	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	cum	10.56	6,054.45
Total				5260429.9
12 % GST				631251.6
1% LABOUR CESS				52604.3
SEIGNIORAGE FEE 10%				47666.7
Total Construction Cost				5991952.6
SCHEDULE B				
21	5 YEAR MAINTENANCE COST	Quarterly	20	124087.10
Total				2481742.0
12 % GST				248174.2
1% LABOUR CESS				297809.0
SEIGNIORAGE FEE 10%				24817.4
Total Maintenance Cost				5558.8
Grand Total Cost (A+B)				2809927.3
				8801879.8



 14/6/14
 Executive Engineer
 R.W.D. Works Division
 Sirgahat, Bihar

Construction Cost Rs-----59,91,952=60
 5 years Maintenance Cost Rs---28,09,927=30


total Amount of B.O.O. Rs---88,01,880=00

BOB Approved for Rs 88,01,880=00 (Eighty Eight
 Lakh one Thousand Eight Hundred Eighty) only

Approved as Corrected


 S.E.
 R.W.D. Works, Circle, Saharua




 30/6/14