

Estimate for Restoration work of Road from Parohi to Khangraitha Road for the year 2021-2022 in Bisfi Block								
Length-4.429 KM								
Sr NO.	Item of Work							
1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching in slope or apron including including light ramming etc. all complete as per approved design,specification and direction of E/I (Brick Bats)							
0.50 km	Nos	Length	Width	Height	Quantity	Unit	Rate	Amounts
1.00 km	1	11.00 ✓	1.00 ✓	0.150 ✓	1.650 ✓			
	1	3.75 ✓	3.00 ✓	0.225 ✓	2.531 ✓			
	1	1.00 ✓	1.00 ✓	0.150 ✓	0.150 ✓			
	1	2.00 ✓	2.00 ✓	0.150 ✓	0.600 ✓			
	1	1.00 ✓	1.00 ✓	0.150 ✓	0.150 ✓			
	1	5.00 ✓	1.50 ✓	0.150 ✓	1.125 ✓			
	1	3.00 ✓	1.50 ✓	0.150 ✓	0.675 ✓			
	1	2.50 ✓	1.25 ✓	0.150 ✓	0.469 ✓			
	1	1.80 ✓	0.60 ✓	0.150 ✓	0.162 ✓			
	1	3.50 ✓	1.25 ✓	0.150 ✓	0.656 ✓			
	1	2.50 ✓	1.25 ✓	0.150 ✓	0.469 ✓			
	1	11.00 ✓	1.50 ✓	0.150 ✓	2.475 ✓			
	1	2.50 ✓	1.25 ✓	0.150 ✓	0.469 ✓			
	1	3.00 ✓	1.25 ✓	0.150 ✓	0.563 ✓			
	1	1.50 ✓	1.25 ✓	0.150 ✓	0.281 ✓			
	1	3.00 ✓	1.00 ✓	0.150 ✓	0.450 ✓			
	1	3.00 ✓	1.25 ✓	0.150 ✓	0.563 ✓			
	1	2.50 ✓	1.00 ✓	0.150 ✓	0.375 ✓			
	1	5.00 ✓	1.00 ✓	0.150 ✓	0.750 ✓			
	1	3.00 ✓	1.50 ✓	0.450 ✓	2.025 ✓			
1	4.00 ✓	3.50 ✓	0.150 ✓	2.100 ✓				
					18.687 ✓	Cum	1939.93	36251
Add 12% GST					=Rs			4350
Add 1% L/Cess					=Rs			363
Add Signorage Fee(18.687x1032x10%)					=Rs			1928
total					=Rs			42893

20-11-21
J E
R W D
Bisfi

20/11/21
A E
R W D
Bisfi

27/11/21
E E
R W D
Benipatti

Verified and found correct.

Damaged length = 75.55 metre.

Restored Qty = 18.687 m³

27/11/21
SE

27/11/2021
AS

27/11/21

Ins]

of 12

2 of

2 of

100

I

I

Name of Road:- Parohi to Khangaitla
Road.

Post facto T/S awarded for Rs. 42893.00
(Rs. Forty two thousand eight hundred ninety
three only.)

Reference letter no. 233 dated 21/2/22


Superintending Engineer
RWD Works Circle, Darbhanga



Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 27.11.2021
to 05.12.2021 Name of PIU :- RWD (W) Div. Darbhanga-2
(Inspected).

Name of Block/PIU :- Bisbi (RWD(W) Div. Benipatti)

Name of Road :- Parahi to Khengraitha.

For Road :-

1. Damage Location/ Chainage :- In between ch 0.500KM to ch 1.00KM.

2. Damage Length :- 75.55 mtr.

3. Nature of Damage

:- Due to heavy flood pot-patch developed.

4. Details of Restoration Works :-

i. Material being used in Restoration Works :- Brick bats.

ii. Equipment's/ Tools being used in Restoration Works :- Tractor & Roller.

iii. Procedure taken up in Restoration Works :- section wise restoration work initiated / completed.

iv. Restored Length :- 75.55 mtr.

Remarks :-

Signature of JE/AE
19/10/2022

JE

Signature of E.E.
19/10/22