



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Work Department, Government of Bihar

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Jhanjharpur

Estimate for Mortable of the Road from L049-L039 TO
MAHINATHPUR (VR049) under FDR at Block- Jhanjharpur
in Madhubani District.

TOTAL COST FOR MOTORABLE Rs.

~~4.62752 lac~~
~~7.15853 lac.~~

4.62187

Submitted by:

Executive Engineer

RWD(W) Division, Jhanjharpur

तकनीकी प्रतिवेदन

पथ का नाम :- 1049-1039 TO Mahinathpur (VR049)

प्राक्कलित राशि :- 7.15853 लघु 4-62355 लघु 4 62182

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक 1049-1039 TO Mahinathpur (VR049) पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था। फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/ मिट्टी/ स्थानीय बालु से भरकर उसका संपीड़न किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है।



कनीय अभियंता



सहायक अभियंता



कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Jhanjharpur

Name of Road :- L049 - L039 TO Mahinathpur (NR049)

A. For Road


1. Damage Location Chainage :- 200M, 400M, 600M, 800M, 1000M, 1200M
2. Damage Length :- 123.65M
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:- Bricks bat &
 - ii. Equipment's/Tools being used in Restoration works:- tractor & tool
 - iii. Procedure taken up in Restoration works:- 195.114m³
 - iv. Restored Length:- 123.65 M

B. For Bridge

1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required: S


95/4/22
Signature of JE/AE/EE


20/4/22
ER


Signature
(Name of Inspection)

estimate for Motorability of road damaged by flood from L049-L039 TO MAHINATHPUR
(VR049) For Year 2021

FDR 2245

Length :- 1.521 km

Item No.	Name of Item	Unit	Quantity As per Appendix - 1	Rate	Amount
	Providing and filling brick bats in ditches/ damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/l.	Cum	$\frac{301.81}{195.114}$	2004.96	$\frac{605106.95}{391195.77}$

391195.77
 $\text{Add } 12\% \text{ GST } ₹ 46943.49$
 $\text{Add } 1\% \text{ L.C } ₹ 3911.96$
 $\text{Add S. Fee } (282.96 \times 1063.00) \times 10\% ₹ 30081.87$
 195.114×1032
 $\text{Total } ₹ 462187.87$
 $\text{Say } ₹ 462187$

85/11/21

Junior Engineer
R.W.D. Works Section,
Jhanjharpur

05/11/21

Assistant Engineer
R.W.D. Work sub Div.
Jhanjharpur

05/11/21

Executive Engineer
R.W.D (W) Division.
Jhanjharpur

कार्यपालक अभियंता राब कार वि०, जयनगर के द्वारा
आचार्य पत्रांक 671(अनु०) दि० 29/04/22 के आधार पर

Technically sanctioned Rs 462187=00 (Rupees Four
Lakh Sixty Two thousand one hundred eighty seven) only.

Superintending Engineer
R.W.D. Circle, Darbhanga

Abhinav
05/05/22

Name of Road :- L049- L039 to Mahinathpur

PMGSY

Length :- 1.521 km

Block :- Jhanjharpur

Appendix - I

**Measurement for restoration of Embankment and shoulder with Brick Bat
(Measurement in mtr.)**

Chainage	Nos.		Length (in Mtr.)		Bidth (in Mtr.)		Thickness (in Mtr.)			Quantity	
ch.200-400	1	x	12.20	x	(0.7+1.8)/2	x	1.25	(1.40+1.60)/2	1.50	av.	= 22.88 cum
ch.200-400	1	x	20.40	x	(1.0+1.0+0.60)/3	x	0.87	(1.60+1.80)/2	1.70	av.	= 34.65 cum
ch.400-500	1	x	3.00	x	(0.4+1.9)/2	x	1.15	(0.90+1.20)/2	2.40	av.	= 8.78 cum
ch.600-800	1	x	3.80	x	(0.45+1.85)/2	x	1.15	(0.90+1.10)/2	1.00	av.	= 4.37 cum
ch.600-800	1	x	17.70	x	(0.85+1.90)/2	x	1.375	(1.40+1.90+2.20)/3	2.20	av.	= 53.54 cum
ch.800-1000	1	x	16.00	x	(3.0+2.6+3.5)/3	x	3.03	(0.40+0.55+0.75)/3	0.90	av.	= 43.68 cum
ch.800-1000	1	x	30.00	x	(3.10+2.7+2.5)/3	x	2.77	(0.40+0.55+0.75)/3	1.10	av.	= 91.39 cum
ch.1000-1200	1	x	7.80	x	(3.10+2.6+2.4)/3	x	2.70	(0.40+0.55+0.75)/3	1.20	av.	= 25.27 cum
ch.1200-1300	1	x	9.00	x	(0.90+1.60)/2	x	1.25	(1.50+2.0+1.85)/3	1.783	av.	= 20.06 cum
ch.1300-1400	1	x	1.80	x	1.20	x	1.20	(0.40+0.60)/2	0.500	av.	= 1.08 cum
ch.1400-1500	1	x	1.95	x	1.10	x	1.10	(0.50+0.70)/2	0.60	av.	= 1.29 cum
Total qty.										= 301.81	cum

9.15
25.62
8.28
4.37
44.53
27.14
47.32
8.424
16.87
1.08
1.29
195.1144

25/4/22
25/4/22

8/5/11/21

Junior Engineer
W.D. Works Section.
Jhanjharpur

8/5/11/21

Assistant Engineer
R.W.D. Work sub Div.
Jhanjharpur

25/4/22

Executive Engineer
R.W.D (W) Division.
Jhanjharpur

25/4/22
25/4/22

25/4/22