



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

158

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Jhanjharpur

Estimate for Mortable of the Road from Nawani hanuman mandir to yadav tol Road **FDR** at **Block- Jhanjharpur** in Madhubani District.

TOTAL COST FOR MOTORABLE Rs.

~~1-78116 lac~~

5.00804 lac.

1-97857 lac

Submitted by:

Executive Engineer

RWD(W) Division, Jhanjharpur

तकनीकी प्रतिवेदन

पथ का नाम :- Nawani-Hannuman mandir to yadav tal.

प्राक्कलित राशि :- ~~1.98116 lac~~ 1.97857 lac

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक Mawani' Hannuman
Mandir to Yadav tal Road पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईंट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीड़न किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।


कनीय अभियंता


सहायक अभियंता


कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- *Jhanjharpur*

Name of Road :- *Nawani Harnam Mandir to Yadav-Jal Road*

A. For Road

1. Damage Location Chainage :-
2. Damage Length :- *222.00 m*
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:- *Borcu bnts*
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:- *83.526 m³*
 - iv. Restored Length:- *222.00 m*

B. For Bridge

1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:-

[Signature]
5/5/22

Signature of JE/AE/EE

[Signature]
24/4/22
BR

'S'

[Signature]
WTA/22

Signature
(Name of Inspection)


Estimate for Motorability of road damaged by flood from Nawani Muswa Pakar Gachhi To Sirkhariya Road For Year 2021

lead :- MMGSY[SC]

Length :- 0.7 km

SI No.	Item No.	Name of Item	Unit	Quantity As per Appendix - I	Rate	Amount
1		Providing and filling brick bats in ditches/damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/L.	Cum	211.14 83.526	2004.96	423327.25 167466.29

₹ 167466.29
 423327.25
 Add 12 % GST ₹ 20095.75
 50799.27
 Add 1 % L.C ₹ 1032.00
 83.526
 Add S. Fee (211.14 x 1063.00) x 10 % ₹ 22444.18
 8019.28
 Total ₹ 500803.98
 Say ₹ 500804.00
 197857


 Junior Engineer
 R.W.D. Works Section.
 Jhanjharpur


 Assistant Engineer
 R.W.D. Work sub Div.
 Jhanjharpur


 Executive Engineer
 R.W.D (W) Division.
 Jhanjharpur

कार्यालयक उम्मीदना, गांव का कि, जगनगर के द्वारा
 बांँपयशोर पाँक - 674 (अब) दिनांक - 29/04/22 के आधार पर
 Technically Sanctioned for Rs-197857.00 (Rupees
 One lakh Ninty seven thousand eight hundred fifty
 seven) only.


 Superintending Engineer
 RWD Work Circle, Darbhanga
 Abhinav
 05/05/22

Name of Road :- Nawani Muswa Pakar Gachhi ToSirkhariya

Length :- 0.7 km

Block :- Jhanjharpur

x - I

Measurement for restoration of Embankment and shoulder with Brick Bat
(Measurement in mtr.)

Chainage	Nos.		Length (in Mtr.)		Bldth (in Mtr.)		Thickness (in Mtr.)			Quantity	
CH. 100M	1	x	25.00	x	3.10	x	0.30	0.30	av.	= 88.35	cum
CH. 200M	1	x	29.00	x	3.30	x	0.30	0.30	av.	= 28.71	cum
CH. 300M	1	x	98.00	x	3.20	x	0.30	0.30	av.	= 94.08	cum
Total qty.										= 211.14	cum

14.88
28.71
39.93
83.526 m
Jhanjharpur

Junior Engineer
R.W.D, Works Section.
Jhanjharpur

Assistant Engineer
R.W.D, Work sub Div.
Jhanjharpur

Executive Engineer
R.W.D (W) Division,
Jhanjharpur

25/04/22
J.E.

2/2019